



CALIFORNIA RANCH



COTTAGE



MODERN

WALNUT CREEK ACCESSORY DWELLING UNIT - PLAN 1

PROJECT ADDRESS: _____

PROJECT DIRECTORY

(TO BE PROVIDED BY APPLICANT OR OWNER)

APPLICANT

ADDRESS: _____
CONTACT: _____
EMAIL: _____
PHONE: _____

OWNER


ADDRESS: _____
CONTACT: _____
EMAIL: _____
PHONE: _____

ARCHITECT

RRM DESIGN GROUP

ADDRESS: 3765 S Higuera St, Suite 102
SAN LUIS OBISPO, CA 93401
CONTACT: RANDY RUSSOM
EMAIL: RVRUSSOM@RRMDDESIGN.COM
PHONE: P:(805) 543-1794

CALGREEN CODE CHECKLIST



Revised June 9, 2017

Information Bulletin No. IB-35

Residential CalGreen Code Checklist

Project designer may use this checklist to indicate sheet number on the project plans showing compliance with CALGREEN code sections for all new residential structures (RNEW).

This guideline also identifies which city division has responsibility for plan check and inspection for the listed sections of the California Green Building Standards Code. B: Building Division; C: Current Engineering Division; P: Planning Division.

When using this checklist, reviewer or inspector place a check mark ✓ next to the division letter; reviewer circle the appropriate letter E or B to indicate which division will do the inspection.

Permit No.	Reviewed by:		Primary responsibility (office use)	
Code Section	Section Title	Sheet Number	Plan check	Inspection
4.106	Site Development 2 Storm water during construction 2 Grading and paving 4 Electric vehicle charging	AS-101	E	E/B
4.201	Energy Efficiency 1 Use California Energy Code standards	G-201, G-202, T24	B	B
4.303	Indoor Water Use 1 Water conserving plumbing fixtures and fittings 2 Plumbing fixtures and fittings	G-201, G-202, T24, A-101	B	B
4.304	Outdoor Water Use 1 Outdoor potable water use in landscape areas	G-201, G-202, AS-101	E	E/B
4.406	Enhanced Durability & Reduced Maintenance 1 Rodent proofing	G-201, G-202	B	B
4.408	Construction Waste Reduction, Disposal & Recycling 1 Construction waste reduction 65 percent	G-201, G-202	B	B
4.410	Building Maintenance & Operation 1 Operation & maintenance manual 2 Recycling by occupants	G-201, G-202	B	B
4.403	Fireplaces 1 EPA Phase II emission limits		B	B
4.504	Pollutant Control 1 Cover dusts, protect mech equip during construction 2 Finish material 3 Carpet systems 4 Resilient flooring systems 5 Composite wood products	G-201, G-202, A-111 A-201, A-202, A-203	B	B
4.505	Interior Moisture Control 2 Concrete slab foundations 3 Moisture content of building materials	G-201, G-202	B	B
4.506	Indoor Air Quality and Exhaust 1 Radon/entry exhaust fans	G-201, G-202, A-111	B	B
4.507	Environmental Comfort 2 Heating and A/C system design	G-201, G-202, A-111	B	B

* For inspection items with E/B, Engineering Division will inspect when a site development permit is issued, otherwise Building Division will inspect.

SUPPORTING DOCUMENTS

ALL PRADU PLAN USERS MUST SUBMIT A COMPLETED LIABILITY AGREEMENT FORM AT THE TIME OF APPLICATION SUBMITTAL.

SIGNED USER LICENSE AGREEMENT? ☐ YES ☐ NO

STAFF INITIALS: _____

ENERGY COMPLIANCE

PREPARED BY: CARSTAIRS ENERGY
DATE PREPARED: FEBRUARY 06, 2023
JOB NUMBER: 23-02066

PROJECT INFORMATION

PROJECT SCOPE:

- CONSTRUCTION OF A NEW DETACHED 1 STORY 408 SF ACCESSORY DWELLING UNIT WITH 1 BEDROOMS AND 1 BATH.
- ALL SITE WORK WITHIN THE PROPERTY LINE.
- ALL THE WORK SHOWN IN THE DRAWINGS AND SPECIFICATIONS.

(TO BE PROVIDED BY APPLICANT OR OWNER)

SITE INFORMATION:

APN: _____
ZONING: _____
LOT SIZE: _____
LAND USE: _____
EXISTING USE: _____
PROPOSED USE: _____
BUILDING: _____
HARDSAPCE/PAVING: _____
LANDSCAPE: _____

SETBACKS	REQUIRED MINIMUM	PROPOSED
FRONT:		
REAR:	4' - 0" (A.B. NO. 86)	
SIDES:	4' - 0" (A.B. NO. 86)	
BETWEEN STRUCTURES:	10' - 0"	

IS THE ADU 5' - 0" OR LESS TO ANY PROPERTY LINE AND/OR IS THE ADU 10' - 0" OR LESS FROM ANY ADJACENT BUILDING OR STRUCTURE?

☐ NO

☐ YES; IF YES, FIRE RATED WALL & PROJECTIONS REQUIRED PER 2022 CBC, CHAPTER 2, FIRE RATED WALL DETAIL: 52/A-901
IF YES, FIREBLOCKING IS REQUIRED IN PROJECTIONS, RAKES AND EAVES. SEE DETAILS: 24/A-903 31/A-912, 32/A-912, 31/A-922, 32/A-922, 31/A-932, 32/A-932

ADDITIONALLY, 1-HOUR FIRE RATED PROJECTION NOTES ARE APPLICABLE ON DETAILS: 52/A-931, 42/A-903, 34/A-903

UTILITIES

WATER AND SEWER SERVICE: CONTRA COSTA WATER DISTRICT
ELECTRICAL SERVICE: PACIFIC GAS AND ELECTRIC
GAS SERVICE: PACIFIC GAS AND ELECTRIC
SEWER SERVICE: EBMUD, CENTRAL SANITARY DISTRICT
GARBAGE SERVICE: REPUBLIC SERVICES
CABLE SERVICE: _____

BUILDING AREAS

PLAN 1 - STUDIO

AREA: 408 SF

FRONT PORCH: 72 SF

PROJECT CHECKLIST

*FOR BUILDING DEPARTMENT REVIEW, INITIAL WHEN SECTION HAS BEEN REVIEWED

STAFF INITIALS:

WASTE WATER *FILLED IN BY OWNER OR APPLICANT

- ☐ SEWER
☐ SEPTIC (REQUIRES APPROVAL)

FIRE SPRINKLERS

DOES THE PRIMARY RESIDENCE HAVE NFPA 13D SPRINKLERS?

- ☐ NO (NOT REQUIRED IF THE PRIMARY RESIDENCE IS UNSPRINKLERED)
☐ YES (REQUIRED IF THE PRIMARY RESIDENCE IS SPRINKLERED)
- REQUIRED AT PROPOSED ADU:
- ☐ NO (NOT REQUIRED IF THE PRIMARY RESIDENCE IS UNSPRINKLERED)
☐ YES (REQUIRED IF THE PRIMARY RESIDENCE IS SPRINKLERED)

ELECTRICAL PANEL (SEE SITE PLAN FOR LOCATION):

- ☐ OPTION 1 NEW ELECTRICAL MAIN PANEL OF 200 AMP WITH 225 AMP MINIMUM BUSBAR RATING
A NEW ELECTRICAL SUBPANEL CONNECTS TO THE ELECTRICAL MAIN PANEL OF THE PRIMARY HOME. A SEPARATE ELECTRICAL PERMIT SHALL BE PULLED FOR THE ELECTRICAL MAIN PANEL OF THE PRIMARY HOME, ELECTRICAL LOAD CALCULATIONS ARE REQUIRED.
- ☐ OPTION 2

FIRE SPRINKLERS NOTES

WHEN SPRINKLERS ARE REQUIRED PER "PRE-APPROVED ADU PLANS APPLICATION FORM":

- DETAILED SPRINKLER PLANS SHALL BE SUBMITTED TO THE FIRE PREVENTION BUREAU AND APPROVED PRIOR TO INSTALLATION. PLANS AND INSTALLATION MUST BE BY A C16 LICENSED SPRINKLER CONTRACTOR.
- SECTION 903.3.1.3 NFPA 13D SPRINKLER SYSTEMS AUTOMATIC FIRE SPRINKLER SYSTEMS INSTALLED IN ONE- AND TWO-FAMILY DWELLINGS, GROUP R-3.
- SECTION 903.2.8 GROUP R-3 AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3 SHALL BE PROVIDED THROUGHOUT ALL BUILDINGS WITH A GROUP R FIRE AREA.
- SECTION 903.2.8.1 GROUP R-3 AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3.1.3 SHALL BE PERMITTED IN GROUP R-3 OCCUPANCIES.
- LOCATION AND SIZE OF WATER SERVICE UNDERGROUND SHALL BE INSTALLED AS SHOWN ON APPROVED FIRE SPRINKLER PLANS. A MINIMUM 1 INCH WATER SHALL BE INSTALLED.
- A FIRE UNDERGROUND FLUSH CERTIFICATION SHALL BE REQUIRED AT FINAL INSPECTION.
- A HYDRO INSPECTION OF THE FIRE SPRINKLER SYSTEM IS REQUIRED PRIOR TO FRAME INSPECTION. ONLY THE NEW PIPING SHALL BE TESTED.

PROJECT INFORMATION

*FOR BUILDING DEPARTMENT REVIEW, INITIAL WHEN SECTION HAS BEEN REVIEWED

STAFF INITIALS:

BUILDING INFORMATION:

NUMBER OF STORIES: 1
OCCUPANCY GROUP: R-3
CONSTRUCTION TYPE: VB
SPRINKLERED: SEE FIRE SPRINKLER SECTION ON SHEET
MAX. HEIGHT ALLOWED: 16' - 0"
MAX. HEIGHT PROPOSED: 15' - 6"

ADDITIONAL INFORMATION

- ANY PROPOSED ENERGY STORAGE SYSTEM (ESS) SHALL FOLLOW SINGLE-FAMILY RESIDENTIAL MANDATORY REQ. SUMMARY SECTION 150.0(s) AND WILL REQUIRE A SEPARATE PERMIT TO BE PULLED BY APPLICANT.
- VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION (VERIFICATION DETAILS FROM VCHP STAFF REPORT, APPENDIX B, AND RA3) (PER TITLE 24).
- NORTHWEST ENERGY EFFICIENCY ALLIANCE (NEEA) RATED HEAT PUMP WATER HEATER, SPECIFIC BRAND/MODEL, OR EQUIVALENT, MUST BE INSTALLED (PER TITLE 24).
- THIS PLAN IS INTENDED FOR FLAT LOTS (FALLING LESS THAN 10' ACROSS THE LONGEST BUILDING DIMENSION OR 5% WHICHEVER IS THE LEAST), WITHOUT HIGHLY EXPANSIVE OR LIQUEFIABLE SOILS AND NOT IN DESIGNATED FLOOD ZONE, WHERE THE MAIN DWELLING UNIT IS SUPPORTED IN SHALLOW FOOTINGS WITH SLABS ON GRADE CONSTRUCTION. IF THE PROJECT SITE DEVIATES FROM ANY OF THE AFOREMENTIONED QUALITIES, AS DETERMINED BY THE BUILDING OFFICIAL, THERE PRE-APPROVED ADU FOUNDATION PLANS AND DETAILS ARE NOT APPLICABLE.

USER LICENSE AGREEMENT

OWNER/APPLICANT TO SIGN & SUBMIT SEPARATE SUPPORTING DOCUMENT "USER LICENSE AGREEMENT" IN ADDITION TO SIGNING THIS USER AGREEMENT BELOW:

BY USING THESE PERMIT READY ACCESSORY DWELLING UNIT CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE, HOLD HARMLESS, AND INDEMNIFY THE CITY OF WALNUT CREEK, ITS ELECTED OFFICIALS AND EMPLOYEES, RRM DESIGN GROUP, AND THE ARCHITECT OR ENGINEER WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.

THE PLANS ATTACHED HERE ARE APPROVED FOR ONLY USE IN CITY OF WALNUT CREEK. NO DEVIATIONS, ALTERATIONS, OR OPTIONS BEYOND THOSE SPECIFICALLY INDICATED IN THE PLANS ARE ALLOWED WITHOUT PRIOR APPROVAL BY THE ISSUING JURISDICTION AND CHIEF BUILDING OFFICIAL. ANY UNAPPROVED PLAN MODIFICATIONS MAY BE DEVELOPED THROUGH RRM DESIGN GROUP AND THE APPROVING JURISDICTION IF REQUIRED. THIS SET OF PLANS SHALL NOT BE USED FOR A PUBLIC HOUSING PROJECT.

SIGNATURE

DATE

SHEET INDEX

G-001	TITLE SHEET
G-101	GENERAL NOTES
G-102	SHEET INDEX, ABBREVIATIONS & SYMBOLS
G-201	CAL. GREEN RESIDENTIAL REQUIREMENTS
G-202	CAL. GREEN RESIDENTIAL REQUIREMENTS

AS101 ARCHITECTURAL SITE PLAN (EXAMPLE & INSTRUCTIONS)

A1-100	RENDERINGS
A1-101	FLOOR PLAN 1
A1-111	FINISH, MECHANICAL, & ELECTRICAL PLANS

A1-121	ROOF PLAN & REFLECTED CEILING PLAN - CAL RANCH
A1-122	ROOF PLAN & REFLECTED CEILING PLAN - COTTAGE
A1-123	ROOF PLAN & REFLECTED CEILING PLAN - MODERN

A1-201	ELEVATIONS & BUILDING SECTIONS - CAL RANCH
A1-202	ELEVATIONS & BUILDING SECTIONS - COTTAGE
A1-203	ELEVATIONS & BUILDING SECTIONS - MODERN


A-901	ARCHITECTURAL DETAILS - COMMON
A-902	ARCHITECTURAL DETAILS - COMMON
A-903	ARCHITECTURAL DETAILS - COMMON ROOF
A-911	ARCHITECTURAL DETAILS - CALIFORNIA RANCH
A-912	ARCHITECTURAL DETAILS - CALIFORNIA RANCH - ROOF
A-913	ARCHITECTURAL DETAILS - CALIFORNIA RANCH
A-921	ARCHITECTURAL DETAILS - COTTAGE
A-922	ARCHITECTURAL DETAILS - COTTAGE - ROOF
A-931	ARCHITECTURAL DETAILS - MODERN
A-932	ARCHITECTURAL DETAILS - MODERN - ROOF

S-101	SHEET INDEX, ABBREVIATION & SYMBOLS
S-102	GENERAL NOTES
S-103	GENERAL NOTES, SPECIAL INSPECTION & TESTS
S-201	FOUNDATION PLAN
S-202	ROOF FRAMING PLAN
S-301	TYPICAL CONCRETE DETAILS
S-311	CONCRETE DETAILS
S-312	CONCRETE DETAILS
S-401	TYPICAL WOOD DETAILS
S-402	TYPICAL WOOD DETAILS
S-403	TYPICAL WOOD DETAILS
S-421	ROOF FRAMING DETAILS

T24-101	ENERGY COMPLIANCE - PLAN 1
T24-102	ENERGY COMPLIANCE - PLAN 1
T24-103	ENERGY COMPLIANCE - PLAN 1
Grand total: 40	

VICINITY MAP (TO BE PROVIDED BY OWNER OR APPLICANT)

VICINITY MAP (TO BE PROVIDED BY OWNER OR APPLICANT)



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK

TITLE SHEET



DATE
02/10/2023

SHEET

G-001

ABBREVIATIONS

A/C	AIR CONDITIONING	EXP	EXPANSION	LVT	LUXURY VINYL TILE	SCHED	SCHEDULE
ABV	ABOVE	EXT	EXTERIOR	LW	LIGHTWEIGHT	SEAL	SEALANT
ACOUS	ACOUSTICAL	FACP	FIRE ALARM CONTROL PANEL	MAX	MAXIMUM	SECT	SECTION
ACT	ACOUSTICAL CEILING TILE	FAU	FORCED AIR UNIT	MDF	MEDIUM DENSITY FIBERBOARD	SF	SQUARE FOOT
ADA	AMERICANS WITH DISABILITIES ACT	FAWP	FLUID APPLIED WATERPROOFING	MECH	MECHANICAL	SHT	SHEET
AFCI	ARC FAULT CIRCUIT INTERRUPTER	FD	FLOOR DRAIN	MEMB	MEMBRANE	SHTHG	SHEATHING
AFF	ABOVE FINISH FLOOR	FDC	FIRE DEPARTMENT CONNECTION	MEP	MECHANICAL, ELECTRICAL, PLUMBING	SIM	SIMILAR
AL	ALUMINUM	FE	FIRE EXTINGUISHER	MFR	MANUFACTURER	SM	SHEET METAL
ALT	ALTERNATE	FEC	FIRE EXTINGUISHER CABINET	MIN	MINIMUM	SPEC	SPECIFICATION
ARCH	ARCHITECT(URAL)	FF	FINISHED FLOOR ELEVATION	MISC	MISCELLANEOUS	SQ	SQUIRE
BD	BOARD	FG	FINISHED GRADE	MO	MASONRY OPENING	SS	SOLID SURFACE
BDRM	BEDROOM	FH	FIRE HYDRANT	MTD	MOUNTED	SSTL	STAINLESS STEEL
BET	BETWEEN	FHC	FIRE HOSE CABINET	MTL	METAL	STC	SOUND TRANSMISSION CLASS
BIT	BITUMINOUS	FIN	FINISH	N	NORTH	STD	STANDARD
BLDG	BUILDING	FIXT	FIXTURE	NIC	NOT IN CONTRACT	STL	STEEL
BLKG	BLOCKING	FLR	FLOOR	NO	NUMBER	STOR	STORAGE
BLW	BELOW	FLUOR	FLUORESCENT	NOM	NOMINAL	STRUCT	STRUCTURAL
BM	BEAM	FND	FOUNDATION	NTS	NOT TO SCALE	SUSP	SUSPENDED
BOT	BOTTOM	FO	FACE OF	O.P.	OVERFLOW PIPE	SV	SHEET VINYL
BUR	BUILT UP ROOF	FOC	FACE OF CONCRETE	OC	ON CENTER	SYM	SYMMETRICAL
CB	CATCH BASIN	FOF	FACE OF FINISH	OD	OVERFLOW DRAIN	T	TREAD
CBC	CALIFORNIA BUILDING CODE	FOIC	FURNISHED BY OWNER INSTALLED BY CONTRACTOR	OFF	OFFICE	T&G	TONGUE & GROOVE
CEM	CEMENT	FOM	FACE OF MASONRY	OH	OPPOSITE HAND	TEL	TELEPHONE
CFM	CUBIC FEET PER MINUTE	FOS	FACE OF STUD	OPG	OPENING	TEMP	TEMPERED
CIP	CAST IN PLACE	FRP	FIBERGLASS REINFORCED PANELS	OPP	OPPOSITE	TER	TERRAZZO
CJ	CONTROL JOINT	FT	FOOT OR FEET	(P)	PROPOSED	THK	THICK
CL	CENTER LINE	FTG	FOOTING	PERM	PERIMETER	THR	THRESHOLD
CLG	CEILING	GA	GAUGE, GAGE	PERP	PERPENDICULAR	TJI	TRUSS JOIST I-JOIST
CLO	CLOSET	GB	GALVANIZED	PG	PAINT GRADE	TO	TOP OF
CLR	CLEAR	GALV	GALVANIZED	PL	PLATE, PROPERTY LINE	TOS	TOP OF SLAB
CMU	CONCRETE MASONRY UNIT	GC	GENERAL CONTRACTOR	PLAM	PLASTIC LAMINATE	TOW	TOP OF WALL
CO	CLEAN OUT	GCI	GROUND FAULT CIRCUIT INTERRUPTER	PLBG	PLUMBING	TRANS	TRANSFORMER
COL	COLUMN	GWB	GYP	PLYWD	PLYWOOD	TV	TELEVISION
CONC	CONCRETE	GYP	GYP	PNL	PANEL	TYP	TYPICAL
CONST	CONSTRUCTION	HB	HOSE BIBB	PP	POWER POLE	UFAS	UNIFORM FEDERAL ACCESSIBILITY STANDARDS
CONT	CONTINUOUS	HC	HOLLOW CORE	PR	PAIR	UG	UNDERGROUND
CONTR	CONTRACTOR	HDWD	HARDWOOD	PRTN	PARTITION	UNFIN	UNFINISHED
CPT	CARPET	HDWR	HARDWARE	PSF	POUNDS PER SQUARE FOOT	UNO	UNLESS NOTED OTHERWISE
CT	CERAMIC TILE	HGT	HEIGHT	PSI	POUNDS PER SQUARE INCH	UV	ULTRAVIOLET
CTR	CENTER	HM	HOLLOW METAL	PSL	PARALLEL STRAND LUMBER	VCT	VINYL COMPOSITION TILE
DBL	DOUBLE	HORIZ	HORIZONTAL	PT	PRESSURE TREATED	VERT	VERTICAL
DF	DRINKING FOUNTAIN	HVAC	HEATING, VENTILATION, A/C	PTD	PAINTED	VIF	VERIFY IN FIELD
DIA	DIAMETER, DIAPHRAGM	ID	INSIDE DIAMETER	PV	PHOTO VOLTAIC	VTR	VENT TERMINATION PIPE
DIM	DIMENSION	IJC	IMPACT INSULATION CLASS	PVC	POLYVINYL CHLORIDE	VWC	VINYL WALL COVERING
DN	DOWN	IN	INCH	PVMT	PAVEMENT	W	WEST
DR	DOOR	INCAND	INCANDESCENT	QTY	QUANTITY	W/	WITH
DS	DOWN SPOUT	INSUL	INSULATION, INSULATED	R	RADIUS, RISER	WD	WASHER DRYER
DTL	DETAIL	INT	INTERIOR	RB	RUBBER BASE	WO	WITHOUT
DW	DISHWASHER	JC	JANITORS CLOSET	RCP	REFLECTED CEILING PLAN	WC	WATERCLOSET
DWG	DRAWING	JT	JOINT	RD	ROOF DRAIN	WD	WOOD
(E)	EXISTING	LAM	LAMINATE	REF	REFRIGERATOR	WDW	WINDOW
E	EAST	LAV	LAVATORY	REINF	REINFORCED	WH	WATER HEATER
EA	EACH	LBS	POUNDS	REQD	REQUIRED	WI	WROUGHT IRON
EJ	EXPANSION JOINT	LEED	LEADERSHIP IN ENERGY AND ENVIRONMENTAL DESIGN	RH	RIGHT HAND	WIN	WINDOW
EL	ELEVATION	LF	LINEAR FEET	RM	ROOM	WP	WATERPROOF(ING)
ELEV		LIN	LINEN CLOSET	RO	ROUGH OPENING	WR	WEATHER RESISTIVE
ELEC	ELECTRIC	LINO	LINOLEUM	RTU	ROOF TOP UNIT (MECH)	WRB	WATER RESISTIVE BARRIER
ENCL	ENCLOSURE	LT(G)	LIGHT(ING)	S	SOUTH	WSCT	WAINSCOT
EQ	EQUAL	LVL	LAMINATED VENEER LUMBER	SAFB	SOUND ATTENUATION FIBER BATT	WT	WEIGHT
EQUIP	EQUIPMENT			SAWP	SELF ADHEREING WATERPROOFING	WWF	WELDED WIRE FABRIC
EXH	EXHAUST			SC	SCUPPER/SOLID CORE	YD	YARD



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK

SHEET INDEX, ABBREVIATIONS & SYMBOLS


DATE
02/10/2023

SHEET

G-102

SITE PLAN TO BE PROVIDED BY APPLICANT

SITE PLAN LEGEND



SITE PLAN GENERAL NOTES

1. REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS
2. REFER TO STRUCTURAL PLANS FOR FURTHER INFORMATION
3. EMERGENCY ESCAPE AND RESCUE OPENINGS SHALL OPEN DIRECTLY INTO A PUBLIC WAY PER 2022 CRC, SECTION 310.1.
4. NOT LESS THAN 30" OF CLEARANCE IN WIDTH, DEPTH, & HEIGHT SHALL BE PROVIDED TO ACCESS EXTERIOR MECHANICAL EQUIPMENT. SHOW LOCATION ON SITE PLAN & LABEL (2022 CMC SECTION 304.1 & 2022 CPC 504.3).

SITE PLAN CHECKLIST

IS (N) ADU 5' - 0" OR LESS TO ANY PROPERTY LINE AND/OR IS (N) ADU 10' - 0" OR LESS FROM ANY ADJACENT BUILDING OR STRUCTURE.

☐ NO ☐ YES; IF YES, FIRE RATED WALL & ROOF REQUIRED PER 2022 CBC, CHAPTER 2. FIRE RATED WALL DETAIL: 52/A-901
IF YES, *FIREBLOCKING IS REQUIRED IN PROJECTIONS, RAKES AND EAVES. SEE DETAILS: 24/A-903 31/A-912, 32/A-912, 31/A-922, 32/A-922, 31/A-932, 32/A-932

***NOTE:** WHERE 1-HR FIRE-RESISTANCE RATED PROJECTIONS REQUIRED (NON-SPRINKLERED & FIRE SEPARATION DISTANCE $\geq 2'-0"$ < $5'-0"$)

ELECTRICAL PANEL: ☐ **OPTION 1 -** NEW ELECTRICAL MAIN PANEL OF 200 AMP WITH 225 AMP MINIMUM BUSBAR RATING

☐ **OPTION 2 -** A NEW ELECTRICAL SUBPANEL CONNECTS TO THE ELECTRICAL MAIN PANEL OF THE PRIMARY HOME WITH A 225 AMP MINIMUM BUSBAR RATING. A SEPARATE ELECTRICAL PERMIT SHALL BE PULLED FOR THE ELECTRICAL MAIN PANEL OF THE PRIMARY HOME, ELECTRICAL LOAD CALCULATIONS IS REQUIRED.

FOOTPRINT OF ALL EXISTING AND PROPOSED BUILDINGS
PLOT THE PROPOSED ADU BUILDING FOOTPRINT ALONG WITH ANY OTHER EXISTING BUILDINGS ONSITE. THIS INCLUDES ALL STRUCTURES / PORCHES / GAZEBO. IF AN OPTIONAL COVERED PATIO IS SELECTED, PLEASE PLOT THAT AS WELL.

☐ **AREA OF EXISTING BUILDING**
INDICATE THE SQUARE FOOTAGE OF THE EXISTING HOUSE

☐ **DRAWING SCALE**
SITE PLAN SHOULD BE DRAWN TO A MEASURABLE SCALE.

☐ **PROPERTY LINES**
SHOW OUTLINE OF PROPERTY USING DASHED LINE IN LEGEND. INDICATE THE BEARING AND DISTANCE OF THE PROPERTY LINE.

LABEL YARDS
 LABEL FRONT, REAR, SIDE YARDS, AS WELL AS DRIVEWAYS, PATHWAYS AND ANY
 OTHER HARDSCAPE.

SETBACKS
DIMENSION THE DISTANCE BETWEEN BUILDINGS AND PROPOERTY LINES, AS WELL AS BUILDINGS TO OTHER STRUCTURES. SETBACKS TO SIDE AND REAR PROPERTY SIDE SHALL BE A MINIMUM OF (4' - 0").

☐ **EASEMENTS**
REFER TO LEGEND. MUST INCLUDE ALL APPLICABLE EASEMENTS. PROPOSED
STRUCTURE SHALL COMPLY WITH EASEMENT REQUIREMENTS.

☐ **LOCATION OF RAIN WATER LEADERS**
THE ROOF DRAINS SHOULD DRAIN AWAY FROM THE PROPERTY LINES AND INTO THE LANDSCAPE AREA.

☐ LABEL STREETS & SIDEWALKS

☐ **DIMENSION BUILDING SEPARATION**
 DIMENSION THE DISTANCE BETWEEN THE PROPOSED ADU AND ANY EXISTING STRUCTURES

☐ **LOT COVERAGE CALCULATION**
TOTAL FOOTPRINT AREA FOR STRUCTURES ON SITE / LOT AREA


☐ **SWIMMING POOLS**
ALL EXISTING SWIMMING POOLS SHALL BE SHOWN ON THE SITE PLAN AND SHALL HAVE 10' MINIMUM SETBACK TO THE NEW ADU STRUCTURE.

PORCHES
THERE SHALL BE NO MORE THAN 30 INCHES MEASURED VERTICALLY TO THE FLOOR OR GRADE BELOW (INCLUDING FLOORS, STAIRS, RAMPS, AND LANDINGS) ANYWHERE MEASURED LESS THAN 36 INCHES HORIZONTALLY TO THE EDGE OF THE PORCH/SLAB/SURFACE OF THE RAIL. INSECT SCREENING SHALL NOT BE CONSIDERED AS A GUARD.

☐ **LOCATION OF EXISTING UTILITIES**
UTILITIES, POLES, SEWER, DRAINS, ELECTRICAL, GAS METERS AND LINES AND
ANY PHOTOVOLTAIC.

LOCATION OF PROPOSED UTILITIES
PROPOSED UTILITIES SHALL CONFORM TO REQUIREMENTS OF CONTRA COSTA COUNTY SANITARY DISTRICT. SANITARY SEWER FROM ADU TO EXISTING SEWER. SEWER LINE TO THE PROPOSED ADU SHALL BE CONNECTED TO THE MAIN LATERAL AT THE PROPERTY LINE OR BEHIND THE SIDEWALK. LATERAL POINT OF CONNECTION INCLUDING REQUIRED CLEANOUTS, WATER LINE TO ADU, ELECTRIC TO ADU INCLUDING ANY NEW METERS OR SUBPANELS.

NOTE: THIS IS AN EXAMPLE SITE PLAN. EXACT LAYOUT, DIMENSIONS, AND BEARINGS SHALL BE PROVIDED BY OWNER/APPLICANT. (E) EXISTING (N) NEW




1 SITE PLAN EXAMPLE FOR REFERENCE

AS101	SCALE: 1" = 20'-0"
-------	--------------------

SITE PLAN

SCALE:



NORTH ARROW



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. WALNUT CREEK CITY PLANS ARE NOT ALLOTTED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO PROVIDE THE FURTHER INFORMATION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK

ARCHITECTURAL SITE PLAN
EXAMPLE & INSTRUCTIONS)

DATE
02/10/2023

SHEET

AS101



CALIFORNIA RANCH



MODERN



COTTAGE



**CITY OF
WALNUT
CREEK**

THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK

RENDERINGS


DATE
02/10/2023

SHEET

A1-100


PLUMBING NOTES

1. WATER HEATER (REFER TO BUILDING ENERGY ANALYSIS REPORT):
- A. ALL DOMESTIC HOT WATER PIPING SHALL BE INSULATED. (2022 CPC 609.12.1)
- PIPES UP TO 2 INCHES IN DIAMETER: INSULATION WALL THICKNESS NOT LESS THAN DIAMETER OF PIPE. (2022 CPC 609.12.2)
- PIPES GREATER THAN 2 INCHES IN DIAMETER: INSULATION WALL THICKNESS NOT LESS THAN 2 INCHES. (2022 CPC 609.12.2)
- EXCEPTIONS:
1. PIPING THAT PENETRATES FRAMING MEMBERS SHALL NOT BE REQUIRED TO HAVE PIPE INSULATION FOR THE DISTANCE OF THE FRAMING PENETRATION. (2022 CPC 609.12.2)
2. HOT WATER PIPING BETWEEN THE FIXTURE CONTROL VALVE OR SUPPLY STOP AND THE FIXTURE OR APPLIANCE SHALL NOT BE REQUIRED TO BE INSULATED. (2022 CPC 609.12.2)
- B. PROVIDE A TEMPERATURE AND PRESSURE RELIEF VALVE WITH A FULL SIZE DRAIN OF GALVANIZED STEEL OR HARD DRAWN COPPER TO THE OUTSIDE OF THE BUILDING WITH THE END OF THE PIPE PROTRUDING 6" MINIMUM @ 2" MAX. ABOVE GRADE POINTING DOWNWARD TO THE TERMINATION - UNTHREADED.
- C. COMBUSTION AIR PER MANUFACTURE REQUIREMENTS.
- D. CLEARANCES PER MANUFACTURE REQUIREMENTS.




1 PLAN 1 - GROUND FLOOR PLAN

A1-201 A1-101 SCALE: 1/4" = 1'-0"



21 PLAN 1 - COTTAGE PORCH

A1-201 A1-101 SCALE: 1/4" = 1'-0"



20 PLAN 1 - MODERN PORCH

A1-201 A1-101 SCALE: 1/4" = 1'-0"

WINDOW GENERAL NOTES

1. REFER TO FLOOR PLANS FOR WINDOW LOCATIONS.
2. CONTRACTOR TO VERIFY EXACT ROUGH OPENING SIZES PRIOR TO FABRICATION OF ROUGH OPENINGS.
3. REFER TO ENERGY COMPLIANCE REPORTS FOR U-FACTOR, SHGC AND ADDITIONAL WINDOW REQUIREMENTS.
4. ALL GLAZING IS DOUBLE PANE UNLESS OTHERWISE NOTED.
5. EGRESS WINDOWS SHALL HAVE A CLEAR OPENING WITH THE BOTTOM OF THE CLEAR OPENING NOT GREATER THAN 44" AFF. MIN. NET CLEAR OPENING FOR EMERGENCY ESCAPE SHALL BE 5.7 S.F. EXCEPT: 5 S.F. MIN. AT GROUND FLOOR. MINIMUM NET CLEAR OPENING DIMENSIONS: HEIGHT: 24", WIDTH: 20". [CRC SEC. R310.2] EMERGENCY ESCAPE AND RESCUE OPENINGS SHALL OPEN DIRECTLY INTO A PUBLIC WAY PER CRC 2022, SECTION 310.1.
6. GLAZING IN WALLS ADJACENT TO BATHTUB / SHOWER WHERE THE BOTTOM EXPOSED EDGE OF THE GLAZING IS LESS THAN 60" MEASURED VERTICALLY ABOVE ANY STANDING OR WALKING SURFACE SHALL BE SAFETY GLAZING. [CRC SEC. R308.4.5]

KEYNOTES

- A01 30" WIDE FREE STANDING ELECTRIC RANGE OVEN. VENT TO EXTERIOR. STAINLESS STEEL.
- A05 REFRIGERATOR LOCATION. PROVIDE 42" SPACE WITH ROUGH PLUMBING FOR ICE MAKER (RECESS IN WALL).
- A06 STACKED WASHER/DRYER MACHINE LOCATION. PROVIDE WASTE AND WATER IN RECESSED WALL BOX. PROVIDE DRYER VENT. VENT TO OUTSIDE AIR.
- A15 WASHING MACHINE LOCATION. PROVIDE WASTE AND WATER IN RECESSED WALL BOX.
- B02 20" SINGLE COMPARTMENT UNDER-MOUNT KITCHEN SINK W/ DISHGE DISPOSAL. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEET.
- B04 LAVATORY SINK. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEETS.
- B05 WATER CLOSET. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEETS. WATER CLOSET SHALL NOT BE SET CLOSER THAN 15" FROM ITS CENTER TO A SIDE WALL OR OBSTRUCTION PER CPC, SECTION 402.5.
- B06 32" x 60" x 72" TUB AND SHOWER COMBINATION. MODEL BY BUILDER. PROVIDE SHOWER ROD.
- B18 ELECTRIC PANEL LOCATION. PROVIDE PROTECTION PER CPC 507.25 & CMC 305.1.1, SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFO.
- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION. 3" MIN. ABOVE GRADE. PROVIDE PROTECTION PER CPC 507.25 & CMC 305.1.1, SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFO. SEE DETAIL 53/A-902.
- B41 FAN COIL @ 80" A.F.F. TO BOTTOM OF UNIT. PROVIDE DEDICATED WALL OUTLET. INSTALL PER MANUFACTURER'S SPECIFICATIONS. REFER TO PLANS FOR LOCATION OF OUTDOOR CONDENSING UNIT. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION.
- B47 40 GALLON HEAT PUMP WATER HEATER. PROVIDE ENCLOSURE IN COMPLIANCE WITH CPC 507.25. PROVIDE CONCRETE PAD 3" MIN. ABOVE GRADE. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. SEE DETAIL 22/A-901. PROVIDE PROTECTION PER CMC 305.1.1, SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFORMATION. SEE DETAIL 53/A-902.
- C01 SINGLE WOOD SHELF AND POLE.
- C10 24" DEEP UPPER CABINET.
- C13 30" HIGH BASE CABINET AND COUNTERTOP.
- C16 MIRROR. THE LENGTH OF THE VANITY OR PEDESTAL X 80" AFS. UNO. VERIFY WITH THE ELECTRICAL PLAN FOR LOCATION OF OUTLETS WHICH REQUIRE A CUT-OUT. PROVIDE 2X6 BACKING AT BATHROOM WALL ATTACHEMENTS
- C31 PROVIDE REINFORCEMENT FOR GRAB BARS PER CRC R327.1.1; SEE DETAILS 43/A-901 & 44/901; SEE GENERAL NOTES FOR MORE INFORMATION.
- G05 CONCRETE STOOP. SLOPE 1/4"/FT AWAY FROM THE BUILDING. MUST BE AT LEAST AS WIDE AS DOOR AND 3" DEEP.
- L02 CORNER TRIM; SEE DETAILS FOR MORE INFORMATION.
- M02 DOWNSPOUT DOWNSPOUT TO SPLASH BLOCK BELOW. SEE DETAIL 12/A-903.
- P01 DECORATIVE PORCH RAILING, HEIGHT OF 24" MIN. TO 48" MAX. REQUIRED FOR WOOD: PRIMER & 2 COATS OF EXTERIOR GRADE PAINT. REQUIRED: 30 INCHES MAX VERTICAL DROP IS PROHIBITED WITHIN 36 INCHES (HORIZONTALLY) OF THE PORCH. SEE DETAIL FOR MORE INFORMATION.
- T12 WOOD POST, SEE STRUCTURAL - REQUIRED: PRIMER & 2 COATS OF EXTERIOR GRADE PAINT.
- X01 OPTIONAL MEDICINE CABINET.

LEGEND

- EXTERIOR - 5 1/2" WOOD STUD W/ PLYWOOD SHEATHING AND FINISH, SEE ELEVATION FOR FINISH, ONE LAYER GYPSUM WALL BOARD INTERIOR.
- EXTERIOR - DOUBLE 5 1/2" WOOD STUD W/ SHEATHING AND EXTERIOR FINISH (REFER TO ELEVATIONS)
- INTERIOR - 3 1/2" WOOD STUD W/ ONE LAYER GYPSUM WALL BOARD EACH SIDE.

WINDOW REMARKS

1. REQUIRED EGRESS WINDOW. REFER TO GENERAL NOTE #5 FOR ADDITIONAL INFORMATION.
2. WINDOW INCLUDES BOTH PANES TEMPERED GLAZING.
3. U-FACTOR = (3) . SHGC = (.23). BUG SCREEN REQUIRED. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION.
4. OPTIONAL WINDOW.
5. OBSCURE.

WINDOW SCHEDULE

NO.	TYPE	SIZE		HEAD HEIGHT	REMARKS	WINDOW DETAIL REFERENCES		
		WIDTH	HEIGHT			HEAD	JAMB	SILL
01	B	3'-0"	2'-0"	6'-8"		CALIFORNIA RANCH	11/A-911	
02	B	3'-0"	4'-0"	6'-8"		COTTAGE	11/A-921	
03	B	2'-0"	2'-0"	6'-8"	2, 3, 5	MODERN	11/A-931	
04	B	4'-0"	4'-0"	6'-8"		FLASHING	32/A-901	33/A-901 34/A-901
05	B	4'-0"	4'-0"	6'-8"				

WINDOW LEGEND

- A. SINGLE HUNG.
- B. SLIDER.

FLOOR PLAN GENERAL NOTES

1. REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
2. REFER TO STRUCTURAL PLANS FOR FURTHER INFORMATION.
3. REFER TO ELECTRICAL PLANS FOR FURTHER INFORMATION IF PROVIDED.
4. REFER TO MECHANICAL PLANS, DRAWINGS OR REPORTS FOR FURTHER INFORMATION.
5. ALL FURNITURE AND EQUIPMENT IS BY OWNER AND IS SHOWN FOR COORDINATION PURPOSES ONLY.
6. DIMENSIONS ARE TO FACE OF FRAMING UNLESS SPECIFICALLY NOTED OTHERWISE.
7. PROVIDE ADEQUATE BLOCKING IN WALLS FOR CABINETS AND OTHER WALL MOUNTED ACCESSORIES INCLUDING BUT NOT LIMITED TO HANDRAILS, SHELVING AND BATHROOM FIXTURES.
8. DOOR AND WINDOW DIMENSIONS ARE CENTERED AT OPENINGS.
9. WHERE DOOR IS LOCATED WITHOUT DIMENSION AT THE CORNER OF A ROOM IT SHALL BE 4" FROM FACE OF FRAMING OF ADJACENT WALL TO ROUGH DOOR OPENING.
10. WHERE RECESSED FIXTURES OCCUR IN WALLS OR HORIZONTAL ASSEMBLIES, THE FIRE RATING OF THOSE ASSEMBLIES SHALL BE MAINTAINED.
11. AT ALL PENETRATIONS AND INTERSECTIONS OF FIRE-RATED PARTITIONS, PROVIDE FIRE SEALANT AND/OR FIRE STOPPING TO MAINTAIN CONTINUITY OF PARTITION RATING.
12. PER CRC R311.3 FLOORS OR LANDINGS AT EXTERIOR DOORS SHALL BE AT LEAST AS WIDE AS DOOR SERVED AND SHALL PROVIDE A LENGTH IN THE DIRECTION OF TRAVEL EQUAL TO 36 INCHES MINIMUM. SLOPE OF EXTERIOR LANDINGS SHALL NOT EXCEED 1/4" PER FOOT (2% SLOPE).
13. PER CRC 327.1.1 REINFORCEMENT FOR GRAB BARS SHALL BE PROVIDED IN AT LEAST ONE BATHROOM. 1. REINFORCEMENT SHALL BE SOLID LUMBER OR OTHER CONSTRUCTION MATERIALS APPROVED BY THE ENFORCING AGENCY. 2. REINFORCEMENT SHALL NOT BE LESS THAN 2X8 INCH NOMINAL LUMBER OR OTHER MATERIAL PROVIDING EQ. HT. AND CAPACITY. REINFORCEMENT ABOVE THE FINISHED FLOOR FLUSH WITH THE WALL FRAMING. 3. WATER CLOSET REINFORCEMENT SHALL BE INSTALLED ON BOTH SIDE WALLS OF THE FIXTURE, OR ONE SIDE WALL AND THE BACK WALL. 4. SHOWER REINFORCEMENT SHALL BE CONTINUOUS WHERE WALL FRAMING IS PROVIDED. 5. BATHTUB AND COMBINATION BATHTUB/SHOWER REINFORCEMENT SHALL BE CONTINUOUS ON EACH END OF THE BATHTUB AND THE BACK WALL. ADDITIONALLY, BACK WALL REINFORCEMENT FOR A LOWER GRAB BAR SHALL BE PROVIDED WITH THE BOTTOM EDGE LOCATED NO MORE THAN 6 INCHES ABOVE THE BATHTUB RIM. REFER TO DETAILS 43/A-901 AND 44/A-901.
14. BATHTUB AND SHOWER FLOORS AND WALLS ABOVE BATHTUBS WITH INSTALLED SHOWER HEADS AND IN SHOWER COMPARTMENTS SHALL BE FINISHED WITH A NONABSORBENT SURFACE. SUCH WALL SURFACES SHALL EXTEND TO A HEIGHT OF NOT LESS THAN 6 FEET ABOVE THE FLOOR PER 2022 CRC, SECTION R307.2.

DOOR GENERAL NOTES

1. GLAZING IN DOORS SHALL BE TEMPERED PER SECTION R308.4.1. PANES INDICATED IN DOOR LEGEND WITH (T).
2. REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
3. REFER TO PLANS FOR LOCATION OF DOORS.
4. VERIFY ROUGH OPENING SIZE WITH DOOR MANUFACTURER SPECIFICATIONS PRIOR TO CONSTRUCTION.
5. CONTRACTOR TO VERIFY ACTUAL DOOR SIZE TO FIT FINISH OPENING PRIOR TO FABRICATION OF DOOR AND FINISH OPENING.
6. FIRE RATED DOORS SHALL BE SOLID WOOD OR SOLID HONEYCOMB CORE STEEL DOOR 1-3/8" THICK OR COMPLIANT WITH CRC SECTION R302.5.1. DOORS SHALL BE SELF-CLOSING AND SELF-LATCHING WITH WEATHER STRIPPING TO BE TIGHT FITTING.

DOOR REMARKS


1. EXTERIOR DOOR.
2. GLAZING PER DOOR TYPES. REFER TO GENERAL DOOR NOTE #1
3. PROVIDE 100 SQ. INCHES OF VENTING IN DOOR OR BY OTHER APPROVED MEANS.
4. OPTIONAL DOOR.
5. REQUIRED OPENING OF NOT LESS THAN 100 IN² FOR MAKEUP AIR SHALL BE PROVIDED IN THE DOOR OR BY APPROVED MEANS. [CMC SEC. R504.4.1]

DOOR SCHEDULE

NO.	TYPE	DOOR		REMARKS	DOOR DETAIL REFERENCES	
		WIDTH	HEIGHT		HEAD	JAMB
01	A1	3'-0"	6'-8"	1, 2	CALIFORNIA RANCH	41/A-911
02	C	4'-0"	6'-8"		COTTAGE	41/A-921
03	G	2'-10"	6'-8"	5	MODERN	41/A-931
04	F	2'-8"	6'-8"		THRESHOLD	11/A-901 12/A-901
05	B	3'-10"	7'-0"	1		

DOOR LEGEND

- A1. SOLID CORE WOOD EXTERIOR ENTRY
- B. DOUBLE HOLLOW CORE EXTERIOR
- C. DOUBLE SLIDING INTERIOR
- F. HOLLOW CORE WOOD POCKET INTERIOR
- G. VENTED DOUBLE INTERIOR (WITH MIN. 100 IN² OPENING)



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU


CITY OF WALNUT CREEK

FLOOR PLAN 1

DATE
02/10/2023

SHEET

A1-101



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK
FINISH, MECHANICAL, &
ELECTRICAL PLANS

DATE
02/10/2023
SHEET

A1-111

GENERAL MEP NOTES

1. REFER TO ELECTRICAL NOTES ON SHEET G-101.
2. REFER TO MECHANICAL NOTES ON SHEET G-101.
3. REFER TO PLUMBING NOTES ON SHEET G-101.
4. REFER TO TITLE 24 COMPLIANCE NOTES ON SHEET G-101.
5. EXTERNALLY MOUNTED HEATING/COOLING UNITS SHALL BE SCREENED IF THEY ARE VISIBLE FROM A PUBLIC STREET.
6. ENVIRONMENTAL AIR DUCT EXHAUST SHALL TERMINATE NOT LESS THAN 3 FT FROM WALL OPENINGS. **CNC 502.2.2.1.**
7. APPLIANCES NOT LISTED FOR OUTDOOR INSTALLATION BUT INSTALLED OUTDOORS SHALL BE PROVIDED WITH PROTECTION TO THE DEGREE THAT THE ENVIRONMENT REQUIRES. APPLIANCES LISTED FOR OUTDOOR INSTALLATION SHALL BE PERMITTED TO BE INSTALLED WITHOUT PROTECTION IN ACCORDANCE WITH THE PROVISIONS OF ITS LISTING AND THE MANUFACTURER'S INSTALLATION INSTRUCTIONS PER **CPC 507.25 PROTECTION OF OUTDOOR APPLIANCES.**
8. APPLIANCES INSTALLED IN GARAGES, WAREHOUSES, OR OTHER AREAS SUBJECT TO MECHANICAL DAMAGE SHALL BE AT LEAST 18" ABOVE THE FLOOR AND GUARDED AGAINST SUCH DAMAGE BY BEING INSTALLED BEHIND PROTECTIVE BARRIERS OR BY BEING ELEVATED OR LOCATED OUT OF THE NORMAL PATH OF VEHICLES PER **CNC 308.1.1 PHYSICAL DAMAGE.**
9. INSTALLED AIR CONDITIONER AND HEAT PUMP SYSTEMS SHALL HAVE A CLEARANCE OF AT LEAST FIVE (5) FEET FROM THE OUTLET OF ANY DRYER VENT. **CENC2022 150.0 (H) 3.**
10. INSTALLED AIR CONDITIONER AND HEAT PUMP SYSTEMS SHALL BE EQUIPPED WITH LIQUID LINE DRIERS IF REQUIRED, AS SPECIFIC BY MANUFACTURER'S INSTRUCTIONS. **CENC2022 150.0 (H) 3. SEE DETAIL 53/A-902.**


KEYNOTES

- B17 WHERE ATTIC ACCESS REQ. PROVIDE SWITCH AND OUTLET @ ATTIC ACCESS.
- B18 ELECTRIC PANEL LOCATION. PROVIDE PROTECTION PER CPC 507.25 & CNC 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFO.
- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE. PROVIDE PROTECTION PER CPC 507.25 & CNC 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFO. SEE DETAIL 53/A-902.
- B41 FAN COIL @ 80" A.F.F. TO BOTTOM OF UNIT, PROVIDE DEDICATED WALL OUTLET, INSTALL PER MANUFACTURER'S SPECIFICATIONS. REFER TO PLANS FOR LOCATION OF OUTDOOR CONDENSING UNIT. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION.
- B42 OUTLET FOR GARBAGE DISPOSAL UNIT.
- B43 SWITCH FOR INDOOR AIR QUALITY FAN. PROVIDE LABEL "THIS SWITCH CONTROLS THE INDOOR AIR QUALITY VENTILATION FOR THE HOME. LEAVE IT ON UNLESS THE OUTDOOR AIR QUALITY IS VERY POOR."
- B47 40 GALLON HEAT PUMP WATER HEATER. PROVIDE ENCLOSURE IN COMPLIANCE WITH CPC 507.25, PROVIDE CONCRETE PAD 3" MIN. ABOVE GRADE. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. SEE DETAIL 22/A-901. PROVIDE PROTECTION PER CNC 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFORMATION. SEE DETAIL 53/A-902.
- M02 DOWNSPOUT DOWNSPOUT TO SPLASH BLOCK BELOW. SEE DETAIL 12/A-903.

LEGEND


§ ELECTRICAL SWITCH	⊙ SMOKE DETECTOR/ALARM	AFI ⚡ DUPLEX OUTLET ARC-FAULT CIRCUIT INTERRUPTER
3 ELECTRICAL SWITCH-THREE WAY	⊙ COMBINATION SMOKE/CARBON MONOXIDE	GFI 240V ⚡ DUPLEX OUTLET 240 VOLTS
4 ELECTRICAL SWITCH-FOUR WAY	Ⓛ DATA LOCATION	GFI ⚡ DUPLEX OUTLET GROUND FAULT INTERRUPTER
5S ELECTRICAL SWITCH-VACANCY SENSOR	Ⓛ TELEPHONE LOCATION	GFI ⚡ DUPLEX OUTLET WATERPROOF GROUND FAULT INTERRUPTER
D ELECTRICAL SWITCH-DIMMER	Ⓛ CABLE TELEVISION LOCATION	GFI ⚡ DUPLEX OUTLET AFCI-HALF HOT
F ELECTRICAL SWITCH-FAN	Ⓛ ELECTRICAL JUNCTION BOX	GFI ⚡ DUPLEX OUTLET MICROWAVE GROUND FAULT INTERRUPTER
A ⚡ ASTRONOMICAL TIME SWITCH		GFI ⚡ DUPLEX OUTLET DISH WASHER GROUND FAULT INTERRUPTER
⊙ EXHAUST FAN		H ⚡ DUPLEX OUTLET RANGE HOOD
⊙ INDOOR AIR QUALITY FAN		CW ⚡ COLD WATER STUB OUT
P PENDANT LIGHT HIGH-EFFICACY		HW ⚡ HOT WATER STUB OUT
⊙ SURFACE MOUNTED HIGH-EFFICACY LIGHT		SOV ⚡ WATER HOSE BIBB WITH SHUT OF VALVE
⊙ WALL MOUNTED HIGH-EFFICACY LIGHT		IM ⚡ ICE MACHINE STUB OUT
⊙ EXTERIOR WALL MOUNTED HIGH-EFFICACY LIGHT W/ PHOTO SENSOR		EC ⚡ FAN COIL UNIT +80" TO BOTTOM OF UNIT PROVIDE DEDICATED OUTLET
⊙ RECESSED HIGH-EFFICACY DOWNLIGHT		
⊙ OPT. OPTIONAL RECESSED HIGH-EFFICACY DOWNLIGHT		
⊙ VP RECESSED HIGH-EFFICACY DOWNLIGHT-VAPOR PROOF		

NOTE: IONIZATION SMOKE DETECTOR 10" MINIMUM FROM STOVE, ALL OTHERS 20" MIN CLEARANCE



2 MECHANICAL PLAN

A1-201 | A1-111 | SCALE: 1/4" = 1'-0"



1 ELECTRICAL PLAN

A1-201 | A1-111 | SCALE: 1/4" = 1'-0"

3 FINISH PLAN

A1-201 | A1-111 | SCALE: 1/4" = 1'-0"

FLOOR FINISH LEGEND

	LUXURY VINYL PLANK (LVP)		CARPET (CPT)
	CERAMIC TILE (CT)		CONCRETE (EC)

VENTILATION SUMMARIES

1) LOCAL EXHAUST VENTILATION

BATHROOM	OPTION A	OPTION B
BATHROOM FAN FLOW (cfm)	50 CFM	50 CFM
DUCT TYPE	FLEX DUCT	SMOOTH DUCT
DUCT SIZE (in)	4"	4"
MAX. ALLOWABLE DUCT LENGTH (ft)	70'	105'
THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 3 SONES.		

KITCHEN	OPTION A	OPTION B
KITCHEN FAN FLOW (cfm)	100 CFM	50 CFM
DUCT TYPE	FLEX DUCT	SMOOTH DUCT
DUCT SIZE (in)	5"	5"
MAX. ALLOWABLE DUCT LENGTH (ft)	35'	85'
THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 3 SONES.		

2) WHOLE BUILDING VENTILATION

PER ASHRAE STANDARD 62.2, CEC EQUATION 150.0-B	OPTION A	OPTION B
BUILDING FAN FLOW (cfm)	50 CFM	50 CFM
DUCT TYPE	FLEX DUCT	SMOOTH DUCT
DUCT SIZE (in)	4"	4"
MAX. ALLOWABLE DUCT LENGTH (ft)	70'	105'

THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 1 SONE.
THIS EXHAUST FAN IS REQUIRED TO OPERATE CONTINUOUSLY TO ENSURE CONTINUOUSLY TO ENSURE INDOOR AIR QUALITY.


WHOLE DWELLING UNIT MECHANICAL VENTILATION

PER SECTION 150.0(C)(1) [ASHRAE 62.2.4.1.2]
STUDIO - MINIMUM CUBIC FEET PER MINUTE (CFM) (Equation 150.0-B)
Qtot = 0.03Afloor + 7.5(Nbr + 1) 03(408 sf) + 7.5 (1) = 19.74 CFM < 50 CFM

ELECTRICAL NOTES

1. CONFORM WITH CURRENT CEC, NFPA, MFR'S, AND LOCAL REQUIREMENTS.
2. ELECTRICAL SYSTEM GROUND TO BE PROVIDED PER NEC ARTICLE 250-81.
3. ALL MATERIALS TO BE U.L. LABELED.
4. METER IS NOT REQUIRED, IF IT IS PROVIDED FOR ADU, MAIN PANEL IS REQUIRED FOR ADU WITH MINIMUM OF 225 AMP BUS-BAR. IF MAIN PANEL IS NOT PROVIDED FOR ADU, ELECTRICAL PERMIT SHALL BE PULLED FOR THE PRIMARY RESIDENCE WITH ELECTRICAL LOAD CALCULATIONS. METER: "SQUARE D", 120 VOLT/240 VOLT, 1 AND 3 WIRE GROUND OR EQUAL.
5. IF PROVIDED, ELECTRICAL MAIN PANEL: FLUSH MOUNT, 30" CLEARANCE, 200 AMP WITH 225 AMP BUS-BAR.
6. CONDUCTORS: TW, THW, COPPER, MINIMUM 14 AT LIGHTING, 12 AT OTHER CIRCUITS.
7. ALL LUMINAIRES SHALL COMPLY WITH 2022 CEC SECTION 150.0 (K) AND TABLE 150.0-A AS REFERENCED IN ENERGY NOTES, LUMINAIRE REQUIREMENTS SHEET G-101.
8. ALL ELECTRICAL OUTLETS INSTALLED IN BATHROOMS, GARAGES, LAUNDRY AREAS, BASEMENTS, CRAWL SPACES, OUTDOORS, KITCHEN COUNTERS, AND AT WET BAR SINKS SHALL HAVE GROUND-FAULT CIRCUIT-INTERRUPTER PROTECTION IN COMPLIANCE WITH NEC Art. 210-8, CONSISTING OF 125 VOLT, SINGLE-PHASE, 15- AND 20- AMPERE RECEPTACLES.
9. ALL BATHROOM RECEPTACLE OUTLETS SHALL BE SUPPLIED BY A MINIMUM OF ONE 120-VOLT, 20-AMPERE BRANCH CIRCUIT. SUCH CIRCUITS SHALL HAVE NO OTHER OUTLETS. THIS DEDICATED CIRCUIT MAY SERVE MORE THAN ONE BATHROOM. (2022 CEC 210.11(C))
10. THERMOSTAT SHALL BE A PROGRAMMABLE TYPE, HONEYWELL TH8320 OR EQUAL.
11. CEILING-SUSPENDED (PADBLE) FANS SHALL BE SUPPORTED INDEPENDENTLY OF AN OUTLET BOX OR BY LISTED OUTLET BOX OR OUTLET BOX SYSTEMS IDENTIFIED FOR THE USE AND INSTALLED IN ACCORDANCE WITH 2022 CEC 314.27(C) (2022 CEC 422.18).
12. ALL LUMINAIRES, LAMPHOLDERS, AND RETROFIT KITS SHALL BE LISTED (2022 CEC 410.6).
13. ALL 120-VOLT, SINGLE PHASE 15- AND 20- AMPERE BRANCH CIRCUITS SUPPLYING OUTLETS INSTALLED IN DWELLING UNIT KITCHENS, FAMILY ROOMS, LIVING ROOMS, DINING ROOMS, PARLORS, LIBRARIES, DENS, BEDROOMS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS OR SIMILAR ROOMS OR AREAS SHALL BE PROTECTED BY A LISTED ARC-FAULT CIRCUIT INTERRUPTER, COMBINATION-TYPE, INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUIT. (2022 CEC 210-12(A)).
14. ALL NON-LOCKING TYPE 125-VOLT, 15 AND 20 AMPERE RECEPTACLES IN A DWELLING UNIT SHALL BE LISTED TAMPER-RESISTANT RECEPTACLES. EXCEPTIONS: (1) RECEPTACLES MORE THAN 5'6" ABOVE THE FLOOR, (2) RECEPTACLES PART OF A LUMINAIRE OR APPLIANCE, (3) A SINGLE RECEPTACLE OR A DUPLEX RECEPTACLE FOR TWO APPLIANCES THAT ARE NOT EASILY MOVED AND LOCATED WITHIN DEDICATED SPACE AND ARE CHORD-AND-PLUG CONNECTED AS PER CEC 400.10, AND (4) NON-GROUNDING RECEPTACLES USED FOR REPLACEMENTS AS PERMITTED IN CEC 406.4(D)(2)(A).
15. HIGH EFFICACY LUMINAIRES OTHER THAN OUTDOOR HID LIGHTING CONTAIN ONLY ONLY HIGH EFFICACY LAMPS AS OUTLINED IN TABLE 150-C OF THE RESIDENTIAL ENERGY CODE AND NOT CONTAIN A MEDIUM SCREW BASE SOCKET.
16. BALLAST FOR LAMPS 13 WATTS OR GREATER SHALL BE ELECTRONIC AND HAVE AN OUTPUT FREQUENCY NO LESS THAN 20 kHz.
17. SMOKE DETECTORS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND PROVIDED WITH A BATTERY BACK-UP. ALL SMOKE DETECTORS SHALL BE INTERCONNECTED. ALL SMOKE DETECTORS SHALL MAINTAIN A MINIMUM 3 FOOT CLEARANCE TO HVAC SUPPLY OR RETURN AIR REGISTERS.
18. CARBON MONOXIDE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND PROVIDED WITH A BATTERY BACK-UP. ALL CARBON MONOXIDE ALARMS SHALL BE INTERCONNECTED.
19. EXHAUST FANS WILL BE CONTROLLED BY A HUMIDISTAT PER THE GREEN BUILDING STANDARDS CODE SECTION 4.506. EXHAUST FANS MUST BE SWITCHED SEPARATELY FROM LIGHTS (2022 CEC 150.0(H)(2)).
20. IN ADDITION TO THE NUMBER OF BRANCH CIRCUITS REQUIRED BY OTHER PARTS OF THE CODE, TWO OR MORE 20-AMPERE SMALL-APPLIANCE BRANCH CIRCUITS SHALL BE PROVIDED FOR ALL RECEPTACLE OUTLETS IN THE KITCHEN, PANTRY, BREAKFAST ROOM, DINING ROOM, OR SIMILAR AREA PER 2022 CEC, ARTICLE 210.11 (C)(1). THE CIRCUITS SHALL HAVE NO OTHER OUTLETS PER 2022 CEC, ARTICLE 210.52(B).
21. IN ADDITION TO THE NUMBER OF BRANCH CIRCUITS REQUIRED BY OTHER PARTS OF THE CODE, AT LEAST ONE ADDITIONAL 20-AMPERE BRANCH CIRCUIT SHALL BE PROVIDED TO SUPPLY THE LAUNDRY RECEPTACLE OUTLET(S) REQUIRED BY 2022 CEC, ARTICLE 210.52 (F). THIS CIRCUIT SHALL HAVE NO OTHER OUTLETS PER 2022 CEC, ARTICLE 201.11(C)(2).

1/10/2023 3:18:12 PM
C:\Users\steele\Documents\2264-01-CU21_Walnut Creek ADU_Central 2022_sleeBdLU.rvt



2

PLAN 1 - REFLECTED CEILING PLAN

A1-201 | A1-121

SCALE: 1/4" = 1'-0"

1

PLAN 1 - CALIFORNIA RANCH - ROOF PLAN

A1-201 | A1-121

SCALE: 1/4" = 1'-0"

ROOF PLAN GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
 - REFER TO STRUCTURAL PLANS FOR ROOF FRAMING INFORMATION INCLUDING MEMBER SIZES AND CONNECTION HARDWARE.
 - PROVIDE A MINIMUM OF 1 INCH OF AIRSPACE BETWEEN THE INSULATION AND ROOF SHEATHING.
 - WHERE THE ROOF PROFILE ALLOWS A SPACE BETWEEN THE ROOF COVERING AND DECKING, THE SPACES SHALL BE CONSTRUCTED TO PREVENT THE INTRUSION OF FLAMES AND EMBERS, BE FIRESTOPPED WITH APPROVED MATERIALS OR HAVE ONE LAYER OF MINIMUM 72 POUND MINERAL-SURFACED NONPERFORATED CAP SHEET OVER THE COMBUSTIBLE DECKING.
 - ALL ROOFING MATERIALS TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
 - OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO ROOF EDGE.
 - ROOF COVERINGS SHALL BE APPLIED IN ACCORDANCE WITH (CRC R905), AND MANUFACTURER'S INSTALLATION INSTRUCTIONS. ROOF COVERINGS SHALL BE INSTALLED TO RESIST THE COMPONENT AND CLADDING LOADS SPECIFIED IN R301.2.1(1), AND ADJUSTED FOR HEIGHT AND EXPOSURE IN ACCORDANCE WITH TABLE R301.2.1(2).
 - ROOF UNDERLAYMENTS SHALL BE IN ACCORDANCE WITH WITH SECTION R905.1.1, TABLE R905.1.1(2), AND TABLE R905.1.1(1).
 - ROOF VENTS SHALL BE APPLIED PER MANUFACTURER'S SPECIFICATIONS.
- FURNISHED DIMENSIONS FOR VENTS ARE GUIDES ONLY. INSTALL PER MANUFACTURER'S SPECIFICATIONS AND ADJUST TO ACCOMMODATE TRUSS LOCATIONS, PLUMBING VENTS, AND SOLAR COLLECTORS.
- ENCLOSED ATTICS AND ENCLOSED RAFTER SPACES FORMED WHERE CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS SHALL HAVE CROSS VENTILATION FOR EACH SEPARATE SPACE BY VENTILATING OPENINGS PROTECTED AGAINST THE ENTRANCE OF RAIN OR SNOW. VENTILATING OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16 INCH (1.6 MM) MINIMUM AND 1/4 INCH (6.4 MM) MAXIMUM. VENTILATING OPENINGS HAVING A LEAST DIMENSION LARGER THAN 1/4 INCH (6.4 MM) SHALL BE PROVIDED WITH CORROSION-RESISTANT WIRE CLOTH SCREENING, HARDWARE CLOTH, PERFORATED VINYL, OR SIMILAR MATERIAL WITH OPENINGS HAVING A LEAST DIMENSION OF 1/16 INCH (1.6 MM) MINIMUM AND 1/4 INCH (6.4 MM) MAXIMUM. OPENINGS IN ROOF FRAMING MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF SECTION R802.7. REQUIRED VENTILATION OPENINGS SHALL OPEN DIRECTLY TO THE OUTSIDE AIR AND SHALL BE PROTECTED TO PREVENT THE ENTRY OF BIRDS, RODENTS, SNAKES AND OTHER SIMILAR CREATURES (CRC R806).
- THE MINIMUM NET FREE VENTILATING AREA SHALL COMPLY WITH CRC R806.2.
 - IN THE INSTANCE OF UPPER VENTS, VENTS SHALL BE LOCATED NO MORE THAN 3 FT BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. CRC R806.2.

RCP GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-102 FOR ADDITIONAL REQUIREMENTS.
- HEIGHT OF CEILINGS SHALL BE MEASURED FROM TOP OF SLAB OR FLOOR TO FINISH FACE OF GWB, U.N.O.
- REFER TO DETAILS FOR FLOOR/CEILING ASSEMBLIES.
- REFER TO ELECTRICAL PLANS FOR LIGHT FIXTURE AND EXHAUST LOCATIONS.
- DIMENSIONS ARE TO THE FACE OF FRAMING UNLESS OTHERWISE NOTED.
- SOFFITS ARE TO BE HELD TIGHT TO UNDERSIDE OF MECHANICAL EQUIPMENT.

KEYNOTES

H07	BUILDING LINE BELOW.
H12	ATTIC VENT (LOW); LOWER VENTILATORS SHALL BE LOCATED IN THE BOTTOM ONE-THIRD OF THE ATTIC SPACE PER R806.2 EXCEPTION 2. PROVIDE DAMPER TO PROVIDE 1" CLR. AIRSPACE WHERE REQ. PAINT FINISH TO MATCH ROOF COLOR, SEE VENTING CALCS.
H13	ATTIC VENT (HIGH); UPPER VENTILATORS SHALL BE LOCATED NOT MORE THAN 3 FEET BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. PAINT FINISH TO MATCH ROOF COLOR, SEE VENTING CALCS.
H17	CEILING SOFFIT @ GABLE PORCH ROOF.
H23	WHERE AIRFLOW IS BLOCKED BY SHEAR PANEL, PROVIDE MINIMUM OF 12"x12" BLOCKED OPENING TO PROVIDE CROSS-VENTILATION.
K05	COMPOSITE ROOF SHINGLES, SEE MATERIALS LEGEND FOR MORE INFORMATION.
K14	EXTERIOR SOFFIT, SEE COVER PAGE FOR MATERIAL SELECTION, SEE DETAILS FOR MORE INFORMATION.
L12	6x WOOD BRACE WITH KICKER.
M01	GUTTER, CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4. SEE DETAIL 12/A-903.
M02	DOWNSPOUT DOWNSPOUT TO SPLASH BLOCK BELOW. SEE DETAIL 12/A-903.

X: SETBACK AT RIDGE TABLE

PV ARRAYS PERCENT OF THE PLAN VIEW TOTAL ROOF AREA	(X) HORIZONTAL RIDGE SETBACK
≤33%	18" BOTH SIDES OF RIDGE
>33%	36" BOTH SIDES OF RIDGE
≤66% + 13D SPRINKLER	18" BOTH SIDES OF RIDGE
>66% + 13D SPRINKLER	36" BOTH SIDES OF RIDGE

ROOF PLAN & RCP LEGEND

	CEILING HEIGHT (SEE PLAN FOR ACTUAL HEIGHTS)
	INTERIOR - GYPSUM BOARD CEILING
	EXTERIOR SOFFITS, RAKES, & EAVES; SEE TITLE SHEET FOR MATERIAL SELECTION AND CORRESPONDING DETAILS FOR MORE INFORMATION.
	COMPOSITE ASPHALT SHINGLE ROOF; SEE MATERIALS LEGEND ON ELEVATION SHEET FOR MORE INFORMATION.
	ROOF SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
	CEILING SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
	22"x30" MIN. ATTIC ACCESS PANEL (WHERE REQ.)
	DORMER STYLE ROOF VENT, SEE ROOF VENTING CALCULATIONS
	OUTLINE OF WALL BELOW
	GUTTER, CONNECT TO DOWNSPOUT; SEE DETAIL: 12/A-903
	APPROXIMATE LOCATION OF DOWNSPOUT/LEADER TO ROOF OR SPLASHBLOCK BELOW; SEE DETAILS:
	AVAILABLE SOLAR ZONE LOCATIONS. PV SYSTEM IS MANDATORY IF THE CONDITIONED AREA IS MORE THAN 652 SQUARE FEET, OTHERWISE IT'S OPTIONAL TO INSTALL A PV SYSTEM. WHEN PV SYSTEM IS INSTALLED, IT SHALL BE UNDER A SEPERATE PERMIT. SEE TITLE 24 REPORT FOR MORE INFORMATION
	AREA OF ATTIC WITH 30" HEIGHT OR GREATER. 22" X 30" CLEAR OPENING ACCESS REQUIRED IF TOTAL AREA GREATER THAN 30 SQ. FT. PER CRC R807.1

ROOF VENTING CALCULATIONS

VENTING:

UPPER & LOWER VENTS:


O'HAGIN TAPERED LOW PROFILE COMPOSITION SHINGLE
FINISH TO MATCH ROOF. SEE DETAIL: 41/A-912 41/A-922
72.0 SQ. IN. OF AIR MOVEMENT PER VENT = 72. SQ. IN. / 144 = 0.5 SF

"UPPER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) * (0.5) / (0.5 SF)

"LOWER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) * (0.5) / (0.5 SF)

ATTIC	AREA	REQUIRED ATTIC VENTING (NFA)	UPPER VENTING REQUIRED (NFA)	LOWER VENTING REQUIRED (NFA)
ATTIC 1 - PLAN 1	480 SF	1.60 SF	0.80 SF	0.80 SF

VENT TYPE	COUNT	VENT LENGTH	NET FREE AREA PER VENT	PROVIDED NET FREE AREA
ATTIC 1 - PLAN 1 LOWER O'HAGIN SHINGLE ROOF VENT (LOWER)	2	2' - 8"	0.50 SF	1.00 SF
UPPER O'HAGIN SHINGLE ROOF VENT (UPPER)	2	2' - 8"	0.50 SF	1.00 SF
				2.00 SF



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU


CITY OF WALNUT CREEK

ROOF PLAN & REFLECTED
CEILING PLAN - CAL RANCH

DATE
02/10/2023

SHEET

A1-121



2

PLAN 1 - REFLECTED CEILING PLAN

A1-201 | A1-122 SCALE: 1/4" = 1'-0"

1

PLAN 1 - COTTAGE - ROOF PLAN

A1-201 | A1-122 SCALE: 1/4" = 1'-0"

ROOF PLAN GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
 - REFER TO STRUCTURAL PLANS FOR ROOF FRAMING INFORMATION INCLUDING MEMBER SIZES AND CONNECTION HARDWARE.
 - PROVIDE A MINIMUM OF 1 INCH OF AIRSPACE BETWEEN THE INSULATION AND ROOF SHEATHING.
 - WHERE THE ROOF PROFILE ALLOWS A SPACE BETWEEN THE ROOF COVERING AND DECKING, THE SPACES SHALL BE CONSTRUCTED TO PREVENT THE INTRUSION OF FLAMES AND EMBERS, BE FIRESTOPPED WITH APPROVED MATERIALS OR HAVE ONE LAYER OF MINIMUM 72 POUND MINERAL-SURFACED NONPERFORATED CAP SHEET OVER THE COMBUSTIBLE DECKING.
 - ALL ROOFING MATERIALS TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
 - OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO ROOF EDGE.
 - ROOF COVERINGS SHALL BE APPLIED IN ACCORDANCE WITH (**CRC R905**), AND MANUFACTURER'S INSTALLATION INSTRUCTIONS. ROOF COVERINGS SHALL BE INSTALLED TO RESIST THE COMPONENT AND CLADDING LOADS SPECIFIED IN R301.2.1(1), AND ADJUSTED FOR HEIGHT AND EXPOSURE IN ACCORDANCE WITH TABLE R301.2.1(2).
 - ROOF UNDERLAYMENTS SHALL BE IN ACCORDANCE WITH WITH SECTION R905.1.1, TABLE R905.1.1(2), AND TABLE R905.1.1(1).
 - ROOF VENTS SHALL BE APPLIED PER MANUFACTURER'S SPECIFICATIONS.
- FURNISHED DIMENSIONS FOR VENTS ARE GUIDES ONLY. INSTALL PER MANUFACTURER'S SPECIFICATIONS AND ADJUST TO ACCOMMODATE TRUSS LOCATIONS, PLUMBING VENTS, AND SOLAR COLLECTORS.
- ENCLOSED ATTICS AND ENCLOSED RAFTER SPACES FORMED WHERE CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS SHALL HAVE CROSS VENTILATION FOR EACH SEPARATE SPACE BY VENTILATING OPENINGS PROTECTED AGAINST THE ENTRANCE OF RAIN OR SNOW. VENTILATING OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16 INCH (1.6 MM) MINIMUM AND 1/4 INCH (6.4 MM) MAXIMUM. VENTILATION OPENINGS HAVING A LEAST DIMENSION LARGER THAN 1/4 INCH (6.4 MM) SHALL BE PROVIDED WITH CORROSION-RESISTANT WIRE CLOTH SCREENING, HARDWARE CLOTH, PERFORATED VINYL, OR SIMILAR MATERIAL WITH OPENINGS HAVING A LEAST DIMENSION OF 1/16 INCH (1.6 MM) MINIMUM AND 1/4 INCH (6.4 MM) MAXIMUM. OPENINGS IN ROOF FRAMING MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF SECTION R802.7. REQUIRED VENTILATION OPENINGS SHALL OPEN DIRECTLY TO THE OUTSIDE AIR AND SHALL BE PROTECTED TO PREVENT THE ENTRY OF BIRDS, RODENTS, SNAKES AND OTHER SIMILAR CREATURES (**CRC R806**).
- THE MINIMUM NET FREE VENTILATING AREA SHALL COMPLY WITH **CRC R806.2**.
 - IN THE INSTANCE OF UPPER VENTS, VENTS SHALL BE LOCATED NO MORE THAN 3 FT BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. **CRC R806.2**.

ROOF VENTING CALCULATIONS

VENTING:

UPPER & LOWER VENTS:

O'HAGIN TAPERED LOW PROFILE COMPOSITION SHINGLE
FINISH TO MATCH ROOF. SEE DETAIL: 41/A-912 41/A-922
72.0 SQ. IN. OF AIR MOVEMENT PER VENT = 72. SQ. IN. / 144 = 0.5 SF

"UPPER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) * (0.5) / (0.5 SF)

"LOWER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) * (0.5) / (0.5 SF)

ATTIC	AREA	REQUIRED ATTIC VENTING (NFA)	UPPER VENTING REQUIRED (NFA)	LOWER VENTING REQUIRED (NFA)
ATTIC 1 - PLAN 1	480 SF	1.60 SF	0.80 SF	0.80 SF

VENT TYPE	COUNT	VENT LENGTH	NET FREE AREA PER VENT	PROVIDED NET FREE AREA
ATTIC 1 - PLAN 1				
LOWER				
O'HAGIN SHINGLE ROOF VENT (LOWER)	2	2' - 8"	0.50 SF	1.00 SF
UPPER				
O'HAGIN SHINGLE ROOF VENT (UPPER)	2	2' - 8"	0.50 SF	1.00 SF
				2.00 SF

RCP GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-102 FOR ADDITIONAL REQUIREMENTS.
- HEIGHT OF CEILINGS SHALL BE MEASURED FROM TOP OF SLAB OR FLOOR TO FINISH FACE OF GWB, U.N.O.
- REFER TO DETAILS FOR FLOOR/CEILING ASSEMBLIES.
- REFER TO ELECTRICAL PLANS FOR LIGHT FIXTURE AND EXHAUST LOCATIONS.
- DIMENSIONS ARE TO THE FACE OF FRAMING UNLESS OTHERWISE NOTED.
- SOFFITS ARE TO BE HELD TIGHT TO UNDERSIDE OF MECHANICAL EQUIPMENT.

KEYNOTES


F03	22" X 30" MINIMUM ATTIC ACCESS. PROVIDED SWITCH AND OUTLET AT ATTIC. THERE IS NO HVAC EQUIPMENT (SUCH AS FURNACE, HEAT PUMP, OR FAU) IN THE ATTIC. PERMANENTLY ATTACH R-38 OR GREATER INSULATION TO ATTIC ACCESS DOOR USING ADHESIVE OR MECHANICAL FASTENERS CEN 150.0 (a). PROVIDE GASKETED ATTIC ACCESS TO PREVENT AIR LEAKAGE CEN 150.0 (a)1."
H07	BUILDING LINE BELOW.
H12	ATTIC VENT (LOW); LOWER VENTILATORS SHALL BE LOCATED IN THE BOTTOM ONE-THIRD OF THE ATTIC SPACE PER R806.2 EXCEPTION 2. PROVIDE DAMPER TO PROVIDE 1" CLR. AIRSPACE WHERE REQ. PAINT FINISH TO MATCH ROOF COLOR, SEE VENTING CALC.
H13	ATTIC VENT (HIGH); UPPER VENTILATORS SHALL BE LOCATED NOT MORE THAN 3 FEET BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. PAINT FINISH TO MATCH ROOF COLOR, SEE VENTING CALC.
H22	AREA OF ATTIC WITH AT LEAST 30" OF HEIGHT, SEE SECTION.
H23	WHERE AIRFLOW IS BLOCKED BY SHEAR PANEL, PROVIDE MINIMUM OF 12"X12" BLOCKED OPENING TO PROVIDE CROSS-VENTILATION.
K05	COMPOSITE ROOF SHINGLES, SEE MATERIALS LEGEND FOR MORE INFORMATION.
K14	EXTERIOR SOFFIT, SEE COVER PAGE FOR MATERIAL SELECTION, SEE DETAILS FOR MORE INFORMATION.
M01	GUTTER, CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4. SEE DETAIL 12A-903
M02	DOWNSPOUT DOWNSPOUT TO SPLASH BLOCK BELOW. SEE DETAIL 12A-903.

X: SETBACK AT RIDGE TABLE

PV ARRAYS PERCENT OF THE PLAN VIEW TOTAL ROOF AREA	(X) HORIZONTAL RIDGE SETBACK
≤33%	18" BOTH SIDES OF RIDGE
>33%	36" BOTH SIDES OF RIDGE
≥66% + 13D SPRINKLER	18" BOTH SIDES OF RIDGE
>66% + 13D SPRINKLER	36" BOTH SIDES OF RIDGE

ROOF PLAN & RCP LEGEND

	CEILING HEIGHT (SEE PLAN FOR ACTUAL HEIGHTS)
	INTERIOR - GYPSUM BOARD CEILING
	EXTERIOR SOFFITS, RAKES, & EAVES; SEE TITLE SHEET FOR MATERIAL SELECTION AND CORRESPONDING DETAILS FOR MORE INFORMATION.
	COMPOSITE ASPHALT SHINGLE ROOF; SEE MATERIALS LEGEND ON ELEVATION SHEET FOR MORE INFORMATION.
	ROOF SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
	CEILING SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
	22"X30" MIN. ATTIC ACCESS PANEL (WHERE REQ.)
	DORMER STYLE ROOF VENT, SEE ROOF VENTING CALCULATIONS
	OUTLINE OF WALL BELOW
	GUTTER, CONNECT TO DOWNSPOUT; SEE DETAIL: 12/A-903
	APPROXIMATE LOCATION OF DOWNSPOUT/LEADER TO ROOF OR SPLASHBLOCK BELOW; SEE DETAILS:
	AVAILABLE SOLAR ZONE LOCATIONS; PV SYSTEM IS MANDATORY IF THE CONDITIONED AREA IS MORE THAN 652 SQUARE FEET, OTHERWISE IT'S OPTIONAL TO INSTALL A PV SYSTEM. WHEN PV SYSTEM IS INSTALLED, IT SHALL BE UNDER A SEPERATE PERMIT. SEE TITLE 24 REPORT FOR MORE INFORMATION
	AREA OF ATTIC WITH 30" HEIGHT OR GREATER. 22" X 30" CLEAR OPENING ACCESS REQUIRED IF TOTAL AREA GREATER THAN 30 SQ. FT. PER CRC R807.1



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU


CITY OF WALNUT CREEK

ROOF PLAN & REFLECTED
CEILING PLAN - COTTAGE


DATE
02/10/2023

SHEET

A1-122



1 PLAN 1 - MODERN REFLECTED CEILING PLAN
A1-201 | A1-123 SCALE: 1/4" = 1'-0"



2 PLAN 1 - MODERN - ROOF PLAN
A1-201 | A1-123 SCALE: 1/4" = 1'-0"

ROOF PLAN GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
- REFER TO STRUCTURAL PLANS FOR ROOF FRAMING INFORMATION INCLUDING MEMBER SIZES AND CONNECTION HARDWARE.
- PROVIDE A MINIMUM OF 1 INCH OF AIRSPACE BETWEEN THE INSULATION AND ROOF SHEATHING.
- WHERE THE ROOF PROFILE ALLOWS A SPACE BETWEEN THE ROOF COVERING AND DECKING, THE SPACES SHALL BE CONSTRUCTED TO PREVENT THE INTRUSION OF FLAMES AND EMBERS, BE FIRESTOPPED WITH APPROVED MATERIALS OR HAVE ONE LAYER OF MINIMUM 72 POUND MINERAL-SURFACED NONPERFORATED CAP SHEET OVER THE COMBUSTIBLE DECKING.
- ALL ROOFING MATERIALS TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
- OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO ROOF EDGE.
- ROOF COVERINGS SHALL BE APPLIED IN ACCORDANCE WITH (CRC R905), AND MANUFACTURER'S INSTALLATION INSTRUCTIONS. ROOF COVERINGS SHALL BE INSTALLED TO RESIST THE COMPONENT AND CLADDING LOADS SPECIFIED IN R301.2.1(1), AND ADJUSTED FOR HEIGHT AND EXPOSURE IN ACCORDANCE WITH TABLE R301.2.1(2).
- ROOF UNDERLAYMENTS SHALL BE IN ACCORDANCE WITH WITH SECTION R905.1.1, TABLE R905.1.1(2), AND TABLE R905.1.1(1).
- ROOF VENTS SHALL BE APPLIED PER MANUFACTURER'S SPECIFICATIONS.

FURNISHED DIMENSIONS FOR VENTS ARE GUIDES ONLY. INSTALL PER MANUFACTURER'S SPECIFICATIONS AND ADJUST TO ACCOMMODATE TRUSS LOCATIONS, PLUMBING VENTS, AND SOLAR COLLECTORS.

ENCLOSED ATTICS AND ENCLOSED RAFTER SPACES FORMED WHERE CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS SHALL HAVE CROSS VENTILATION FOR EACH SEPARATE SPACE BY VENTILATING OPENINGS PROTECTED AGAINST THE ENTRANCE OF RAIN OR SNOW. VENTILATING OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16 INCH (1.6 MM) MINIMUM AND 1/4 INCH (6.4 MM) MAXIMUM. VENTILATING OPENINGS HAVING A LEAST DIMENSION LARGER THAN 1/4 INCH (6.4 MM) SHALL BE PROVIDED WITH CORROSION-RESISTANT WIRE CLOTH SCREENING, HARDWARE CLOTH, PERFORATED VINYL, OR SIMILAR MATERIAL WITH OPENINGS HAVING A LEAST DIMENSION OF 1/16 INCH (1.6 MM) MINIMUM AND 1/4 INCH (6.4 MM) MAXIMUM. OPENINGS IN ROOF FRAMING MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF SECTION R802.7. REQUIRED VENTILATION OPENINGS SHALL OPEN DIRECTLY TO THE OUTSIDE AIR AND SHALL BE PROTECTED TO PREVENT THE ENTRY OF BIRDS, RODENTS, SNAKES AND OTHER SIMILAR CREATURES (CRC R806).
- THE MINIMUM NET FREE VENTILATING AREA SHALL COMPLY WITH CRC R806.2.
- IN THE INSTANCE OF UPPER VENTS, VENTS SHALL BE LOCATED NO MORE THAN 3 FT BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. CRC R806.2.

ROOF VENTING CALCULATIONS

ATTIC	AREA	REQUIRED ATTIC VENTING (NFA)	UPPER VENTING REQUIRED (NFA)	LOWER VENTING REQUIRED (NFA)
ATTIC 1 - PLAN 1	402 SF	1.34 SF	0.67 SF	0.67 SF

NOTE: SEE TITLE PAGE FOR VENTING OPTION SELECTION; STRIKE THROUGH NON-USED ITEMS

OPTION A RIDGE AND SOFFIT VENTS

"UPPER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) * (0.5) / (0.35 SF)

CONTINUOUS RIDGE VENTING WITH 2 1/2" HOLES IN SHEATHING. SEE DETAIL: 42/A-932

50.0 SQ. IN OF AIR MOVEMENT PER 120" = 50.0 SQ. IN. / 144 = 0.35 SF

"LOWER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) * (0.5) / (0.35 SF)

VULCAN 120" CONTINUOUS SOFFIT VENT.
ALTERNATIVE PRODUCT SHALL PROVIDE EQUAL OR GREATER NFA. SEE DETAIL: 51/A-932

96.0 SQ. IN OF AIR MOVEMENT PER VENT = 96.0 SQ. IN. / 144 = 0.67 SF

VENT TYPE	COUNT	LENGTH	NET FREE AREA PER VENT	PROVIDED NET FREE AREA
ATTIC 1 - PLAN 1 - A HIGH				
Vulcan Ridge Vent - High	4	10'-0"	0.35 SF	1.39 SF
LOW				
Vulcan Soffit Vent - Low	2	10'-0"	0.67 SF	1.33 SF
				2.72 SF

OPTION B DORMER VENTS

UPPER & LOWER VENTS (RECOMMENDED):

VULCAN VENT VDLR419 13" X 19" - SEE DETAIL: 52/A-932
ALTERNATIVE PRODUCT SHALL PROVIDE EQUAL OR GREATER NFA.
52.0 SQ. IN OF AIR MOVEMENT PER VENT = 52.0 SQ. IN. / 144 = 0.36 SF

"UPPER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) * (0.5) / (0.36 SF)

"LOWER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) * (0.5) / (0.36 SF)

VENT TYPE	COUNT	VENT LENGTH	NET FREE AREA PER VENT	PROVIDED NET FREE AREA
ATTIC 1 - PLAN 1 - B HIGH				
Vulcan Roof Vent - High	2	1' - 2"	0.36 SF	0.72 SF
LOW				
Vulcan Roof Vent - Low	2	1' - 2"	0.36 SF	0.72 SF
				1.44 SF

RCP GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-102 FOR ADDITIONAL REQUIREMENTS.
- HEIGHT OF CEILINGS SHALL BE MEASURED FROM TOP OF SLAB OR FLOOR TO FINISH FACE OF GWB, U.N.O.
- REFER TO DETAILS FOR FLOOR/CEILING ASSEMBLIES.
- REFER TO ELECTRICAL PLANS FOR LIGHT FIXTURE AND EXHAUST LOCATIONS.
- DIMENSIONS ARE TO THE FACE OF FRAMING UNLESS OTHERWISE NOTED.
- SOFFITS ARE TO BE HELD TIGHT TO UNDERSIDE OF MECHANICAL EQUIPMENT.

KEYNOTES


F03	22" X 30" MINIMUM ATTIC ACCESS. PROVIDED SWITCH AND OUTLET AT ATTIC. THERE IS NO HVAC EQUIPMENT (SUCH AS FURNACE, HEAT PUMP, OR FAU) IN THE ATTIC. PERMANENTLY ATTACH R-38 OR GREATER INSULATION TO ATTIC ACCESS DOOR USING ADHESIVE OR MECHANICAL FASTENERS CEN 150.0 (a)1. PROVIDE GASKETED ATTIC ACCESS TO PREVENT AIR LEAKAGE CEN 150.0 (a)1.
H18	DORMER VENT (LOW). ATTIC VENTING OPTION B. STRIKE THROUGH IF NOT USED. SEE VENTING CALCS.
H19	DORMER VENT (HIGH). ATTIC VENTING OPTION B. STRIKE THROUGH IF NOT USED. SEE VENTING CALCS.
H20	RIDGE VENT (HIGH). ATTIC VENTING OPTION A. STRIKE THROUGH IF NOT USED. SEE VENTING CALCS.
H21	SOFFIT VENT (LOW). ATTIC VENTING OPTION A. STRIKE THROUGH IF NOT USED. SEE VENTING CALCS.
H22	AREA OF ATTIC WITH AT LEAST 30" OF HEIGHT. SEE SECTION.
K08	METAL ROOF. SEE MATERIALS LEGEND FOR MORE INFORMATION.
K14	EXTERIOR SOFFIT. SEE COVER PAGE FOR MATERIAL SELECTION. SEE DETAILS FOR MORE INFORMATION.
L04	FAUX RAFTER TAILS. 24" O.C. PROVIDE BLOCKING AS NEEDED. REQ. PRIMER & 2 COATS EXT. GRADE PAINT.
M01	GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4. SEE DETAIL 12/A-903.
M02	DOWNSPOUT DOWNSPOUT TO SPLASH BLOCK BELOW. SEE DETAIL 12/A-903.
U11	WOOD BEAM / HEADER. REFER TO STRUCTURAL.
U13	FAUX OUTRIGGER. SEE STRUCTURAL AND DETAILS FOR MORE INFORMATION.

X: SETBACK AT RIDGE TABLE

PV ARRAYS PERCENT OF THE PLAN VIEW TOTAL ROOF AREA	(X) HORIZONTAL RIDGE SETBACK
≤33%	18" BOTH SIDES OF RIDGE
>33%	36" BOTH SIDES OF RIDGE
≤66% + 13D SPRINKLER	18" BOTH SIDES OF RIDGE
>66% + 13D SPRINKLER	36" BOTH SIDES OF RIDGE

ROOF PLAN & RCP LEGEND

	XX'-X" CEILING HEIGHT (SEE PLAN FOR ACTUAL HEIGHTS)
	INTERIOR - GYPSUM BOARD CEILING
	EXTERIOR SOFFITS, RAKES, & EAVES; SEE TITLE SHEET FOR MATERIAL SELECTION AND CORRESPONDING DETAILS FOR MORE INFORMATION.
	STANDING SEAM METAL ROOF; SEE MATERIALS LEGEND ON ELEVATION SHEET FOR MORE INFORMATION.
	X: 12 ROOF SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
	X: 12 CEILING SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
	22"X30" MIN. ATTIC ACCESS PANEL (WHERE REQ.)
	CONT. ATTIC VENTING OPTION A, MARK WITH "X" IF NOT USED. SEE ROOF VENTING CALCS.
	ATTIC ROOF VENT OPTION B, MARK WITH "X" IF NOT USED. SEE ROOF VENTING CALCS.
	OUTLINE OF WALL BELOW
	GUTTER, CONNECT TO DOWNSPOUT; SEE DETAIL: 12/A-903
	APPROXIMATE LOCATION OF DOWNSPOUT/LEADER TO ROOF OR SPLASHBLOCK BELOW; SEE DETAILS:
	AVAILABLE SOLAR ZONE LOCATIONS: PV SYSTEM IS MANDATORY IF THE CONDITIONED AREA IS MORE THAN 652 SQUARE FEET, OTHERWISE IT'S OPTIONAL TO INSTALL A PV SYSTEM. WHEN PV SYSTEM IS INSTALLED, IT SHALL BE UNDER A SEPARATE PERMIT. SEE TITLE 24 REPORT FOR MORE INFORMATION
	AREA OF ATTIC WITH 30" HEIGHT OR GREATER. 22" X 30" CLEAR OPENING ACCESS REQUIRED IF TOTAL AREA GREATER THAN 30 SQ. FT. PER CRC R807.1



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK


ROOF PLAN & REFLECTED
CEILING PLAN - MODERN

DATE
02/10/2023


SHEET

A1-123


1/10/2023 1:45:44 PM
C:\Users\jfox\Documents\2684-01-CU21_Walnut Creek ADU_Central 2022_jfoxDEV\TU.rvt




2 PLAN 1 - CAL RANCH - LEFT ELEVATION
A1-101 | A1-201 SCALE: 1/4" = 1'-0"




4 PLAN 1 - CAL RANCH - RIGHT ELEVATION
A1-101 | A1-201 SCALE: 1/4" = 1'-0"




6 PLAN 1 - CALIFORNIA RANCH - SECTION 02
A1-101 | A1-201 SCALE: 1/4" = 1'-0"



1 PLAN 1 - CAL RANCH - FRONT ELEVATION
A1-101 | A1-201 SCALE: 1/4" = 1'-0"



3 PLAN 1 - CAL RANCH - REAR ELEVATION
A1-101 | A1-201 SCALE: 1/4" = 1'-0"



5 PLAN 1 - CALIFORNIA RANCH - SECTION 01
A1-101 | A1-201 SCALE: 1/4" = 1'-0"

MATERIALS LEGEND CALIFORNIA RANCH

NOTES:

- SEE TITLE SHEET FOR MATERIAL SELECTIONS. APPLICANT OR OWNER TO PROVIDE MANUFACTURER AND COLOR/FINISH.
- ALL MATERIAL SELECTIONS SHALL COMPLY WITH CRC, SECTION R703.

GRAPHICS LEGEND: (SEE TITLE SHEET; STRIKE THROUGH NON-USED OPTIONS)

	HORIZONTAL SIDING 4" MIN. TO 12" MAX. BOARD EXPOSURE OPTION A: FIBER CEMENT (PER CRC R703.10) OPTION B: WOOD SIDING (PER CRC 703.5.3)
	BRICK VENEER WITH BRICK WAINSCOT ADHERED MASONRY VENEER (PER CRC 703.12) (SEE SHEET A-913 FOR REFERENCE DETAILS)
	ASPHALT COMPOSITE ROOF SHINGLES - CLASS C MIN. REQUIRED. (SHALL COMPLY WITH CRC R905.2.4, CRC R905.1, TABLE R905.1.1(1), TABLE R905.1.1(2) & ASTM D3462)
	EAVES, RAKES, & EXT. SOFFIT MATERIAL (SEE REFLECTED CEILING PLAN) OPTION A: FIBER CEMENT OPTION B: EXTERIOR TOUNGE & GROOVE OPTION C: EXTERIOR GRADE PLYWOOD

SIZE, MANUFACTURER, & PRODUCT INFORMATION:

COLOR/FINISH:

SIDING:

TRIM:

NO ATTIC ACCESS REQ. PER CRC R807

CL

CL

CL

CL

CL

CL

SECTIONS GENERAL NOTES

- THE PURPOSE OF THESE DRAWINGS IS TO SHOW CONSTRUCTION MATERIALS/ASSEMBLIES. FOR SPECIFIC SIZES AND DETAILS REFER TO ARCHITECTURAL PLANS, ELEVATIONS, DETAILS, AND STRUCTURAL PLANS. "KEYNOTES ONLY APPLY IF REFERENCED ON PLANS.
- WALL ASSEMBLIES TO BE PER FLOOR PLAN.
- DOORS AND WINDOWS TO BE PER APPLICABLE SCHEDULE. REFER TO FLOOR PLANS FOR IDENTIFICATION.
- INSULATION: REFER TO TITLE 24 REPORT AND "INSULATION" NOTES ON SHEET FOR ADDITIONAL RATINGS, REQUIREMENTS, AND INFORMATION.
- FIREBLOCKING TO BE LOCATED PER **CRC SECTION R302.11**:
 - SECTION R302.11.1**: FIREBLOCKING SHALL BE PROVIDED IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS, INCLUDING FURRED SPACES AND PARALLEL ROWS OF STUDS OR STAGGERED STUDS, AS FOLLOWS:
 - VERTICALLY AT CEILING AND FLOOR LEVELS.
 - HORIZONTALLY AT INTERVALS NOT EXCEEDING 10 FEET.
 - AT INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS SOFFITS, DROP CEILINGS AND COVE CEILINGS.
 - IN CONCEALED SPACES BETWEEN STAIR STRINGERS AT THE TOP AND BOTTOM OF THE RUN, ENCLOSED SPACES UNDER STAIRS SHALL COMPLY WITH **SECTION R302.7**.
 - AT OPENINGS AROUND VENTS, PIPES, DUCTS, CABLES AND WIRES AT CEILINGS AND FLOOR LEVEL, WITH AN APPROVED MATERIAL TO RESIST THE FREE PASSAGE OF FLAME PRODUCTS OF COMBUSTION. THE MATERIAL FILLING THIS ANNULAR SPACE SHALL NOT BE REQUIRED TO MEET THE ASTM E136 REQUIREMENTS.
 - FOR THE FIREBLOCKING OF CHIMNEYS AND FIREPLACES, SEE **SECTION R1003.19**.
 - FIREBLOCKING OF CORNICES OF A TWO-FAMILY DWELLING IS REQUIRED AT THE LINE OF DWELLING-UNIT SEPARATION.
- SECTION R302.11.1** - FIREBLOCKING MATERIALS SHALL CONSIST OF FOLLOWING MATERIALS:
 - TWO-INCH NOMINAL LUMBER
 - TWO THICKNESSES OF ONE-INCH NOMINAL LUMBER WITH BROKEN LAP JOINTS
 - THE THICKNESS OF 0.719-INCH WOOD STRUCTURAL PANELS WITH JOINTS BACKED BY 0.719-INCH WOOD STRUCTURAL PANELS
 - THE THICKNESS OF 0.75-INCH PARTICLE BOARD WITH JOINTS BACKED BY 0.75-INCH PARTICLE BOARD
 - ONE-HALF-INCH GYPSUM BOARD
 - ONE-FOURTH-INCH CEMENT-BASED MILLBOARD
 - BATTS OR BLANKETS OF MINERAL WOOL, MINERAL FIBER OR OTHER APPROVED MATERIAL INSTALLED IN SUCH A MANNER AS TO BE SECURELY RETAINED IN PLACE
 - CELLULOSE INSULATION INSTALLED AS TESTED IN ACCORDANCE WITH ASTM E119 OR UL 263, FOR THE SPECIFIC APPLICATION.
- PER **CRC SECTION R317** SLEEPERS AND SILLS ON A CONCRETE OR MASONRY SLAB THAT IS IN DIRECT CONTACT WITH GROUND, UNLESS SEPARATED BY AN IMPERVIOUS MOISTURE BARRIER SHALL BE NATURALLY DURABLE OR PRESERVATIVE-TREATED WOOD IN ACCORDANCE WITH AWPA U1.
- REFER TO RCP'S FOR SOFFIT DIMENSIONS AND FURTHER INFORMATION.
- PROVIDE BLOCKING FOR ALL WALLS WHERE WALL HUNG EQUIPMENT AND FIXTURES OCCUR.
- ALL WALL AND CEILING FINISHES SHALL COMPLY WITH **CRC 803.13** FOR MAXIMUM FLAME SPREAD AND SMOKE DENSITY.

GENERAL ELEVATION NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS
- SEE DETAILS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
- REFER TO ROOF PLAN FOR OVERHANGS. FASCIA PER DETAILS. PROVIDE ALUMINUM GUTTER. SEE ROOF PLAN FOR APPROXIMATE DOWNSPOUT LOCATIONS, U.N.O.
- REFER TO DOOR AND WINDOW SCHEDULES AND TYPES FOR DOOR AND WINDOW INFORMATION.
- THE NOMINAL THICKNESS AND ATTACHMENT OF EXTERIOR WALL COVERINGS SHALL BE IN ACCORDANCE WITH CRC TABLE R703.3(1).
- GYPSUM SHEATHING SHALL BE ATTACHED TO EXTERIOR WALLS IN ACCORDANCE WITH CRC TABLE R802.3
- CLADDING ATTACHMENT OVER FOAM SHEATHING TO WOOD FRAMING IN ACCORDANCE WITH CRC R703.15. REFER TO CRC R703.8 FOR ANCHORED MASONRY OR STONE VENEER INSTALLED OVER FOAM SHEATHING.

KEYNOTES

- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE. PROVIDE PROTECTION PER CPC 507.25 & CMC 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL & ELECTRICAL PLANS" SHEET FOR MORE INFO. SEE DETAIL 53/A-902.
- B47 40 GALLON HEAT PUMP WATER HEATER. PROVIDE ENCLOSURE IN COMPLIANCE WITH CPC 507.25. PROVIDE CONCRETE PAD 3" MIN. ABOVE GRADE. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. SEE DETAIL 22/A-901. PROVIDE PROTECTION PER CMC 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL & ELECTRICAL PLANS" SHEET FOR MORE INFORMATION. SEE DETAIL 53/A-902.
- H05 ROOF EDGE/FASCIA. SEE DETAILS FOR FASCIA TYPE.
- H12 ATTIC VENT (LOW); LOWER VENTILATORS SHALL BE LOCATED IN THE BOTTOM ONE-THIRD OF THE ATTIC SPACE PER R806.2 EXCEPTION 2. PROVIDE DAMPER TO PROVIDE 1" CLR. AIRSPACE WHERE REQ. PAINT FINISH TO MATCH ROOF COLOR, SEE VENTING CALCS.
- H13 ATTIC VENT (HIGH); UPPER VENTILATORS SHALL BE LOCATED NOT MORE THAN 3 FEET BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. PAINT FINISH TO MATCH ROOF COLOR, SEE VENTING CALCS.
- H23 WHERE AIRFLOW IS BLOCKED BY SHEAR PANEL, PROVIDE MINIMUM OF 12"x12" BLOCKED OPENING TO PROVIDE CROSS-VENTILATION.
- K01 HORIZONTAL SIDING. SEE MATERIALS LEGEND FOR MORE INFORMATION.
- K05 COMPOSITE ROOF SHINGLES. SEE MATERIALS LEGEND FOR MORE INFORMATION.
- K06 BRICK VENEER WITH WAINSCOT. SEE SHEET A-913 FOR DETAILS AND SEE MATERIALS LEGEND FOR MORE INFORMATION.
- K13 WINDOW PER PLAN
- L02 CORNER TRIM. SEE DETAILS FOR MORE INFORMATION.
- L11 DECORATIVE KNEE BRACE. SEE DETAIL 42/A-912.
- L21 DECORATIVE FAUX SHUTTERS. SEE DETAIL 23/A-912.
- M01 GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4. SEE DETAIL 12/A-903.
- M02 DOWNSPOUT DOWNSPOUT TO SPLASH BLOCK BELOW. SEE DETAIL 12/A-903.
- S03 R-38 MIN. ROOF INSULATION; RADIANT BARRIER REQUIRED (VERIFY WITH TITLE 24 REPORT).
- S04 2X6 WALL INSULATION. REFER TO TITLE 24 (R-21 MIN.)
- T02 2X6 WOOD STUD WALL. REFER TO STRUCTURAL
- T12 WOOD POST. SEE STRUCTURAL - REQUIRED; PRIMER & 2 COATS OF EXTERIOR GRADE PAINT.



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK

ELEVATIONS & BUILDING
SECTIONS - CAL RANCH

DATE
02/10/2023

SHEET

A1-201



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

SECTIONS GENERAL NOTES

- THE PURPOSE OF THESE DRAWINGS IS TO SHOW CONSTRUCTION MATERIALS/ASSEMBLIES. FOR SPECIFIC SIZES AND DETAILS REFER TO ARCHITECTURAL PLANS, ELEVATIONS, DETAILS, AND STRUCTURAL PLANS. *KEYNOTES ONLY APPLY IF REFERENCED ON PLANS.
- WALL ASSEMBLIES TO BE PER FLOOR PLAN.
- DOORS AND WINDOWS TO BE PER APPLICABLE SCHEDULE. REFER TO FLOOR PLANS FOR IDENTIFICATION.
- INSULATION: REFER TO TITLE 24 REPORT AND "INSULATION" NOTES ON SHEET FOR ADDITIONAL RATINGS, REQUIREMENTS, AND INFORMATION.
- FIREBLOCKING TO BE LOCATED PER **CRC SECTION R302.11**:
 - SECTION R302.11**:
 - FIREBLOCKING SHALL BE PROVIDED IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS, INCLUDING FURRED SPACES AND PARALLEL ROWS OF STUDS OR STAGGERED STUDS, AS FOLLOWS:
 - VERTICALLY AT CEILING AND FLOOR LEVELS.
 - HORIZONTALLY AT INTERVALS NOT EXCEEDING 10 FEET.
 - AT INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS SOFFITS, DROP CEILINGS AND COVE CEILINGS.
 - IN CONCEALED SPACES BETWEEN STAIR STRINGERS AT THE TOP AND BOTTOM OF THE RUN, ENCLOSED SPACES UNDER STAIRS SHALL COMPLY WITH **SECTION R302.7**.
 - AT OPENINGS AROUND VENTS, PIPES, DUCTS, CABLES AND WIRES AT CEILINGS AND FLOOR LEVEL, WITH AN APPROVED MATERIAL TO RESIST THE FREE PASSAGE OF AIR AND FLOOR JOISTS. THE MATERIAL FILLING THIS ANNULAR SPACE SHALL NOT BE REQUIRED TO MEET THE ASTM E136 REQUIREMENTS.
 - FOR THE FIREBLOCKING OF CHIMNEYS AND FIREPLACES, SEE **SECTION R1003.19**.
 - FIREBLOCKING OF CORNICES OF A TWO-FAMILY DWELLING IS REQUIRED AT THE LINE OF DWELLING-UNIT SEPARATION.
 - SECTION R302.11.1** - FIREBLOCKING MATERIALS SHALL CONSIST OF FOLLOWING MATERIALS:
 - TWO-INCH NOMINAL LUMBER
 - TWO THICKNESSES OF ONE-INCH NOMINAL LUMBER WITH BROKEN LAP JOINTS
 - THE THICKNESS OF 0.719-INCH WOOD STRUCTURAL PANELS WITH JOINTS BACKED BY 0.719-INCH WOOD STRUCTURAL PANELS
 - THE THICKNESS OF 0.75-INCH PARTICLE BOARD WITH JOINTS BACKED BY 0.75-INCH PARTICLE BOARD
 - ONE-HALF-INCH GYPSUM BOARD
 - ONE-FOURTH-INCH CEMENT-BASED MILLBOARD
 - BATTS OR BLANKETS OF MINERAL WOOL, MINERAL FIBER OR OTHER APPROVED MATERIAL INSTALLED IN SUCH A MANNER AS TO BE SECURELY RETAINED IN PLACE
 - CELLULOSE INSULATION INSTALLED AS TESTED IN ACCORDANCE WITH ASTM E119 OR UL 263, FOR THE SPECIFIC APPLICATION.
 - PER **CRC SECTION R317** SLEEPERS AND SILLS ON A CONCRETE OR MASONRY SLAB THAT IS IN DIRECT CONTACT WITH GROUND, UNLESS SEPARATED BY AN IMPERVIOUS MOISTURE BARRIER SHALL BE NATURALLY DURABLE OR PRESERVATIVE-TREATED WOOD IN ACCORDANCE WITH AWPA U1.
 - REFER TO RCP'S FOR SOFFIT DIMENSIONS AND FURTHER INFORMATION.
 - PROVIDE BLOCKING FOR ALL WALLS WHERE WALL HUNG EQUIPMENT AND FIXTURES OCCUR.
 - ALL WALL AND CEILING FINISHES SHALL COMPLY WITH **CRC 803.13** FOR MAXIMUM FLAME SPREAD AND SMOKE DENSITY.

GENERAL ELEVATION NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS
- SEE DETAILS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
- REFER TO ROOF PLAN FOR OVERHANGS, FASCIA PER DETAILS. PROVIDE ALUMINUM GUTTER. SEE ROOF PLAN FOR APPROXIMATE DOWNSPOUT LOCATIONS, U.N.O.
- REFER TO DOOR AND WINDOW SCHEDULES AND TYPES FOR DOOR AND WINDOW INFORMATION.
- THE NOMINAL THICKNESS AND ATTACHMENT OF EXTERIOR WALL COVERINGS SHALL BE IN ACCORDANCE WITH CRC TABLE R703.3(1).
- GYPSUM SHEATHING SHALL BE ATTACHED TO EXTERIOR WALLS IN ACCORDANCE WITH CRC TABLE R602.3.
- CLADDING ATTACHMENT OVER FOAM SHEATHING TO WOOD FRAMING IN ACCORDANCE WITH CRC R703.15. REFER TO CRC R703.8 FOR ANCHORED MASONRY OR STONE VENEER INSTALLED OVER FOAM SHEATHING.


KEYNOTES

- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE. PROVIDE PROTECTION PER CPC 507.25 & CMC 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFO. SEE DETAIL 53/A-902.
- B47 40 GALLON HEAT PUMP WATER HEATER. PROVIDE ENCLOSURE IN COMPLIANCE WITH CPC 507.25. PROVIDE CONCRETE PAD 3" MIN ABOVE GRADE. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. SEE DETAIL 22/A-901. PROVIDE PROTECTION PER CMC 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFORMATION. SEE DETAIL 53/A-902.
- H05 ROOF EDGE/FASCIA. SEE DETAILS FOR FASCIA TYPE.
- H12 ATTIC VENT (LOW); LOWER VENTILATORS SHALL BE LOCATED IN THE BOTTOM ONE-THIRD OF THE ATTIC SPACE PER R806.2 EXCEPTION 2. PROVIDE DAMPER TO PROVIDE 1" CLR. AIRSPACE WHERE REQ. PAINT FINISH TO MATCH ROOF COLOR, SEE VENTING CALC'S.
- H13 ATTIC VENT (HIGH); UPPER VENTILATORS SHALL BE LOCATED NOT MORE THAN 3 FEET BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. PAINT FINISH TO MATCH ROOF COLOR, SEE VENTING CALC'S.
- H17 CEILING SOFFIT @ GABLE PORCH ROOF.
- H23 WHERE AIRFLOW IS BLOCKED BY SHEAR PANEL, PROVIDE MINIMUM OF 12"x12" BLOCKED OPENING TO PROVIDE CROSS-VENTILATION.
- K01 HORIZONTAL SIDING. SEE MATERIALS LEGEND FOR MORE INFORMATION.
- K05 COMPOSITE ROOF SHINGLES. SEE MATERIALS LEGEND FOR MORE INFORMATION.
- K13 WINDOW PER PLAN
- L02 CORNER TRIM; SEE DETAILS FOR MORE INFORMATION.
- L03 TRIM. SEE DETAILS FOR MORE INFORMATION.
- L09 FAUX DECORATIVE VENT. SEE DETAIL 31/A-901.
- M01 GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4. SEE DETAIL 12/A-903.
- M02 DOWNSPOUT DOWNSPOUT TO SPLASH BLOCK BELOW. SEE DETAIL 12/A-903.
- P01 DECORATIVE PORCH RAILING. HEIGHT OF 24" MIN. TO 48" MAX. REQUIRED FOR WOOD: PRIMER & 2 COATS OF EXTERIOR GRADE PAINT. REQUIRED: 30 INCHES MAX VERTICAL DROP IS PROHIBITED WITHIN 36 INCHES (HORIZONTALLY) OF THE PORCH, SEE DETAIL FOR MORE INFORMATION.
- S03 R-38 MIN. ROOF INSULATION; RADIANT BARRIER REQUIRED (VERIFY WITH TITLE 24 REPORT).
- S04 2X6 WALL INSULATION. REFER TO TITLE 24 (R-21 MIN.)
- T02 2X6 WOOD STUD WALL. REFER TO STRUCTURAL.
- T12 WOOD POST, SEE STRUCTURAL - REQUIRED: PRIMER & 2 COATS OF EXTERIOR GRADE PAINT.

WALNUT CREEK ADU
CITY OF WALNUT CREEK
ELEVATIONS & BUILDING
SECTIONS - COTTAGE


DATE
02/10/2023
SHEET

A1-202




2 PLAN 1 - COTTAGE - LEFT ELEVATION

A1-101 | A1-202 SCALE: 1/4" = 1'-0"



4 PLAN 1 - COTTAGE - RIGHT ELEVATION

A1-101 | A1-202 SCALE: 1/4" = 1'-0"



6 PLAN 1 - COTTAGE - SECTION 01

A1-101 | A1-202 SCALE: 1/4" = 1'-0"

MATERIALS LEGEND COTTAGE

NOTES:

- SEE TITLE SHEET FOR MATERIAL SELECTIONS. APPLICANT OR OWNER TO PROVIDE MANUFACTURER AND COLOR/FINISH.
- ALL MATERIAL SELECTIONS SHALL COMPLY WITH CRC, SECTION R703.

GRAPHICS LEGEND: (SEE TITLE SHEET; STRIKE THROUGH NON-USED OPTIONS)

- HORIZONTAL SIDING**
4" MIN. TO 12" MAX. BOARD EXPOSURE
OPTION A: FIBER CEMENT (PER CRC R703.10)
OPTION B: WOOD SIDING (PER CRC 703.5.3)
- SHAKE/SHINGLE SIDING**
OPTION A: FIBER CEMENT (PER CRC R703.10)
OPTION B: WOOD SHAKES/SHINGLES (PER CRC R703.6)
- ASPHALT COMPOSITE ROOF SHINGLES - CLASS C MIN. REQUIRED.**
(SHALL COMPLY WITH CRC R905.2.4, CRC R905.1, TABLE R905.1.1(1), TABLE R905.1.1(2) & ASTM D3462)
- EAVES, RAKES, & EXT. SOFFIT MATERIAL (SEE REFLECTED CEILING PLAN)**
OPTION A: FIBER CEMENT
OPTION B: EXTERIOR TOUNGE & GROOVE
OPTION C: EXTERIOR GRADE PLYWOOD


SIZE, MANUFACTURER, & PRODUCT INFORMATION:

COLOR/FINISH:

SIDING:


TRIM:

(REQ. PRIMER & 2 COATS OF EXT. GRADE PAINT)




1 PLAN 1 - COTTAGE - FRONT ELEVATION

A1-101 | A1-202 SCALE: 1/4" = 1'-0"



3 PLAN 1 - COTTAGE - REAR ELEVATION


A1-101 | A1-202 SCALE: 1/4" = 1'-0"



5 PLAN 1 - COTTAGE - SECTION 02


A1-101 | A1-202 SCALE: 1/4" = 1'-0"

1/10/2023 1:45:46 PM
C:\Users\jfox\Documents\2684-01-CU21_Walnut Creek ADU_Central 2022_jfoxDEV\TU.rvt




2 PLAN 1 - MODERN - LEFT ELEVATION

A1-101 | A1-203 SCALE: 1/4" = 1'-0"




4 PLAN 1 - MODERN - RIGHT ELEVATION

A1-101 | A1-203 SCALE: 1/4" = 1'-0"




6 PLAN 1 - MODERN - SECTION 02

A1-101 | A1-203 SCALE: 1/4" = 1'-0"




1 PLAN 1 - MODERN - FRONT ELEVATION

A1-101 | A1-203 SCALE: 1/4" = 1'-0"



3 PLAN 1 - MODERN - REAR ELEVATION

A1-101 | A1-203 SCALE: 1/4" = 1'-0"



5 PLAN 1 - MODERN - SECTION 01

A1-101 | A1-203 SCALE: 1/4" = 1'-0"

SECTIONS GENERAL NOTES

- THE PURPOSE OF THESE DRAWINGS IS TO SHOW CONSTRUCTION MATERIALS/ASSEMBLIES. FOR SPECIFIC SIZES AND DETAILS REFER TO ARCHITECTURAL PLANS, ELEVATIONS, DETAILS, AND STRUCTURAL PLANS. KEYNOTES ONLY APPLY IF REFERENCED ON PLANS.
- WALL ASSEMBLIES TO BE PER FLOOR PLAN.
- DOORS AND WINDOWS TO BE PER APPLICABLE SCHEDULE. REFER TO FLOOR PLANS FOR IDENTIFICATION.
- INSULATION: REFER TO TITLE 24 REPORT AND "INSULATION" NOTES ON SHEET FOR ADDITIONAL RATINGS, REQUIREMENTS, AND INFORMATION.
- FIREBLOCKING TO BE LOCATED PER **CRC SECTION R302.11**:
 - SECTION R302.11**:
 - FIREBLOCKING SHALL BE PROVIDED IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS, INCLUDING FURRED SPACES AND PARALLEL ROWS OF STUDS OR STAGGERED STUDS, AS FOLLOWS:
 - VERTICALLY AT CEILING AND FLOOR LEVELS.
 - HORIZONTALLY AT INTERVALS NOT EXCEEDING 10 FEET.
 - AT INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS SOFFITS, DROP CEILINGS AND COVE CEILINGS.
 - IN CONCEALED SPACES BETWEEN STAIR STRINGERS AT THE TOP AND BOTTOM OF THE RUN, ENCLOSED SPACES UNDER STAIRS SHALL COMPLY WITH **SECTION R302.7**.
 - AT OPENINGS AROUND VENTS, PIPES, DUCTS, CABLES AND WIRES AT CEILINGS AND FLOOR LEVEL, WITH AN APPROVED MATERIAL TO RESIST THE FREE PASSAGE OF FLAME PRODUCTS OF COMBUSTION. THE MATERIAL FILLING THIS ANNULAR SPACE SHALL NOT BE REQUIRED TO MEET THE ASTM E136 REQUIREMENTS.
 - FOR THE FIREBLOCKING OF CHIMNEYS AND FIREPLACES, SEE **SECTION R1003.19**.
 - FIREBLOCKING OF CORNICES OF A TWO-FAMILY DWELLING IS REQUIRED AT THE LINE OF DWELLING-UNIT SEPARATION.
 - SECTION R302.11.1** - FIREBLOCKING MATERIALS SHALL CONSIST OF FOLLOWING MATERIALS:
 - TWO-INCH NOMINAL LUMBER
 - TWO THICKNESSES OF ONE-INCH NOMINAL LUMBER WITH BROKEN LAP JOINTS
 - THE THICKNESS OF 0.719-INCH WOOD STRUCTURAL PANELS WITH JOINTS BACKED BY 0.719-INCH WOOD STRUCTURAL PANELS
 - THE THICKNESS OF 0.75-INCH PARTICLE BOARD WITH JOINTS BACKED BY 0.75-INCH PARTICLE BOARD
 - ONE-HALF-INCH GYPSUM BOARD
 - ONE-FOURTH-INCH CEMENT-BASED MILLBOARD
 - BATTS OR BLANKETS OF MINERAL WOOL, MINERAL FIBER OR OTHER APPROVED MATERIAL INSTALLED IN SUCH A MANNER AS TO BE SECURELY RETAINED IN PLACE
 - CELLULOSE INSULATION INSTALLED AS TESTED IN ACCORDANCE WITH ASTM E119 OR UL 263, FOR THE SPECIFIC APPLICATION.
 - PER **CRC SECTION R317** SLEEPERS AND SILLS ON A CONCRETE OR MASONRY SLAB THAT IS IN DIRECT CONTACT WITH GROUND, UNLESS SEPARATED BY AN IMPERVIOUS MOISTURE BARRIER SHALL BE NATURALLY DURABLE OR PRESERVATIVE-TREATED WOOD IN ACCORDANCE WITH AWPA U1.
 - REFER TO RCP'S FOR SOFFIT DIMENSIONS AND FURTHER INFORMATION.
 - PROVIDE BLOCKING FOR ALL WALLS WHERE WALL HUNG EQUIPMENT AND FIXTURES OCCUR.
 - ALL WALL AND CEILING FINISHES SHALL COMPLY WITH **CRC 803.13** FOR MAXIMUM FLAME SPREAD AND SMOKE DENSITY.

GENERAL ELEVATION NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS
- SEE DETAILS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
- REFER TO ROOF PLAN FOR OVERHANGS, FASCIA PER DETAILS. PROVIDE ALUMINUM GUTTER. SEE ROOF PLAN FOR APPROXIMATE DOWNSPOUT LOCATIONS, U.N.O.
- REFER TO DOOR AND WINDOW SCHEDULES AND TYPES FOR DOOR AND WINDOW INFORMATION.
- THE NOMINAL THICKNESS AND ATTACHMENT OF EXTERIOR WALL COVERINGS SHALL BE IN ACCORDANCE WITH CRC TABLE R703.3(1).
- GYPSUM SHEATHING SHALL BE ATTACHED TO EXTERIOR WALLS IN ACCORDANCE WITH CRC TABLE R602.3.
- CLADDING ATTACHMENT OVER FOAM SHEATHING TO WOOD FRAMING IN ACCORDANCE WITH CRC R703.15. REFER TO CRC R703.8 FOR ANCHORED MASONRY OR STONE VENEER INSTALLED OVER FOAM SHEATHING.

KEYNOTES

- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE. PROVIDE PROTECTION PER CPC 507.25 & CMG 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFO. SEE DETAIL 53/A-902.
- B47 40 GALLON HEAT PUMP WATER HEATER. PROVIDE ENCLOSURE IN COMPLIANCE WITH CPC 507.25. PROVIDE CONCRETE PAD 3" MIN. ABOVE GRADE. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. SEE DETAIL 22/A-901. PROVIDE PROTECTION PER CMG 305.1.1. SEE GENERAL MEP NOTES 7 & 8 ON THE "FINISH, MECHANICAL, & ELECTRICAL PLANS" SHEET FOR MORE INFORMATION. SEE DETAIL 53/A-902.
- H05 ROOF EDGE/FASCIA. SEE DETAILS FOR FASCIA TYPE.
- H18 DORMER VENT (LOW). ATTIC VENTING OPTION B. STRIKE THROUGH IF NOT USED. SEE VENTING CALC'S.
- H19 DORMER VENT (HIGH). ATTIC VENTING OPTION B. STRIKE THROUGH IF NOT USED. SEE VENTING CALC'S.
- H20 RIDGE VENT (HIGH). ATTIC VENTING OPTION A. STRIKE THROUGH IF NOT USED. SEE VENTING CALC'S.
- H21 SOFFIT VENT (LOW). ATTIC VENTING OPTION A. STRIKE THROUGH IF NOT USED. SEE VENTING CALC'S.
- K01 HORIZONTAL SIDING, SEE MATERIALS LEGEND FOR MORE INFORMATION.
- K02 FIBER CEMENT PANELS WITH REVEALS. SEE MATERIALS LEGEND FOR MORE INFORMATION.
- K04 VERTICAL SIDING, SEE MATERIALS LEGEND FOR MORE INFORMATION.
- K08 METAL ROOF. SEE MATERIALS LEGEND FOR MORE INFORMATION.
- L10 VERTICAL TRIM @ MATERIAL CHANGE, SEE DETAILS.
- M01 GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4. SEE DETAIL 12/A-903.
- M02 DOWNSPOUT DOWNSPOUT TO SPLASH BLOCK BELOW. SEE DETAIL 12/A-903.
- S03 R-38 MIN. ROOF INSULATION; RADIANT BARRIER REQUIRED (VERIFY WITH TITLE 24 REPORT).
- S04 2X6 WALL INSULATION. REFER TO TITLE 24 (R-21 MIN.)
- T02 2X6 WOOD STUD WALL. REFER TO STRUCTURAL.
- T12 WOOD POST, SEE STRUCTURAL - REQUIRED: PRIMER & 2 COATS OF EXTERIOR GRADE PAINT.
- T20 6X8 WOOD HEADER UON, REFER TO STUCTURAL PLANS.
- T21 WOOD BEAM, SEE STRUCTURAL - REQUIRED: PRIMER & 2 COATS OF EXTERIOR GRADE PAINT.
- U11 WOOD BEAM / HEADER, REFER TO STRUCTURAL.
- U13 FAUX OUTRIGGER, SEE STRUCTURAL AND DETAILS FOR MORE INFORMATION.

MATERIALS LEGEND MODERN

NOTES:

- SEE TITLE SHEET FOR MATERIAL SELECTIONS. APPLICANT OR OWNER TO PROVIDE MANUFACTURER AND COLOR/FINISH.
- ALL MATERIAL SELECTIONS SHALL COMPLY WITH CRC, SECTION R703.

GRAPHICS LEGEND: (SEE TITLE SHEET; STRIKE THROUGH NON-USED OPTIONS)

- VERTICAL SIDING
OPTION A: FIBER CEMENT (PER CRC R703.10)
OPTION B: WOOD SIDING (PER CRC 703.5.3)
- 48" X 96" FIBER CEMENT PANELS (PER CRC R703.10)
LOCATIONS OF REVEALS PER ELEVATION
SEE DETAIL: 21/A-931
- STANDING SEAM METAL ROOF PANEL SYSTEM - CLASS C MIN. REQ.
(SHALL COMPLY WITH CRC R905.1, CRC R905.10 & CRC R905.1.1)
- EAVES, RAKES, & EXT. SOFFIT MATERIAL (SEE REFLECTED CEILING PLAN)
OPTION A: FIBER CEMENT
OPTION B: EXTERIOR TOUNGE & GROOVE
OPTION C: EXTERIOR GRADE PLYWOOD


SIZE, MANUFACTURER, & PRODUCT INFORMATION:

COLOR/FINISH:

SIDING:

TRIM:

(REQ. PRIMER & 2 COATS OF EXT. GRADE PAINT)



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK

ELEVATIONS & BUILDING
SECTIONS - MODERN

DATE
02/10/2023

SHEET

A1-203

1/10/2023 1:45:47 PM
C:\Users\jacob\Documents\264-01-CU21_Walnut Creek ADU_Central 2022_jacob\REV\T\01.rvt

UL DESIGN NO. U 356 REFER TO DETAIL: 54/A-901 FOR THROUGH WALL PENETRATIONS

WOOD STUDS, GYPSUM BOARD AND CEMENT STUCCO

1. **WOOD STUDS**
NOMINAL 2X6 SPACED 16" O.C. WITH (2) 2X4 TOP PLATES (1) 2X4 BOTTOM PLATE. STUDS LATERALLY-BRACED BY WOOD STRUCTURAL PANEL SHEATHING (ITEM 5) AND EFFECTIVELY FIRE STOPPED AT TOP AND BOTTOM OF WALL.

2. **GYPSUM BOARD**
ANY CLASSIFIED 5/8" THICK, 48" WIDE, APPLIED VERTICALLY AND NAILED TO STUDS AND BEARING PLATES 7" O.C. WITH 6D CEMENT-COATED NAILS, 1 7/8" LONG WITH 1/4" DIAM. HEAD.

JOINTS AND NAILHEADS (NOT SHOWN) - WALLBOARD JOINTS COVERED WITH TAPE AND JOINT COMPOUND. NAIL HEADS COVERED WITH JOINT COMPOUND.

3. **BATTS AND BLANKETS**
MINERAL FIBER OR GLASS INSULATION, 3 1/2" THICK, PRESSURE FIT TO FILL WALL CAVITIES BETWEEN STUDS AND PLATES. MINERAL FIBER INSULATION TO BE UNFACED AND TO HAVE A MIN. DENSITY OF 3 PCF. GLASS FIBER INSULATION TO BE FACED WITH ALUMINUM FOIL OR FRAFT PAPER AND TO HAVE A MIN. DENSITY OF 0.9 PCF (MIN. R-13 THERMAL INSULATION RATING). FIBER SPRAYED - AS AN ALTERNATE TO BATTS AND BLANKETS (ITEM 4) - SPRAY APPLIED CELLULOSE INSULATION MATERIAL. THE FIBER IS APPLIED WITH WATER TO COMPLETELY FILL THE ENCLOSED CAVITY IN ACCORDANCE WITH THE APPLICATION INSTRUCTIONS SUPPLIED WITH THE PRODUCT. NOMINAL DRY DENSITY OF 3.0 LB/CU.FT.

4. **WOOD STRUCTURAL PANEL SHEATHING**
MIN 7/16" THICK, 4 FT. WIDE WOOD STRUCTURAL PANELS, MIN. GRADE "C-D" OR "SHEATHING" - INSTALLED WITH LONG DIMENSION OF SHEET (STRENGTH AXIS) OR FACE GRAIN OF PLYWOOD PARALLEL WITH OR PERPENDICULAR TO STUDS. VERTICAL JOINTS CENTERED ON STUDS. HORIZONTAL JOINTS BACKED WITH NOMINAL 2X4 WOOD BLOCKING. ATTACHED TO STUDS ON EXTERIOR SIDE OF WALL WITH 6D CEMENT COATED BOX NAILS SPACED 6" O.C. AT PERIMETER OF PANELS AND 12" O.C. ALONG INTERIOR STUDS.

5. **EXTERIOR FACING**
INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTION. ONE OF THE FOLLOWING EXTERIOR FACINGS IS TO BE APPLIED OVER THE SHEATHING. REFER TO PLAN FOR INFOEMATION:

D. CEMENTITIOUS STUCCO - PORTLAND CEMENT OR SYNTHETIC STUCCO SYSTEM WITH SELF-FURRING METAL LATH OR ADHESIVE BASE COAT. THICKNESS FROM 3/8" TO 3/4", DEPENDING ON SYSTEM.

H. FIBER-CEMENT SIDING - FIBER-CEMENT EXTERIOR SIDING INCLUDING SMOOTH AND PATTERNED PANEL OR LAP SIDING.

UL DES U305
AT INTERIOR WALL USE:
5/8" SHEETROCK FIRE CODE CORE PANELS,
5/8" SHEETROCK ULTRALIGHT PANELS FIRE CODE X OR
5/8" FIBEROCK PANELS -
2 X 4 WOOD STUD 16" OR 24" O.C.

52 1-HR EXTERIOR RATED WALL ASSEMBLY
SCALE: 3" = 1'-0"

XHEZ-W-L-1166

WALL SYSTEM PENETRATION
F RATING - 1 AND 2 HR (SEE ITEM 1B)
T RATING - 0 HR

1. **WALL ASSEMBLY**
THE 1 OR 2 HR. FIRE RATED GYPSUM WALLBOARD/STUD WALL ASSEMBLY SHALL BE CONSTRUCTED OF THE MATERIALS AND IN THE MANNER SPECIFIED IN THE INDIVIDUAL U300 OR U400 SERIES WALL AND PARTITION DESIGNS IN THE UL FIRE RESISTANCE DIRECTORY AND SHALL INCLUDE THE FOLLOWING CONSTRUCTION FEATURES:

A. **STUDS**-
WALL FRAMING MAY CONSIST OF EITHER WOOD STUDS OR STEEL CHANNEL STUDS. WOOD STUDS TO CONSIST OF NOM. 2 IN. BY 4 IN. LUMBER SPACED 16 IN. O.C. STEEL STUDS TO BE MIN. 3 1/2 IN. WIDE AND SPACED MAX. 24 IN. O.C.

B. **GYPSUM BOARD** (BEARING THE UL CLASSIFICATION MARKING)- THICKNESS, TYPE, NUMBER OF LAYERS AND FASTENERS AS REQUIRED IN THE INDIVIDUAL WALL AND PARTITION DESIGN. MAX. DIAM. OF OPENING IS 5 IN.

THE HOURLY F RATING OF THE FIRESTOP SYSTEM IS EQUAL TO THE HOURLY FIRE RATING OF THE WALL ASSEMBLY IN WHICH IT IS INSTALLED.

2. **THROUGH-PENETRANTS**
ONE METALLIC PIPE, CONDUIT OR TUBING INSTALLED EITHER CONCENTRICALLY OR ECCENTRICALLY WITHIN THE FIRESTOP SYSTEM. THE ANNULAR SPACE BETWEEN THE PIPE, CONDUIT OR TUBING AND PERIPHERY OF THE OPENING SHALL BE MIN. OF 0 IN. (POINT CONTACT) TO A MAX. 1/8 IN. PIPE, CONDUIT OR TUBING TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF WALL ASSEMBLY. THE FOLLOWING TYPES AND SIZES OF METALLIC PIPES, CONDUITS OR TUBING MAY BE USED:

A. COPPER TUBING-
NOM. 4 IN. DIAM. (OR SMALLER) TYPE M (OR HEAVIER) COPPER TUBING.

B. COPPER PIPE-
NOM. 4 IN. DIAM. (OR SMALLER) REGULAR (OR HEAVIER) COPPER PIPE.

C. STEEL PIPE-
NOM. 4 IN. DIAM. (OR SMALLER) SCHEDULE 5 (OR HEAVIER) STEEL PIPE.

D. CONDUIT-
NOM. 4 IN. DIAM. (OR SMALLER) STEEL ELECTRICAL METALLIC TUBING OR RIGID STEEL CONDUIT

E. IRON PIPE-
NOM. 4 IN. DIAM. (OR SMALLER) CAST OR DUCTILE IRON PIPE.

3. **FILL, VOID OR CAVITY MATERIALS** (BEARING THE UL CLASSIFICATION MARKING) - CAULK OR PUTTY MIN. 1/2 IN. DIAMETER BEAD CAULK OR PUTTY APPLIED CONTINUOUSLY AROUND THE PENETRANT ON THE WALL SURFACES ON BOTH SIDES OF THE WALL.

3M COMPANY - CP 25WB+ CAULK OR MPS-2+ PUTTY

54 THROUGH PENETRATION @ WALL
SCALE: 1 1/2" = 1'-0"

BACK WALL

FRONT / REAR WALL

(REF 2022 CRC R327.1)

42 TYPICAL POST
SCALE: 3/4" = 1'-0"

FRONT/SIDE ELEVATION

TOP PLAN VIEW

PLAN VIEW

POSTS AND COLUMNS THAT ARE EITHER EXPOSED TO THE WEATHER OR LOCATED IN BASEMENTS OR CELLARS, SUPPORTED BY CONCRETE PIERS OR METAL PEDESTALS, SHALL BE PROJECTED AT LEAST 1 INCH ABOVE THE SLAB OR DECK AND 8 INCHES ABOVE EXPOSED EARTH AND SHALL BE SEPARATED BY AN IMPERVIOUS MOISTURE BARRIER.

NOTE: REQUIRED ON ALL EXPOSED LUMBER: PIMER & 2 COATS OF EXTERIOR GRADE PAINT

43 TOILET BLOCKING - AGING-IN-PLACE
SCALE: 1/2" = 1'-0"

SIDE WALL

BACK WALL

(REF 2022 CRC R327.1)

44 TUB BLOCKING - AGING-IN-PLACE
SCALE: 1/2" = 1'-0"

BACK WALL

FRONT / REAR WALL

(REF 2022 CRC R327.1)

31 DECORATIVE FAUX GABLE VENTS
SCALE: 1 1/2" = 1'-0"

OPTION A - ROUND VENT

OPTION B - SQUARE VENT

SECTION CUT

ROUND VENT

SQUARE VENT

NOTE: SEE TITLE SHEET FOR STYLE SELECTION

32 DETAILED HEAD FLASHING
SCALE: 1/2" = 1'-0"

BUILDING PAPER OVER SELF-SEALING MEMBRANE, 6" MIN LAP

SELF-SEALING MEMBRANE OVER WINDOW FIN

A CONTINUOUS BEAD OF SEALANT APPLIED TO THE WINDOW FLANGE

33 DETAILED JAMB FLASHING
SCALE: 1/2" = 1'-0"

(1) CONT. BEAD OF SEALANT

SILL FLASHING OVER BLDG. PAPER

(1) CONT. BEAD OF SEALANT

34 DETAILED SILL FLASHING
SCALE: 1/2" = 1'-0"

(1) CONT. BEAD OF SEALANT

SILL FLASHING OVER BLDG. PAPER

(1) CONT. BEAD OF SEALANT

21 TYP. PORCH BEAM
SCALE: 1 1/2" = 1'-0"

FRAMING PER STRUCTURAL

SIDING PER ELEVATIONS

SHEATHING

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC 703

TRIM DETAIL PER STYLE; SEE ELEVATION MATERIAL LEGEND

PORCH BEAM PER STRUCTURAL

3/4" MIN. TRIM

FIBER CEMENT BOARD OR T&G; MATERIAL SELECTION PER TITLE SHEET

22 WATER HEATER MOUNTING
SCALE: 1/2" = 1'-0"

NOTE: APPLIANCES INSTALLED IN GARAGES, WAREHOUSES OR OTHER AREAS SUBJECT TO MECHANICAL DAMAGE SHALL BE GUARDED AGAINST SUCH DAMAGE BY BEING INSTALLED BEHIND PROTECTIVE BARRIERS OR BY BEING ELEVATED OR LOCATED OUT OF THE NORMAL PATH OF VEHICLES. **CPC 507.13.1 PHYSICAL DAMAGE**

LOCATE TS-1 EARTHQUAKE STRAP WITH TENSIONING BUCKLES WITHIN UPPER 1/3 OF WATER HEATER

LOCATE TS-1 EARTHQUAKE STRAP WITH TENSIONING BUCKLES 4" ABOVE CONTROLS WITHIN LOWER 1/3 OF THE VERTICAL DIMENSION OF THE WATER HEATER **CPC 507.2**

ANCHOR LEGS TO PLATFORM OR FLOOR

MINIMUM 1" NON-METALLIC SPACER

LAG STRAP SECURELY TO WALL FRAMING: (4) 3/8"x 2 1/2" LAG BOLTS AND FENDER WASHERS. STRAP SHALL BE ENCIRCLED TIGHTLY AROUND WATER HEATER IN A MANNER WHICH DOES NOT DEPRESS INSULATION BLANKET

23 TYPICAL FOUNDATION - SIDING
SCALE: 3" = 1'-0"

BATT INSULATION (REFER TO SECTIONS FOR R-VALUE)

WALL FRAMING AND SHEATHING PER PLANS/ STRUCTURAL

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC 703 OVER 26 GA. FLASHING. 4" LAP EXTENSION

FLASHING PER CRC R703.4

MIN. 2%

ADJACENT WALKWAY OR DECK

FOUNDATION OR CURB

ADJACENT EARTH

MIN. 5%

MIN. 2" EARTH TO FLASH

4" MIN. EARTH TO SILL

6" MIN. GRADE TO SILL

OPTION A - NO BASE TRIM

24 TYPICAL FOUNDATION - HORIZONTAL LAP SIDING
SCALE: 3" = 1'-0"

BATT INSULATION (REFER TO SECTIONS FOR R-VALUE)

WALL FRAMING AND SHEATHING PER PLANS/ STRUCTURAL

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC 703 OVER 26 GA. FLASHING. 4" LAP EXTENSION

FLASHING PER CRC R703.4

MIN. 2%

ADJACENT WALKWAY OR DECK

FOUNDATION OR CURB

ADJACENT EARTH

MIN. 5%

MIN. 2" EARTH TO FLASH

4" MIN. EARTH TO SILL

6" MIN. GRADE TO SILL

OPTION A - NO BASE TRIM

11 EXTERIOR DOOR THRESHOLD - TYPICAL
SCALE: 6" = 1'-0"

EXTERIOR

INTERIOR

ALUMINUM DOOR THRESHOLD OVER PVC LINER. SILICONE CAULK AT ALL SCREW HOLES.

APPLY CONTINUOUS BEAD OF SEALANT TO UNDERSIDE OF THRESHOLD.

LANDING TO BE 1/4" / 12" MIN. SLOPE AWAY FROM OPENING AND MEET **CRC R311.3.1** AND **CRC R311.7**

CONCRETE SLAB; SEE STRUCTURAL FOR MORE INFORMATION

R311.3.1 FLOOR ELEVATIONS AT THE REQUIRED EGRESS DOORS
LANDINGS OR FINISHED FLOORS AT THE REQUIRED EGRESS DOOR SHALL BE NOT MORE THAN 1 1/2 INCHES LOWER THAN THE TOP OF THE THRESHOLD. THE LANDING OR FLOOR ON THE EXTERIOR SIDE SHALL BE NOT MORE THAN 7 3/4 INCHES BELOW THE TOP OF THE THRESHOLD PROVIDED THAT THE DOOR DOES NOT SWING OVER THE LANDING OR FLOOR.

WHERE EXTERIOR LANDINGS OR FLOORS SERVING THE REQUIRED EGRESS DOOR ARE NOT AT GRADE, THEY SHALL BE PROVIDED WITH ACCESS TO GRADE BY MEANS OF A RAMP IN ACCORDANCE WITH **CRC R311.8** OR A STAIRWAY IN ACCORDANCE WITH **CRC R311.7**

12 EXT. THRESHOLD - SLIDING DOOR TYP.
SCALE: 3" = 1'-0"

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC R703 OVER 26 GA. FLASHING. 4" LAP EXTENSION

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

METAL FLASHING PER CRC R703.4 W/ DRIP EDGE. 3-1/2" UPSTAND.

2" MIN. TRIM, 14" MAX. MATERIAL SHALL BE SAME AS ELEVATION ABOVE. SEE MATERIALS LEGEND FOR MORE INFORMATION. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.

FLASHING SEALANT

MIN. 2%

ADJACENT PAVED AREA

FOUNDATION OR CURB

ADJACENT EARTH

MIN. 5%

MIN. 2" EARTH TO FLASH

2 1/2" MIN. EARTH TO SILL

6" MIN. GRADE TO SILL

OPTION B - WITH BASE TRIM

12 EXT. THRESHOLD - SLIDING DOOR TYP.
SCALE: 3" = 1'-0"

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC R703 OVER 26 GA. FLASHING. 4" LAP EXTENSION

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

METAL FLASHING PER CRC R703.4 W/ DRIP EDGE. 3-1/2" UPSTAND.

2" MIN. TRIM, 14" MAX. MATERIAL SHALL BE SAME AS ELEVATION ABOVE. SEE MATERIALS LEGEND FOR MORE INFORMATION. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.

FLASHING SEALANT

MIN. 2%

ADJACENT PAVED AREA

FOUNDATION OR CURB

ADJACENT EARTH

MIN. 5%

MIN. 2" EARTH TO FLASH

2 1/2" MIN. EARTH TO SILL

6" MIN. GRADE TO SILL

OPTION B - WITH BASE TRIM

24 TYPICAL FOUNDATION - HORIZONTAL LAP SIDING
SCALE: 3" = 1'-0"

BATT INSULATION (REFER TO SECTIONS FOR R-VALUE)

WALL FRAMING AND SHEATHING PER PLANS/ STRUCTURAL

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC 703 OVER 26 GA. FLASHING. 4" LAP EXTENSION

FLASHING PER CRC R703.4

MIN. 2%

ADJACENT WALKWAY OR DECK

FOUNDATION OR CURB

ADJACENT EARTH

MIN. 5%

MIN. 2" EARTH TO FLASH

4" MIN. EARTH TO SILL

6" MIN. GRADE TO SILL

OPTION B - WITH BASE TRIM

CITY OF WALNUT CREEK

THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK

ARCHITECTURAL DETAILS - COMMON

DATE
02/10/2023

SHEET
A-901

1/10/2023 1:45:48 PM
C:\Users\jfox\Documents\2264-01-CU21_Walnut Creek ADU_Central_2022_jfoxDEV\TU1.nt

	NOTE: ① = INDICATES SEQUENCE FOR INSTALLATION "MOISTOP" CAULK BEHIND ALL 4 SIDES "TOP 90" VENT OR EYEBROW "MOISTOP"	FLASHING PAPER, MOISTOP FLASHING OR EQUAL (9" WIDE MIN.) (2) NAILING FIN @ TOP OF WINDOWS (HEAD) TYP. TWO CONTINUOUS BEADS OF MOISTOP SEALANT OR EQUAL UNDER FLASHING PAPER (1) (2) NAILING FIN AND (1) AT TOP OF FLASHING PAPER TYP. NAIL'G FIN. FLASHING PAPER, SELF SEALING MEMBRANE (9" WIDE MIN., 12" WIDE TYP. AT JAMBS) OR WOOD FRAMING & UNDER NAILING FIN @ SIDE OF WINDOWS (JAMB) TYP. NOTES: ① = INDICATES SEQUENCE FOR INSTALLATION • 9" MOIST STOP FLASHING PAPER TYP. OF FLASHING PAPER • THE ACTUAL NUMBER OF FLASHING PIECES REQUIRED IS DETERMINED BY THE RADIUS OF THE OPENING AND THE SIZE OF THE FLASHING. (9" WIDE FLASHING MIN.) • APPLY A CONTINUOUS BEAD OF SEALANT COMPLYING WITH AAMA 800 TO THE BACKSIDE (INTERIOR) OF THE WINDOW MOUNTING FLANGES • AT WINDOW HEAD, JAMBS AND SILL ALL CORROSIVE RESISTANT FASTENERS ARE TO BE NAILED THROUGH FIN NO CLOSER THAN 3" O.C. AND NOT MORE THAN 16" O.C. • FASTENERS SHALL BE WITHIN 10" FROM CORNERS. • NO NAILS SHALL BE BENT OVER THE NAILING FIN TO SECURE WINDOW • REFER TO AAMA 2400-10 STANDARD PRACTICE FOR INSTALLATION OF WINDOWS WITH MOUNTING FLANGES IN STUD CONSTRUCTION FOR ADDITIONAL REQUIREMENTS. WINDOW WINDOW 32 A-902 REFER TO TYPICAL CORNER WINDOW FLASHING DETAIL FOR ADDITIONAL INFO.	NOTE: CAULK ALL JOINTS TO CREATE 3-DIMENSIONAL FLASHING W/VULKEM OR EQUAL. 26 GA BONDERIZED COMBINATION "Z" BAR AND COUNTER FLASHING. CUT TO FIT TIGHTLY OVER CORNER "Z" BAR FLASHING IN A BED OF SEALANT (VULKEM OR EQUAL) 26 GA BONDERIZED STANDARD "Z" BAR FLASHING AT ABUTTING WALL (1) ROOFING FELT SEALANT 26 GA BONDERIZED ABUTTING WALL PAN FLASHING UNDER "Z" BAR FLASHING OVER ROOFING UNDERLAYMENT(S) BENT TO FORM CORNER FLASHING SEE FLASHING PROFILES AT ROOF TO WALL DETAILS	26 GA. BONDERIZED "Z" BAR FLASHING. PROVIDE SLICE IN FLASHING TO SLIDE OVER TILE PAN FLASHING VERTICAL BONDERIZED "Z" BAR FLASHING OVER END OF 1X NAILER 26 GA BONDERIZED TILE PAN FLASHING WITH DIVERTER AT END. (1) LAYER OF RUBBERIZED WPM FLASHING BEHIND ASSEMBLY OVER WALL FRAMING. EXTEND ROOFING UNDERLAYMENT(S) UP TO TOP OF 1X NAILER. HOLD 1X NAILER BACK 1" MINIMUM FROM FASCIA. HOLD BARGE BOARD 1-1/2" FROM ROUGH FRAMING
41 FLASHING - G.I. VENT SCALE: 1" = 1'-0"	42 FLASHING - PROTRUSIONS SCALE: 1 1/2" = 1'-0"	31 FLASHING - WINDOW TYP. SCALE: 12" = 1'-0"	21 ROOF TO WALL TYP. FLASHING 5 SCALE: 3" = 1'-0" 1'-0" MIN. 1'-0" MIN. 1'-0" MIN. 1'-0" MIN. BONDERIZED STEEL Z- BAR/COUNTER FLASHING ROOF SHEATHING ROOF RAFTER SELF-SEALING MAMBRANE INSTALLED BY FRAMER	11 ROOF TO WALL TYP. FLASHING 1 SCALE: 6" = 1'-0"
52 BEAM TO WALL FLASHING SCALE: 1" = 1'-0"	42 FLASHING - PROTRUSIONS SCALE: 1 1/2" = 1'-0"	32 FLASHING - WINDOW CORNER TYP. SCALE: 12" = 1'-0"	22 FLASHING - FASCIA TO WALL TYP. SCALE: 1 1/2" = 1'-0"	12 ROOF TO WALL TYP. FLASHING 2 SCALE: 3" = 1'-0"
53 FIXED BOLLARD SCALE: 3/4" = 1'-0"	43 FLASHING - DETAILED PROTRUSION SCALE: 1 1/2" = 1'-0"	33 FLASHING - DOOR AT GRADE2 NTS	23 FLASHING PAN @ DOOR THRESHOLD SCALE: 3" = 1'-0" WIDTH OF WALL FRAMING, INCLUDING SHEATHING SELF-SEALING MEMBRANE - DUPONT "STRAIGHT FLASH" OR "FLEXWRAP OR EQUAL BONDERIZED STEEL PAN FLASHING (SHOWN SHADED AND DASHED FOR CLARITY) O/SELF-SEALING MEMBRANE - DUPONT "STRAIGHT FLASH" OR "FLEXWRAP OR EQUAL NOTE: ALL EXTERIOR DOOR INSTALLATIONS SHALL COMPLY WITH MANUFACTURER/INDUSTRY STANDARDS AAMA 300-12	13 ROOF TO WALL TYP. FLASHING SCALE: 3" = 1'-0" (1) PIECE 26 GA BONDERIZED STEEL "Z" BAR FLASHING. CUT, FOLD AND SEAL ALL JOINTS TO FORM (3) DIMENSIONAL FLASHING AT END (VULKEM OR EQUAL) 26 GA BONDERIZED STEEL COUNTER HEAD FLASHING UNDER "Z" BAR FLASHING. EXTEND ROOFING UNDERLAYMENT(S) UP TO TOP OF 1X NAILER. (1) LAYER OF RUBBERIZED W.P.M. FLASHING BEHIND ASSEMBLY OVER WALL FRAMING. HOLD 1X NAILER FLUSH WITH FACE OF INTERSECTING WALL. VERTICAL "L" BAR FLASHING OVER END OF 1X NAILER. RAKE BOARD OR PLASTER WALL
	44 RAILING CONNECTION DETAIL SCALE: 6" = 1'-0"	34 FLASHING - DOOR AT W.P. DECK2 NTS	24 FLASHING - JAMB TO SILL TYP. SCALE: 3" = 1'-0" WIDTH OF WALL FRAMING, INCLUDING SHEATHING SELF-SEALING MEMBRANE - DUPONT "STRAIGHT FLASH" OR "FLEXWRAP OR EQUAL BONDERIZED STEEL PAN FLASHING (SHOWN SHADED AND DASHED FOR CLARITY) O/SELF-SEALING MEMBRANE - DUPONT "STRAIGHT FLASH" OR "FLEXWRAP OR EQUAL NOTE: ALL EXTERIOR DOOR INSTALLATIONS SHALL COMPLY WITH MANUFACTURER/INDUSTRY STANDARDS AAMA 300-12	14 ROOF TO WALL TYP. FLASHING SCALE: 3" = 1'-0" (1) PIECE 26 GA BONDERIZED STEEL "Z" BAR FLASHING. CUT, FOLD AND SEAL ALL JOINTS TO FORM (3) DIMENSIONAL FLASHING AT END (VULKEM OR EQUAL) 26 GA BONDERIZED STEEL COUNTER HEAD FLASHING UNDER "Z" BAR FLASHING. EXTEND ROOFING UNDERLAYMENT(S) UP TO TOP OF 1X NAILER. (1) LAYER OF RUBBERIZED W.P.M. FLASHING BEHIND ASSEMBLY OVER WALL FRAMING. HOLD 1X NAILER FLUSH WITH FACE OF INTERSECTING WALL. VERTICAL "L" BAR FLASHING OVER END OF 1X NAILER. RAKE BOARD OR PLASTER WALL



CITY OF
WALNUT
CREEK



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK
ARCHITECTURAL DETAILS -
COMMON

DATE
02/10/2023
SHEET
A-902

NOTE: WHEN 1-HR FIRE RATING REQUIRED SEE TABLE: **43/A-903**

ROOFING: SEE TITLE SHEET MATERIALS LEGEND FOR MORE INFORMATION



- NOTES:**
1. CAULK ALL JOINTS.
 2. PRIME TRIM ALL SIDES.
 3. REQUIRED ON ALL EXPOSED LUMBER, PIMER & 2 COATS OF EXTERIOR GRADE PAINT.

42 TYP. POST & ROOF

SCALE: 3/4" = 1'-0"

***ROOF ASSEMBLY REQUIREMENTS ONLY APPLY TO EAVES AND ROOF EXTENSIONS WHERE LESS THAN 5' - 0" FROM PROPERTY LINE OR ASSUMED PROPERTY LINE BETWEEN STRUCTURES.**

ROOF ASSEMBLY FIRE RESISTANCE CALCULATION
PER CBC TABLE 722.6.2(1) & PER CBC 722.6.2(2)

WOOD JOISTS 16" O.C.	10 MIN.
1/2" PLYWOOD	10 MIN.
5/8" TYPE X GYPSUM BOARD	40 MIN.
TOTAL FIRE RESISTANCE	60 MIN.


***WALL ASSEMBLY REQUIREMENTS ONLY APPLY WHERE LESS THAN 5'-0" FROM PROPERTY LINE OR ASSUMED PROPERTY LINE BETWEEN STRUCTURES.**

WALL ASSEMBLY FIRE RESISTANCE CALCULATION
PER CBC TABLE 722.6.2(1) & PER CBC 722.6.2(2)

WOOD STUDS 16" O.C.	20 MIN.
1/2" PLYWOOD	10 MIN.
5/8" TYPE X GYPSUM BOARD	40 MIN.
TOTAL FIRE RESISTANCE	70 MIN.


43 CALC. FIRE RESISTANCE RATING

SCALE: 1/2" = 1'-0"




31 SIDE WALL

SCALE: 3" = 1'-0"





21 HEADWALL

SCALE: 3" = 1'-0"




22 HEADWALL - VERTICAL SIDING

SCALE: 3" = 1'-0"



12 GUTTER TO EXTERIOR DOWNSPOUT

SCALE: 1/2" = 1'-0"




- NOTES**
1. NOT ALLOWED WITHIN 5' OF PROPERTY LINE
 2. PRE-PRIME ALL SIDES OF BRACE FRAMING PRIOR TO INSTALLATION. TYPICAL
 3. A SELF SEALING MEMBRANE SHALL BE INSTALLED BEHIND WALL TRIM & EXTEND 6" BEYOND WALL TRIM AND 4" MIN. LAP O/WEATHER BARRIER
 4. CAULK AROUND TOP & SIDES OF 4X AT WALL PENETRATION.
 5. A BITUTHENE MEMBRANE SHALL BE INSTALLED BEHIND 4X6 BRACE W/ 4" LAP MIN.

34 SHED ROOF W/ KICKER

SCALE: 1" = 1'-0"


NOTE: OVERHANG IS NOT PERMITTED WHEN PROPERTY LINE IS 5' - 0" OR LESS FROM THE EDGE OF OVERHANG



- NOTES**
1. NOT ALLOWED WITHIN 5' OF PROPERTY LINE
 2. PRE-PRIME ALL SIDES OF BRACE FRAMING PRIOR TO INSTALLATION. TYPICAL
 3. A SELF SEALING MEMBRANE SHALL BE INSTALLED BEHIND WALL TRIM & EXTEND 6" BEYOND WALL TRIM AND 4" MIN. LAP O/WEATHER BARRIER
 4. CAULK AROUND TOP & SIDES OF 4X AT WALL PENETRATION.
 5. A BITUTHENE MEMBRANE SHALL BE INSTALLED BEHIND 4X6 BRACE W/ 4" LAP MIN.

24 SHED ROOF WITH KICKER @ METAL ROOF

SCALE: 1" = 1'-0"




THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU CITY OF WALNUT CREEK ARCHITECTURAL DETAILS - COMMON ROOF

DATE
02/10/2023
SHEET


A-903

1/10/2023 1:45:49 PM
C:\Users\jacob\Documents\2264-01-CU21_Walnut Creek ADU_Central 2022_jacob\REVIT\nt




41 DOOR TRIM - CAL RANCH

SCALE: 3/4" = 1'-0"




42 DOOR HEAD - CAL RANCH

SCALE: 3" = 1'-0"



43 DOOR JAMB - CAL RANCH

SCALE: 3" = 1'-0"




44 DECORATIVE PORCH RAILING

SCALE: 1" = 1'-0"

THE GREAT OUTDOORS -
WALL MOUNT KIRKHAM
ASPEN BRONZE (8102-A138-L)
OR EQUAL

LIGHT OPTION A



LIGHT OPTION B

LUTEC - BLACK SOLAR OUTDOOR
BARN LIGHT SCONCE WITH DUSK
TO DAWN (6940002012) OR EQUAL

NOTE: ALL EXTERIOR LIGHTS MUST BE ON A MANUAL SWITCH AND MUST COMPLY WITH ALL SINGLE FAMILY RESIDENTIAL MANDATORY REQUIREMENTS SUMMARY SECTION:


- 150.0(K)1A - LUMINAIRE EFFICACY**
- 150.0(K)1D - LIGHT SOURCES IN ENCLOSED RECESSED LUMINAIRES**
- 150.0(K)2E - AUTOMATIC SHUTOFF CONTROLS**
- 150.0(K)3A - RESIDENTIAL OUTDOOR LIGHTING** (2022 CEnC 150.0(k)3).

IN ADDITION TO MEETING THE REQUIREMENTS OF SECTION 150.0(K)1A, LUMINAIRES PROVIDING RESIDENTIAL OUTDOOR LIGHTING SHALL MEET THE FOLLOWING REQUIREMENTS, AS APPLICABLE:

- A. FOR SINGLE-FAMILY RESIDENTIAL BUILDINGS, OUTDOOR LIGHTING PERMANENTLY MOUNTED TO A RESIDENTIAL BUILDING OR TO OTHER BUILDINGS ON THE SAME LOT SHALL MEET THE REQUIREMENT IN ITEM I AND THE REQUIREMENTS IN EITHER ITEM II OR ITEM III:
- CONTROLLED BY A MANUAL ON AND OFF CONTROL SWITCH THAT PERMITS THE AUTOMATIC ACTIONS OF ITEMS II OR III BELOW; AND
 - CONTROLLED BY A PHOTOCELL AND EITHER A MOTION SENSOR OR AN AUTOMATIC TIME SWITCH CONTROL; OR
 - CONTROLLED BY AN ASTRONOMICAL TIME CLOCK CONTROL.
- NOTE:** CONTROLS THAT OVERRIDE TO ON SHALL NOT BE ALLOWED UNLESS THE OVERRIDE AUTOMATICALLY RETURNS THE AUTOMATIC CONTROL TO ITS NORMAL OPERATION WITHIN 6 HOURS. AN ENERGY MANAGEMENT CONTROL SYSTEM THAT PROVIDES THE SPECIFIED LIGHTING CONTROL FUNCTIONALITY AND COMPLIES WITH ALL REQUIREMENTS APPLICABLE TO THE SPECIFIED CONTROLS MAY BE USED TO MEET THESE REQUIREMENTS.


32 LIGHT FIXTURE - CAL RANCH

SCALE: 1 1/2" = 1'-0"




21 FIBER CEMENT - LAP - MOUNTING PAD

SCALE: 3" = 1'-0"




22 CALIFORNIA RANCH - TRIM PROFILE

SCALE: 3" = 1'-0"




23 TYP. INSIDE CORNER - CAL. RANCH

SCALE: 3" = 1'-0"




24 TYP. OUTSIDE CORNER - CAL. RANCH

SCALE: 3" = 1'-0"




11 WINDOW TRIM - CAL. RANCH

SCALE: 3/4" = 1'-0"




12 TYP. WINDOW HEAD

SCALE: 3" = 1'-0"




13 TYP. WINDOW JAMB

SCALE: 3" = 1'-0"



14 TYP. WINDOW SILL

SCALE: 3" = 1'-0"



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.


WALNUT CREEK ADU
CITY OF WALNUT CREEK
ARCHITECTURAL DETAILS - CALIFORNIA RANCH

DATE
02/10/2023


SHEET

A-911


1/10/2023 1:45:49 PM
C:\Users\jfox\Documents\2264-01-CU21_Walnut Creek ADU_Central 2022_jfox\REV\TU.nt




51 RIDGE/HIP DETAIL
SCALE: 3" = 1'-0"




52 VALLEY DETAIL
SCALE: 3" = 1'-0"




41 O'HAGIN ROOF VENT
SCALE: 3" = 1'-0"




42 BRACE - CALIFORNIA RANCH
SCALE: 3/4" = 1'-0"




31 CALIFORNIA RANCH - EAVE
SCALE: 1 1/2" = 1'-0"




32 CALIFORNIA RANCH - RAKE
SCALE: 1 1/2" = 1'-0"




33 CAL. RANCH - DECORATIVE SHUTTER
SCALE: 3" = 1'-0"




23 CALIFORNIA RANCH - DECORATIVE SHUTTER
SCALE: 3/4" = 1'-0"



23 CALIFORNIA RANCH - DECORATIVE SHUTTER
SCALE: 3/4" = 1'-0"



23 CALIFORNIA RANCH - DECORATIVE SHUTTER
SCALE: 3/4" = 1'-0"



23 CALIFORNIA RANCH - DECORATIVE SHUTTER
SCALE: 3/4" = 1'-0"

CITY OF WALNUT CREEK

THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK


ARCHITECTURAL DETAILS -
CALIFORNIA RANCH - ROOF

DATE
02/10/2023

SHEET
A-912

1/10/2023 1:45:50 PM
C:\Users\jca\Documents\2264-01-CU21_Walnut Creek ADU_Central 2022_jca\REV\TU1.rvt


Figure 6a. Cladding Transition



DISCLAIMER: EL DORADO STONE DETAILS HAVE BEEN INCLUDED FOR REFERENCE ONLY. REFER AND INSTALL ADHERED MASONRY FROM THE SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.

34 INSTALLATION GUIDE FOR ADHERED MANUFACTURED STONE VENEER, 3RD EDITION, 5TH PRINTING, REVISED AUGUST 2021


Figure 3. Wall Assembly Transition



DISCLAIMER: EL DORADO STONE DETAILS HAVE BEEN INCLUDED FOR REFERENCE ONLY. REFER AND INSTALL ADHERED MASONRY FROM THE SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.

NATIONAL CONCRETE MASONRY ASSOCIATION


Figure 5a. Foundation Wall Base



DISCLAIMER: EL DORADO STONE DETAILS HAVE BEEN INCLUDED FOR REFERENCE ONLY. REFER AND INSTALL ADHERED MASONRY FROM THE SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.

20 INSTALLATION GUIDE FOR ADHERED MANUFACTURED STONE VENEER, 3RD EDITION, 5TH PRINTING, REVISED AUGUST 2021


Figure 1. Installation Over Wood Framing



DISCLAIMER: EL DORADO STONE DETAILS HAVE BEEN INCLUDED FOR REFERENCE ONLY. REFER AND INSTALL ADHERED MASONRY FROM THE SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.

NATIONAL CONCRETE MASONRY ASSOCIATION


Figure 21a. Window Sill



DISCLAIMER: EL DORADO STONE DETAILS HAVE BEEN INCLUDED FOR REFERENCE ONLY. REFER AND INSTALL ADHERED MASONRY FROM THE SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.

44 INSTALLATION GUIDE FOR ADHERED MANUFACTURED STONE VENEER, 3RD EDITION, 5TH PRINTING, REVISED AUGUST 2021


Figure 12a. Vertical Transition



DISCLAIMER: EL DORADO STONE DETAILS HAVE BEEN INCLUDED FOR REFERENCE ONLY. REFER AND INSTALL ADHERED MASONRY FROM THE SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.

32 INSTALLATION GUIDE FOR ADHERED MANUFACTURED STONE VENEER, 3RD EDITION, 5TH PRINTING, REVISED AUGUST 2021


Figure 11a. Horizontal Transition



DISCLAIMER: EL DORADO STONE DETAILS HAVE BEEN INCLUDED FOR REFERENCE ONLY. REFER AND INSTALL ADHERED MASONRY FROM THE SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.

30 INSTALLATION GUIDE FOR ADHERED MANUFACTURED STONE VENEER, 3RD EDITION, 5TH PRINTING, REVISED AUGUST 2021

Figure 9a. Outside Corner



DISCLAIMER: EL DORADO STONE DETAILS HAVE BEEN INCLUDED FOR REFERENCE ONLY. REFER AND INSTALL ADHERED MASONRY FROM THE SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.

28 INSTALLATION GUIDE FOR ADHERED MANUFACTURED STONE VENEER, 3RD EDITION, 5TH PRINTING, REVISED AUGUST 2021



CITY OF
WALNUT
CREEK

THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK


ARCHITECTURAL DETAILS -
CALIFORNIA RANCH

DATE
02/10/2023
SHEET

A-913


1/10/2023 1:45:50 PM
C:\Users\jfox\Documents\2264-01-CU21_Walnut Creek ADU_Central 2022_jfoxREV\TU1.rvt

NOTE: REFER TO
HEAD/JAMB DETAILS FOR
FLASHING AND MATERIAL
TRANSITIONS




41 COTTAGE DOOR TRIM

SCALE: 3/4" = 1'-0"




42 DOOR HEAD - COTTAGE

SCALE: 3" = 1'-0"



43 DOOR JAMB - COTTAGE

SCALE: 3" = 1'-0"




OPTION A DECORATIVE "X" PORCH RAILING

NOTE: DECORATIVE PORCH RAILING 24" MINIMUM. SEE DETAILS FOR MORE INFORMATION. THERE SHALL BE NO MORE THAN 30 INCHES MEASURED VERTICALLY TO THE FLOOR OR GRADE BELOW, (INCLUDING FLOORS, STAIRS, RAMPS, AND LANDINGS) ANYWHERE MEASURED LESS THAN 36 INCHES HORIZONTALLY TO THE EDGE OF THE PORCH/SLAB/SURFACE OF THE RAIL. INSECT SCREENING SHALL NOT BE CONSIDERED AS A GUARD

44 DECORATIVE PORCH RAILING


SCALE: 1" = 1'-0"

LNC - MODERN FROSTED BLACK
PORCH OUTDOOR WALL
SCOOPE WITH MUSHROOM
CLEAR SEEDED GLASS SHADE
(VAFNYAHD13356V6) OR EQUAL



LIGHT OPTION A

HAMPTON BAY- BLACK OUTDOOR
WALL LANTERN SCOOPE
(JBO1691A-4) OR EQUAL



LIGHT OPTION B

NOTE: ALL EXTERIOR LIGHTS MUST BE ON A MANUAL SWITCH AND MUST COMPLY WITH ALL SINGLE FAMILY RESIDENTIAL MANDATORY REQUIREMENTS SUMMARY SECTION:

150.0(K)1A - LUMINAIRE EFFICACY

150.0(K)1D - LIGHT SOURCES IN ENCLOSED RECESSED LUMINAIRES

150.0(K)2E - AUTOMATIC SHUTOFF CONTROLS

150.0(K)3A - RESIDENTIAL OUTDOOR LIGHTING (2022 CEnC 150.0(k)3).


IN ADDITION TO MEETING THE REQUIREMENTS OF SECTION 150.0(K)1A, LUMINAIRES PROVIDING RESIDENTIAL OUTDOOR LIGHTING SHALL MEET THE FOLLOWING REQUIREMENTS, AS APPLICABLE:

- A. FOR SINGLE-FAMILY RESIDENTIAL BUILDINGS, OUTDOOR LIGHTING PERMANENTLY MOUNTED TO A RESIDENTIAL BUILDING OR TO OTHER BUILDINGS ON THE SAME LOT SHALL MEET THE REQUIREMENT IN ITEM I AND THE REQUIREMENTS IN EITHER ITEM II OR ITEM III:
1. CONTROLLED BY A MANUAL ON AND OFF CONTROL SWITCH THAT PERMITS THE AUTOMATIC ACTIONS OF ITEMS II OR III BELOW; AND
 2. CONTROLLED BY A PHOTOCELL AND EITHER A MOTION SENSOR OR AN AUTOMATIC TIME SWITCH CONTROL; OR
 3. CONTROLLED BY AN ASTRONOMICAL TIME CLOCK CONTROL.

NOTE: CONTROLS THAT OVERRIDE TO ON SHALL NOT BE ALLOWED UNLESS THE OVERRIDE AUTOMATICALLY RETURNS THE AUTOMATIC CONTROL TO ITS NORMAL OPERATION WITHIN 6 HOURS. AN ENERGY MANAGEMENT CONTROL SYSTEM THAT PROVIDES THE SPECIFIED LIGHTING CONTROL FUNCTIONALITY AND COMPLIES WITH ALL REQUIREMENTS APPLICABLE TO THE SPECIFIED CONTROLS MAY BE USED TO MEET THESE REQUIREMENTS.


32 COTTAGE - LIGHT FIXTURE

SCALE: 1 1/2" = 1'-0"




33 COTTAGE - FIBER CEM. MOUNTING PAD

SCALE: 3" = 1'-0"




21 COTTAGE - TRIM PROFILE

SCALE: 1 1/2" = 1'-0"




22 COTTAGE - TYP. INSIDE CORNER

SCALE: 3" = 1'-0"




23 COTTAGE - TYP. OUTSIDE CORNER

SCALE: 3" = 1'-0"




OPTION B DECORATIVE PORCH RAILING




11 COTTAGE - WINDOW TRIM

SCALE: 3/4" = 1'-0"




12 COTTAGE - TYP. WINDOW HEAD

SCALE: 3" = 1'-0"



13 COTTAGE - TYP. WINDOW JAMB

SCALE: 3" = 1'-0"



NOTE: ALL WINDOW FLASHING SHALL COMPLY WITH MANUFACTURER/INDUSTRY STANDARDS AAMA 2400-02

14 COTTAGE - TYP. WINDOW SILL

SCALE: 3" = 1'-0"



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK


ARCHITECTURAL DETAILS -
COTTAGE

DATE
02/10/2023


SHEET

A-921


1/10/2023 1:45:51 PM
C:\Users\jfox\Documents\2264-01-CU21_Walnut Creek ADU_Central 2022_jfox\REV\TU.nt




51 COTTAGE - ROOF - HIP/RIDGE
SCALE: 1" = 1'-0"




52 COTTAGE - ROOF - VALLEY
SCALE: 1 1/2" = 1'-0"




41 O'HAGIN ROOF VENT
SCALE: 3" = 1'-0"



31 COTTAGE - EAVE
SCALE: 1 1/2" = 1'-0"



32 COTTAGE - RAKE
SCALE: 1 1/2" = 1'-0"



33 COTTAGE - RAKE
SCALE: 1 1/2" = 1'-0"




CITY OF WALNUT CREEK


THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK
ARCHITECTURAL DETAILS -
COTTAGE - ROOF


1/10/2023 1:45:52 PM
C:\Users\jfox\Documents\2264-01-CU21_Walnut Creek ADU_Central_2022_jfoxDEV\TU1.rvt




52 MODERN - OUTRIGGER
SCALE: 1 1/2" = 1'-0"




41 MODERN - DOOR TRIM
SCALE: 3/4" = 1'-0"




42 DOOR HEAD - MODERN
SCALE: 3" = 1'-0"




43 DOOR JAMB - MODERN
SCALE: 3" = 1'-0"




44 MODERN - MOUNTING PAD
SCALE: 3" = 1'-0"




32 MODERN - LIGHT FIXTURE
SCALE: 1 1/2" = 1'-0"




34 MODERN - POST
SCALE: 3" = 1'-0"




21 @ FIBER CEMENT PANELS
SCALE: 3" = 1'-0"




22 TYP. INSIDE CORNER-MODERN
SCALE: 3" = 1'-0"




23 MODERN - TYP. OUTSIDE CORNER
SCALE: 3" = 1'-0"




24 MATERIAL TRANSITION - MODERN
SCALE: 3" = 1'-0"




11 MODERN - WINDOW TRIM
SCALE: 3/4" = 1'-0"



12 MODERN - TYP. WINDOW HEAD
SCALE: 3" = 1'-0"



13 MODERN - TYP. WINDOW JAMB
SCALE: 3" = 1'-0"



14 MODERN - TYP. WINDOW SILL
SCALE: 3" = 1'-0"

THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK


ARCHITECTURAL DETAILS - MODERN

DATE
02/10/2023

SHEET
A-931

VULCAN VENT®
FIRE & EMERGENCY SAFE VENTS
WWW.VULCANVENTS.COM (916)

© 2000 Blackwell Science Ltd *Journal of Internal Medicine* 247: 399–406


VSC2120FF PRODUCT SPECIFICATION & DATA SHEET www.ti.com/param3000

NOTE: ALTERNATIVE PRODUCT SHALL
SUPPLY EQUAL OR GREATER NFVA

NOTE: TO BE APPLIED WITH ATTIC VENTING OPTION A

A1-123	A-202
--------	-------

VULCAN VENT
FIRE & EMBER SAFE VENTS
WWW.VULCANVENTS.COM (916) 444-4444



Model/Description VDR419	Standard Dormer Vent VDR419	Flange Type HPVA	Sub Base 52 sq. in.	Hood & Flange Frame (Int)	G90 Galvanized Steel - 26GA G90 Galvanized Perforated Steel - 24GA
-----------------------------	--------------------------------	---------------------	------------------------	------------------------------	---

NOTE: ALTERNATIVE PRODUCT SHALL
SUPPLY EQUAL OR GREATER NEVA

NOTE: TO BE APPLIED WITH ATTIC VENTING OPTION B


A-502

SCALE: 12" = 1'-0"

SEE ROOF PLAN AND ROOF VENTILATION CALCS
FOR VENT SIZES, LOCATIONS, AND NFVA


2 1/2" HOLES = 4.91 SI NFAV PER HOLE

2 1/2" HOLES = 4.91 SI NFAV PER HOLE



120" / 8" (X) 4.01 = 72.65 ± 50 NEA

SHEET METAL RIDGE CAP BY ROOFING
MANUF. SHALL BE CONSISTENT FOR ALL
RIDGES WHETHER VENTED OR NOT




NOTE: TO BE APPLIED WITH VENTING OPTION A

3	A-002
---	-------

SCALE: 3" = 1'-0"

A1-123	A-202
--------	-------

SCALE: 3" = 1'-0"




NOTE: INSTALL COMPONENTS PER MANUFACTURER'S RECOMMENDATIONS, TYP.

A1-123	A-999
--------	-------

SCALE: 1 1/2" = 1'-0"

SCA

SCALE: 1 1/2" = 1'-0"




SCA

SCALE: 2" = 1'-0"


A-53

SCALE: 3" = 1'-0"



NOTE: VALLEY FLASHINGS SUBJECT TO CBC CHAPTER 7A ARE NOT TO BE LESS THAN 26 GALVANIZED SHEET GAUGE CORROSION RESISTANT METAL INSTALLED OVER A MINIMUM 36" WIDE UNDERLAYMENT CONSISTING OF ONE LAYER OF MINIMUM 72 POUND MINERAL SURFACED NON-PERFORATED CAP SHEET COMPLYING WITH ASTM D3909 INSTALLED OVER THE COMBUSTIBLE DECKING. [CBC 705A.3]

SCALE: 1" = 4' 0"



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK











































ARCHITECTURAL DETAILS
MODERN - ROOF

DATE
02/10/2023

SHEET


A-932

N:\2020\2264-01\CI01-WalnutCreek-ADO\Structural\ConDocs\Sheet Files\Plan\12264-01-CI01 - \$101.dwg, \$101 - Nov 20, 2023 12:29pm, adopez

SYMBOLS				WALL TYPES		SHEET INDEX	
	DETAIL REFERENCE BUBBLE WITH LEADER		INDICATES SHEAR WALL TYPE AND LENGTH, PER SHEAR WALL SCHEDULE		INDICATES TOP PLATE SPLICE NAILING PER SCHEDULE		INDICATES PLYWOOD SIDE FOR SHEARWALL
	DETAIL REFERENCE BUBBLE		INDICATES SPAN AND DIRECTION OF PREFABRICATED ROOF TRUSS (BY OTHERS)		INDICATES SHEAR WALL STRAP / HOLDOWN TYPE PER SCHEDULE		INDICATES BEARING WOOD WALL BELOW
	FULL HEIGHT SECTION INDICATOR		INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST WITH WEB STIFFENER		INDICATES PAD FOOTING TYPE PER SCHEDULE		INDICATES BEARING WOOD WALL ABOVE
	ELEVATION OF WALL OR FRAME		INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST		INDICATES CONTINUOUS FOOTING TYPE PER SCHEDULE		INDICATES NON-BEARING WOOD WALL BELOW
	NORTH ARROW		INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST		ANGLE BRACE		INDICATES NON-BEARING WOOD WALL ABOVE
	TOP/BOTTOM OF ELEVATIONS		INDICATES EXTENTS OF FRAMING OR OTHER STRUCTURAL ELEMENT		DOUBLE ANGLE BRACE		INDICATES EXISTING BEARING WOOD WALL
	SLOPE		INDICATES HEADER @ OPENING PER HEADER SCHEDULE		DRAG STRUT CONNECTION		INDICATES EXISTING NON-BEARING WOOD WALL
	WELDED WIRE FABRIC (WWF LAYER)		EARTH LAYER		FULL HEIGHT STIFFENER CONNECTION		INDICATES BEARING CMU WALL BELOW
	STEPPED SURFACE: FLOOR DEPRESSION		INDICATES SAND OR GROUT		MOMENT CONNECTION		INDICATES BEARING CMU WALL ABOVE
	SLOPED SURFACE		INDICATES GRAVEL		MEMBER SPLICE		INDICATES NON-BEARING CMU WALL BELOW
	STEPPED FOOTING		STEEL IN CROSS SECTION		TOP OF STEEL ± ELEVATION		INDICATES NON-BEARING CMU WALL ABOVE
	BOTTOM STEPPED FOOTING		INDICATES BEARING WALL		NUMBER OF EVENLY SPACED SHEAR STUDS		INDICATES EXISTING BEARING CMU WALL
			SHADED AREA INDICATES CALIFORNIA FRAMING		SPECIAL STUD SPACING SEE TYPICAL STEEL DETAILS		INDICATES EXISTING NON-BEARING CMU WALL
			SHADED AREA INDICATES FOOTPRINT OF FLOOR ABOVE		BEAM CAMBER AT MID-SPAN		INDICATES BEARING CONCRETE WALL BELOW
			STEEL HSS TUBE COLUMN				INDICATES BEARING CONCRETE WALL ABOVE
			STEEL HSS OR PIPE COLUMN				INDICATES NON-BEARING CONCRETE WALL BELOW
			WIDE FLANGE STEEL COLUMN				INDICATES NON-BEARING CONCRETE WALL ABOVE
			WOOD POST				INDICATES EXISTING BEARING CONCRETE WALL
							INDICATES EXISTING NON-BEARING CONCRETE WALL

ABBREVIATIONS

A & B	ABOVE AND BELOW	d	PENNY (NAIL OR BAR DIA)	HDR	HEADER	PA	POST ABOVE	T & B	TOP AND BOTTOM
AB	ANCHOR BOLT	DBL	DOUBLE	HGR	HANGER	PARA OR //	PARALLEL	T & G	TONGUE & GROOVE
ABV	ABOVE	DEPT	DEPARTMENT	HP	HIGH POINT	PC	PRECAST; PIECE	TO	TOP OF
ACI	AMERICAN CONCRETE INSTITUTE	DET	DETAIL	HSB	HORIZONTALLY SLOTTED HOLES	PERP	PERPENDICULAR	TOC	TOP OF CURB; TOP OF CONCRETE
ADDL	ADDITIONAL	DF	DOUGLAS FIR/LARCH	HT	HEIGHT	PI	PLYWOOD INDEX	TOF	TOP OF FOOTING
ADJ	ADJACENT	DIA OR Ø	DIAMETER	ID	INSIDE DIAMETER	PL OR PL.	PLATE	TEMP	TEMPERATURE; TEMPORARY
AESS	ARCHITECTURAL EXPOSED STRUCTURAL STEEL	DIAG	DIAGONAL	IF	INSIDE FACE	PL	PROPERTY LINE	THRU	THROUGH
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION	DIAPH	DIAPHRAGM	I-JST	I-JOIST	PLF	PONDS PER LINEAL FOOT	THK	THICKNESS/THICK
ALT	ALTERNATE	DIM	DIMENSION	IN	INCH	PLCS	PLACES	THR	THREADED
ALUM	ALUMINUM	DN	DOWN	INCL	INCLUDE	PLY	PLYWOOD	TOP or T	TOP
ANCH	ANCHOR	DO	DO OVER	INFO	INFORMATION	PROP	PROPERTY	TOS	TOP OF STEEL/TOP OF SLAB
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	DWG	DRAWING	INSP	INSPECTION	PT	PRESSURE TREATED	TOW	TOP OF WALL
APA	ENGINEERED WOOD ASSOCIATION (FORMERLY THE AMERICAN PLYWOOD ASSOCIATION)	DWL	DRAWING	INT	INTERIOR	PW	PLATE WASHER	TS	TRIMMER STUD
APPROX	APPROXIMATE	EA	EACH	JST	JOIST	PJP	PARTIAL JOINT PENETRATION WELD	TYP	TYPICAL
ARCH	ARCHITECTURAL; ARCHITECT	EF	EACH FACE	JT	JOINT	PREFAB	PREFABRICATED	UNO	UNLESS NOTED OTHERWISE
AWPA	AMERICAN WOOD PRESERVERS ASSOCIATION	EJ	EXPANSION JOINT	K	KIPS	PSF	POUNDS PER SQUARE FOOT	UT	ULTRA-SONIC TEST
AWS	AMERICAN WELDING SOCIETY	EL	ELEVATION	KS	KING STUD	PSI	POUNDS PER SQUARE INCH	VERT	VERTICAL
AITC	AMERICAN INSTITUTE OF TIMBER CONSTRUCTION	ELEC	ELECTRICAL	KP	KING POST	PSL	PARALLEL STRAND LUMBER	VSH	VERTICAL SLOTTED HOLES
ASTM	AMERICAN SOCIETY FOR TESTING MATERIALS	ELEV	ELEVATOR	KSI	KIPS PER SQUARE INCH	PVMT	PAVEMENT	W/	WITH
BLDG	BUILDING	EMBED	EMBEDMENT	LB(S) OR #	POUND(S)	#	POUND; NUMBER	W/O	WITHOUT
BLK	BLOCK	EN	EDGE NAIL	LN	LINEAL FOOT	REF	REFERENCE	WO	WHERE OCCURS
BLKG	BLOCKING	ENGR	ENGINEER	LLH	LONG LEG HORIZONTAL	REINF	REINFORCE; REINFORCING	WD	WOOD
BM	BEAM	EQ	EQUAL OR EQUIVALENT	LLV	LONG LEG VERTICAL	REQD	REQUIRED	WP	WORK POINT; WATERPROOF
BN	BOUNDARY NAIL	EQUIP	EQUIPMENT	LP	LOW POINT	RF	ROOF	WWF	WELDED WIRE FABRIC
BOT OR B	BOTTOM	ES	EACH SIDE	LSH	LONG SLOTTED HOLES	RR	ROOF RAFTER		
BRC	BRACE	EW	EACH WAY	LSL	LAMINATED STRAND LUMBER	Ø	ROUND; DIAMETER		
BRG	BEARING	EXT	EXISTING	LT WT	LIGHTWEIGHT	SCHED	SCHEDULE	W	W SHAPE
BTWN	BETWEEN	FDN	FOUNDATION	LVL	LEVEL OR LAMINATED VENEER LUMBER	SECT	SECTION	C	AMERICAN STD CHANNEL SHAPE
CANT	CANTILEVER	FIN	FINISH	MAS	MASONRY	SEP	SEPARATION	MC	MISC CHANNEL SHAPE
CAM OR C	CAMBER	FJ	FLOOR JOIST	MATL	MATERIAL	SHT	SHEET	L	ANGLE SHAPE
CC	CENTER TO CENTER	FLG	FLANGE	MAX	MAXIMUM	SHTG	SHEATHING	WT, ST, MT	STRUCT TEE SHAPE
CG	CENTER OF GRAVITY	FLR	FLOOR	MB	MACHINE BOLT	SIM	SIMILAR	PIPE	STANDARD PIPE SHAPE
CIP	CAST-IN-PLACE	FN	FIELD NAIL	MECH	MECHANICAL	SOG	SLAB ON GRADE	PIPE-X	EXTRA STRONG PIPE SHAPE
C/J	CONSTRUCTION JOINT; CONTROL JOINT	FOC	FACE OF CONCRETE	MFR	MANUFACTURER	SN	SHEAR NAIL	PIPE-XX	DBL EXTRA STRONG PIPE SHAPE
CL	CENTER LINE	FOM	FACE OF MASONRY	MIN	MINIMUM; MINUTE	SPCG	SPACING	HSS	HOLLOW STRUCTURAL SECTION
CLR	CLEARANCE; CLEAR	FOS	FACE OF STUD	MISC	MISCELLANEOUS	SPECS	SPECIFICATIONS		
CMU	CONCRETE MASONRY UNIT	FOW	FACE OF WALL	[N]	NEW	SQ	SQUARE		
COL	COLUMN	FRMG	FRAMING	N	NORTH	SS	STAINLESS STEEL		
COMP	COMPRESSION	FT	FOOT; FEET	NO or #	NUMBER	SSL	SHORT SLOTTED HOLES		
CONC	CONCRETE	FTA	FLOOR TIE ABOVE	NTS	NOT TO SCALE	STD	STANDARD		
CONN	CONNECTION; CONNECT	FTG	FOOTING	OC	ON CENTER	STGR	STAGGER		
CONSTR	CONSTRUCTION	GA	GAUGE	OD	OUTSIDE DIAMETER	STIFF	STIFFENERS		
CONT	CONTINUE; CONTINUOUS	GALV	GALVANIZED	OF	OUTSIDE FACE	STIRR	STIRRUP		
CONTR	CONTRACTOR	GB	GRADE BEAM	OH	OPPOSITE HAND	STL	STEEL		
CJP	COMPLETE JOINT PENETRATION WELD	GLB	GLUED LAMINATED BEAM	OPNG	OPENING	STRUCT	STRUCTURAL		
CTR	CENTER	GR	GRADE	OPP	OPPOSITE	SW	SHEAR WALL		
CTSK	COUNTERSINK; COUNTERSUNK	GRND	GROUND	ORIG	ORIGINAL	SYM	SYMMETRICAL		
CU FT	CUBIC FOOT	H or HORIZ	HORIZONTAL	OSB	ORIENTED STRAND BOARD	TB	TIE BEAM		



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK


SHEET INDEX, ABBREVIATION
& SYMBOL

DATE
11/20/2023

SHEET

S-101

N:\2000\2244-01\CI01-WalnutCreek-ADO\Structural\ConDocs\Sheet\Final\2244-01-CI01 - \$103.dwg, PLN1 - \$103, Nov 20, 2022, 12:32pm, dloaez



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK

GENERAL NOTES, SPECIAL
INSPECTION & TESTS

DATE
11/20/2023

SHEET

S-103

REQUIRED VERIFICATION AND INSPECTIONS

WOOD CODE CHAPTER 17 AND REFERENCED 2018 NDS AND AWC SDPWS-2015			
SPECIAL INSPECTION OR TEST	CONTINUOUS	PERIODIC	CBC REFERENCE
3. WOOD LATERAL FORCE-RESISTING SYSTEM WITH FASTENER SPACING OF THE SHEATHING LESS THAN OR EQUAL TO 4" OC. - WOOD SHEAR WALLS - WOOD DIAPHRAGMS - DRAG STRUTS - SHEAR PANELS - HOLD-DOWNS	—	X	1705.13.2
4. WOOD LATERAL FORCE-RESISTING SYSTEM WITH FASTENER SPACING OF THE SHEATHING GREATER THAN 4" OC (NOT REQUIRED) - WOOD SHEAR WALLS - WOOD DIAPHRAGMS - DRAG STRUTS - SHEAR PANELS - HOLD-DOWNS	—	—	1705.13.2

STATEMENT OF SPECIAL INSPECTIONS

- THIS STATEMENT OF SPECIAL INSPECTIONS HAS BEEN PREPARED PURSUANT TO SECTION 1704.3 OF THE CODE . THIS SECTION DETAILS BOTH REQUIRED SPECIAL INSPECTIONS AND TESTS INCLUDING TESTING PER SECTION 1705 OF THE CODE. THE FOLLOWING SHALL BE OBSERVED DURING THEIR IMPLEMENTATION:
 - GENERAL:
 - STRUCTURAL VERIFICATIONS, INSPECTIONS AND TESTS SHALL BE PERFORMED IN ACCORDANCE WITH CHAPTER 17 OF THE CODE AND/OR THE APPLICABLE REFERENCE STANDARD.
 - OWNER REQUIREMENTS:
 - THE OWNER OR OWNER'S AGENT SHALL EMPLOY ONE OR MORE APPROVED AGENCIES TO PERFORM INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK LISTED IN SECTION 1705 OF THE CODE AND IN THIS STATEMENT OF INSPECTIONS.
 - SPECIAL INSPECTOR QUALIFICATIONS:
 - THE SPECIAL INSPECTIONS SHALL PROVIDE WRITTEN DOCUMENTATION TO THE BUILDING OFFICIAL DEMONSTRATING HIS OR HER COMPETENCE AND RELEVANT EXPERIENCE OR TRAINING. THE EXPERIENCE OR TRAINING SHALL BE CONSIDERED RELEVANT WHEN THE DOCUMENTED EXPERIENCE OR TRAINING IS RELATED IN COMPLEXITY TO THE SAME TYPE OF SPECIAL INSPECTION ACTIVITIES FOR PROJECTS OF SIMILAR COMPLEXITY AND MATERIAL QUANTITIES.
 - CONTRACTOR REQUIREMENTS:
 - SPECIAL INSPECTION IS IN ADDITION TO THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS AND TESTING. THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS AND TESTING SHALL OCCUR PRIOR TO SPECIAL INSPECTION AND REPORTS SHALL BE AVAILABLE TO THE SPECIAL INSPECTOR.
 - THE CONTRACTOR SHALL ENSURE THAT THE WORK FOR WHICH SPECIAL INSPECTION IS REQUIRED REMAINS ACCESSIBLE AND EXPOSED FOR SPECIAL INSPECTION PURPOSES UNTIL COMPLETION OF THE REQUIRED SPECIAL INSPECTION.
 - ANY CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF THE MAIN WIND OR SEISMIC FORCE RESISTING SYSTEM SHALL SUBMIT A WRITTEN STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND OWNER PRIOR TO COMMENCEMENT OF WORK ON THE SYSTEM OR COMPONENT. THE STATEMENT OF RESPONSIBILITY SHALL CONTAIN ACKNOWLEDGEMENT OF AWARENESS OF THE SPECIAL INSPECTION REQUIREMENTS CONTAINED IN THE STATEMENT OF SPECIAL INSPECTIONS.
 - SPECIAL INSPECTOR REPORT REQUIREMENTS:
 - THE SPECIAL INSPECTOR SHALL KEEP RECORD OF INSPECTIONS
 - THE SPECIAL INSPECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL AND TO THE ARCHITECT AND STRUCTURAL ENGINEER OF RECORD.
 - REPORTS SHALL INDICATE THAT WORK INSPECTED WAS OR WAS NOT COMPLETED IN CONFORMANCE TO APPROVED CONSTRUCTION DOCUMENTS.
 - DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION.
 - IF NOT CORRECTED DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND THE ARCHITECT AND STRUCTURAL ENGINEER OF RECORD PRIOR TO THE COMPLETION OF THAT PHASE OF WORK.
 - A FINAL REPORT DOCUMENTING SPECIAL INSPECTIONS AND CORRECTION OF ANY DISCREPANCIES NOTED SHALL BE SUBMITTED TO THE BUILDING OFFICIAL.

SHOP FABRICATION

- SHOP FABRICATION REQUIRES SPECIAL INSPECTION IN ACCORDANCE WITH CODE SECTION 1704.2.5. EXCEPTION: SHOP SPECIAL INSPECTIONS ARE NOT REQUIRED WHEN WORK IS DONE ON THE PREMISES OF FABRICATOR REGISTERED AND APPROVED TO PERFORM SUCH WORK IN ACCORDANCE WITH CODE SECTION 1704.2.5.1. THE FOLLOWING ACCREDITATIONS MEET THE REQUIREMENTS OF THIS EXCEPTION
 - WOOD BUILDINGS
 - WOOD STRUCTURAL PANELS (SHEATHING) SHALL BE IDENTIFIED BY THE APA TRADEMARK.

WOOD STRUCTURAL PANELS (SHEATHING)

- WOOD STRUCTURAL PANELS SHALL MEET THE FOLLOWING MINIMUM STANDARDS EXCEPT WHERE OTHERWISE NOTED:

WOOD STRUCTURAL PANEL PROPERTIES							
USE	PLY	BOND CLASSIFICATION ^C	SHEATHING GRADE	PERFORMANCE RATING	SPAN RATING	RATING ^B	REFERENCE ^A
ROOF	5	EXPOSURE 1	REFER TO TYPICAL DIAPHRAGM SCHEDULE			APA	2022 CBC 2303.1.5 (DOC PS 1-09 OR PS 2-10)
FLOOR	5	EXPOSURE 1				APA	
WALL ^D	5	EXPOSURE 1	REFER TO TYPICAL SHEAR WALL SCHEDULE			APA	


TABLE NOTES:

- WOOD STRUCTURAL PANELS SHALL CONFORM TO THE REQUIREMENTS FOR THEIR TYPE IN ACCORDANCE WITH THE FOLLOWING VOLUNTARY STANDARDS BY THE ENGINEERED WOOD ASSOCIATION (APA):
 - VOLUNTARY PRODUCT STANDARD, STRUCTURAL PLYWOOD, PS 1-09
 - VOLUNTARY PRODUCT STANDARD, PERFORMANCE STANDARD FOR WOOD-BASED STRUCTURAL-USE PANELS, PS 2-10
 - WOOD STRUCTURAL PANELS SHALL BE IDENTIFIED BY THE APA TRADEMARK INDICATING CONFORMANCE TO THE APPLICABLE VOLUNTARY STANDARD
 - WHERE PANELS ARE EXPOSED TO REPEATED WETTING AND REDRYING, LONG-TERM EXPOSURE TO WEATHER, OR CONDITIONS OF SIMILAR SEVERITY, "EXTERIOR" APA RATED PLYWOOD SHEATHING SHALL BE USED. C-D "EXPOSURE 1" APA RATED PLYWOOD SHEATHING (CDX) SHALL NOT BE USED FOR CONDITIONS INVOLVING LONG-TERM EXPOSURE TO WEATHER.
 - EXCEPTION: WOOD STRUCTURAL PANEL ROOF SHEATHING EXPOSED TO THE OUTDOORS ON THE UNDERSIDE IS PERMITTED TO BE "EXPOSURE 1" TYPE.
 - WOOD STRUCTURAL PANELS TO BE USED AS SIDING SHALL COMPLY WITH ANSI/APA PRP-210.
 - ORIENTED STRAND BOARD (OSB) WITH EQUIVALENT CLASSIFICATION AND RATINGS MAY BE USED IN LIEU OF PLYWOOD FOR WOOD STRUCTURAL PANEL WALL SHEATHING.
- TRANSPORTATION, STORAGE, AND HANDLING:
 - TRANSPORTATION
 - IN TRANSPORTING PANELS ON OPEN TRUCK BEDS, COVER THE BUNDLES WITH A TARP.
 - STORAGE
 - ALWAYS STORE THE PANELS UNDER COVER WHENEVER POSSIBLE
 - WHEN STORING PANELS OUTSIDE STACK THEM ON A LEVEL SURFACE ON TOP OF STRINGERS OR OTHER BLOCKING, THREE STRINGERS MINIMUM.
 - NEVER LEAVE PANELS IN CONTACT WITH THE GROUND
 - COVER THE STACK WITH A PLASTIC TARP, ENSURING THAT THE BUNDLE IS WELL VENTILATED TO PREVENT MILDEW.
 - IF MOISTURE ABSORPTION IS EXPECTED, CUT THE STEEL BAND TO PREVENT DAMAGE
 - KEEP SANDED OR OTHER APPEARANCE GRADE PANELS AWAY FROM HIGH TRAFFIC AREAS
 - HANDLING
 - ALWAYS PROTECT ENDS AND EDGES, ESPECIALLY TONGUE AND GROOVE PRODUCTS, FROM PHYSICAL DAMAGE.
 - ACCLIMATE THE PANELS FOR 24 HOURS MINIMUM BEFORE INSTALLATION BY STANDING THE PANELS ON EDGE WITH A GAP BETWEEN EACH TO ALLOW FOR AIR CIRCULATION OR PER MANUFACTURER'S RECOMMENDATIONS.
 - PLYWOOD ORIENTATION

- ROOF AND FLOOR SHEATHING SHALL BE LAID WITH THE GRAIN OF THE OUTER PILES PERPENDICULAR TO THE FRAMING MEMBERS. SHALL BE CONTINUOUS OVER 2 JOIST BAYS MINIMUM AND END JOINTS SHALL BE JOINED OVER FRAMING AND STAGGERED. LEAVE A $\frac{1}{8}$ " GAP BETWEEN PANELS TO ALLOW FOR PANEL EXPANSION UNLESS RECOMMENDED OTHERWISE BY THE PANEL MANUF. REFER TO SPECIFIC DETAILS IN THE DRAWINGS FOR FURTHER PARAMETERS.
 - PLYWOOD OR OSB WALL SHEATHING MAY BE APPLIED VERTICALLY OR HORIZONTALLY. ALL END JOINTS BE JOINED OVER FRAMING AND STAGGERED.
- BLOCKING:
 - ROOF: ALL ROOF SHEATHING SHALL BE BLOCKED UNLESS SPECIFICALLY ALLOWED ON PLANS, WHERE PERMITTED TO BE UNBLOCKED, ALL UNBLOCKED EDGES SHALL BE TONGUE AND GROOVE.
 - FLOOR SHEATHING SHALL BE BLOCKED UNLESS SPECIFICALLY ALLOWED ON PLANS, WHERE PERMITTED TO BE UNBLOCKED, ALL UNBLOCKED EDGES SHALL BE TONGUE AND GROOVE.
 - WALLS: ALL SHEAR WALLS SHALL BE FULLY BLOCKED AT PLYWOOD EDGES.
 - FASTENERS
 - USE SHEATHING NAILS SAME GAUGE AS COMMON WIRE NAILS WITH LENGTHS AT LEAST EQUAL TO SHEATHING THICKNESS PLUS REQUIRED PENETRATION PER AWS SDPWS TABLE 4.2A OR 4.3A (AS REQUIRED).
 - EQUIVALENT PNEUMATIC DRIVE NAILS OR STAPLES MAY BE USED IF FASTENER MANUFACTURER HAS RECEIVED ICC OR IAPMO APPROVAL FOR THE INTENDED US. FASTENERS TO BE SUBSTITUTED SHALL BE EQUIVALENT IN LATERAL AND WITHDRAWAL STRENGTH TO THE SIZE OF COMMON NAIL SPECIFIED.
 - USE OF MACHINE NAILING IS SUBJECT TO A SATISFACTORY JOB SITE DEMONSTRATION FOR EACH PROJECT AND THE APPROVAL BY THE PROJECT ARCHITECT OR STRUCTURAL ENGINEER. THE APPROVAL IS SUBJECT TO CONTINUED SATISFACTORY PERFORMANCE. MACHINE NAILING WILL NOT BE APPROVED IN 5/16" PLYWOOD OR OSB SHEATHING. IF NAIL HEADS PENETRATE THE OUTER PLY MORE THAN WOULD BE NORMAL FOR A HAND HAMMER OR IF MINIMUM ALLOWABLE EDGE DISTANCES ARE NOT MAINTAINED, THE PERFORMANCE WILL BE DEEMED UNSATISFACTORY.
 - TYPICAL NAILING SHALL BE 10D AT 6" O.C. AT ALL SUPPORTED EDGES AND OVER SHEAR WALLS, AND 10D AT 12" O.C. AT ALL INTERMEDIATE SUPPORTS, UNLESS OTHERWISE NOTED. SEE PLANS AND REFER TO SHEAR WALL SCHEDULE.

N:\2000\2264-01\CI01-WalnutCreek-ADU\Structural\ConDocs\Sheet Files\Plan\1\2264-01\CI01 - Plan.dwg, 5/1/2021, Nov 20, 2023 12:33pm, dlp@pc

FOR USE IN THE CITY OF WALNUT CREEK




1 FOUNDATION PLAN - CALIFORNIA RANCH - COTTAGE - MODERN
SCALE: 1/4" = 1'-0"

FOUNDATION PLAN NOTES

- REFER TO THE FOLLOWING SHEETS FOR TYPICAL DETAILS:

DESCRIPTION	SHEET (S)
SYMBOLS AND ABBREVIATIONS	S-101
STRUCTURAL GENERAL NOTES	S-102 - S-103
TESTING AND INSPECTION	S-103
TYPICAL CONCRETE DETAILS	S-301
TYPICAL WOOD DETAILS	S-401 - S-404
- SEE ARCHITECTURAL DRAWINGS FOR FINISHED FLOOR ELEVATIONS, REFERENCE FINISHED FLOOR ELEVATION = 0'-0" CORRESPONDS TO FINISHED FLOOR ELEVATION.
- ALL DIMENSIONS SHOWN ARE FROM FACE OF CONCRETE/MASONRY, FACE OF SHEATHING, OR CENTERLINE OF COLUMN. ALL COLUMNS ARE CENTERED IN STUD WALLS, UNO.
- FOR ANY DIMENSIONAL INFORMATION NOT SHOWN, SEE ARCHITECTURAL DRAWINGS.
- SEE ARCHITECTURAL DRAWINGS FOR ANY EMBEDDED ITEMS AND ALL EXTERIOR CONCRETE PAVING.
- SEE PLANS AND ARCHITECTURAL DRAWINGS FOR DEPRESSIONS AND/OR SLOPES IN CONCRETE SLABS.
- SEE ARCHITECTURAL DRAWINGS FOR SIZE AND LOCATION OF ALL DOOR AND WINDOW OPENINGS IN BEARING AND NON-BEARING WALLS.
- SEE ARCHITECTURAL DRAWINGS FOR LOCATION OF INTERIOR NON-BEARING PARTITIONS.
- SEE ARCHITECTURAL, PLUMBING, MECHANICAL AND ELECTRICAL DRAWINGS FOR ADDITIONAL EMBEDDED ITEMS AND SLAB PENETRATIONS.
- FOR TYPICAL SLAB-ON-GRADE REQUIREMENTS, INCLUDING SLAB JOINTS, SEE DETAIL 31/S-301.
- ALL POSTS IN 4" WALLS SHALL BE 4x4, UNLESS NOTED OTHERWISE
ALL POSTS IN 6" WALLS SHALL BE 6x6, UNLESS NOTED OTHERWISE
- PLATE WASHERS ARE REQUIRED FOR ALL SILL PLATE ANCHOR BOLTS. REFER TO 34/S-402 FOR PLATE WASHER REQUIREMENTS AT SHEAR WALLS.
- ALL HOLDOWN ANCHOR NUTS SHALL BE TIGHTENED JUST PRIOR TO COVERING.
- ALL BOLT HOLES IN WOOD MEMBERS, SHALL BE DRILLED A MAXIMUM OF 1/8" OVERSIZED, INSPECTOR TO VERIFY.
- THE BUILDING PAD SHALL BE PREPARED AS OUTLINED IN DETAIL 53/S-301. THE BUILDING OFFICIAL SHALL REQUIRE PAD CERTIFICATION BY A GEOTECHNICAL ENGINEER AT THEIR DISCRETION.
- BOTTOM OF FOOTING SHALL BE, UNLESS DEEPER FOUNDATIONS ARE REQUIRED BY THE BUILDING OFFICIAL:
 - 21" BELOW PAD OR ADJACENT GRADE AT PERIMETER, WHICHEVER IS DEEPER, UNO.
 - 21" BELOW PAD OR ADJACENT GRADE AT INTERIOR GRADE BEAMS, WHICHEVER IS DEEPER, UNO.NOTE: FOOTING MUST BE DEEPENED LOCALLY PER DETAIL 32/S-301 TO ACCOMMODATE ANCHOR BOLT HOLDOWN EMBED DEPTHS.
- FOR DEEPENED FOOTING REFER TO 14/S-312. DISTANCE TO DAYLIGHT MUST BE A MINIMUM OF 10'-0" AS MEASURED FROM THE BOTTOM OF THE FOOTING. SHOULD THE SITE REQUIRE RETAINING WALLS TO FLATTEN THE LOT, REFER TO NOTES ON COVER SHEET FOR PERMITTING REQUIREMENTS.
- THIS PLAN IS INTENDED FOR FLAT LOTS (SLOPING LESS THAN 10° ACROSS THE LONGEST BUILDING DIMENSION), WITHOUT HIGHLY EXPANSIVE OR LIQUEFIABLE SOILS, AND NOT IN FLOOD ZONE WHERE THE MAIN DWELLING UNIT IS SUPPORTED IN SHALLOW FOOTINGS WITH SLABS ON GRADE CONSTRUCTION. IF THE PROJECT SITE DEVIATES FROM ANY OF THE AFOREMENTIONED QUALITIES, AS DETERMINED BY THE BUILDING OFFICIAL, THESE PRE-APPROVED ADU FOUNDATION PLANS AND DETAILS ARE NOT APPLICABLE.

SYMBOL LEGEND



SCHEDULES

HOLDOWN SCHEDULE			
SPECIFIES HOLDOWN/STRAP DETAIL	INDICATES HOLDOWN/STRAP TYPE	DETAIL	
	INDICATES SIMPSON SSTB HOLDOWN TO: CONIC FOUNDATION:	12/S-311	

CONTINUOUS FOOTING SCHEDULE					
MARK	WIDTH	MIN EMBED BELOW LOWEST PAD GRADE	LONG REINF	TRANS REINF	DETAIL
C1.23	1'-3"	SEE NOTE 16	(2) #5 T88	#3 @ 12" OC, BOT	31/S-311

GRADE BEAM SCHEDULE						
TYPE	WIDTH	THICKNESS	MIN EMBED BELOW LOWEST PAD GRADE	LONG REINF	TRANS REINF	DETAIL
GB1	1'-0"	1'-0"	SEE NOTE 16	(2) #4 @ TOP (2) #4 @ BOT	#3 @ 24" OC	13/S-312

PAD FOOTING SCHEDULE							
TYPE	WIDTH	LENGTH	THICKNESS	MIN EMBED BELOW LOWEST PAD GRADE	TOP REINF	BOT REINF	DETAIL
F2	2'-0"	2'-0"	1'-6"	SEE NOTE 16	(3) #5, EW	(3) #5 @, EW	PER PLAN

NOTE: FOOTING MUST BE DEEPENED LOCALLY PER DETAIL 32/S-301 TO ACCOMMODATE AB HOLDOWN EMBED DEPTHS



CITY OF
WALNUT
CREEK

THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU


CITY OF WALNUT CREEK

FOUNDATION PLAN


DATE
11/20/2023

SHEET


S-201



2 ROOF FRAMING PLAN - COTTAGE
SCALE: 1/4" = 1'-0"



3 ROOF FRAMING PLAN - MODERN
SCALE: 1/4" = 1'-0"



1 ROOF FRAMING PLAN - CALIFORNIA RANCH
SCALE: 1/4" = 1'-0"

ROOF FRAMING NOTES

- SEE ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS AND ELEVATIONS INCLUDING, BUT NOT LIMITED TO THE FOLLOWING. ALL DIMENSIONS TO BE VERIFIED PRIOR TO CONSTRUCTION:
 - GRID DIMENSIONS AND HORIZONTAL CONTROL
 - ALL DIMENSIONS, ELEVATIONS, FINISH SURFACE, SLOPES, DRAINS, SLAB DEPRESSIONS, ETC.
 - LOCATION AND EXTENT OF EXTERIOR WALL ASSEMBLIES AND OPENINGS
 - ALL NON STRUCTURAL WALLS
- REFER TO THE FOLLOWING SHEETS FOR TYPICAL DETAILS:

DESCRIPTION	SHEET (S)
SYMBOLS AND ABBREVIATIONS	S-101
STRUCTURAL GENERAL NOTES	S-102 - S-103
TESTING AND INSPECTION	S-103
TYPICAL CONCRETE DETAILS	S-301
TYPICAL WOOD DETAILS	S-401 - S-404
- SEE ARCHITECTURAL DRAWINGS FOR ALL TOP OF SHEATHING AND TOP OF WALL ELEVATIONS.
- SEE ARCHITECTURAL, PLUMBING, MECHANICAL AND ELECTRICAL DRAWINGS FOR SIZE AND LOCATION OF PIPES, DUCTS AND OTHER ROOF PENETRATIONS. FOR ROOF PENETRATIONS NOT SHOWN ON ROOF FRAMING PLAN, SEE DETAIL 23/S-403 FOR TYPICAL OPENINGS, UNO.
- ALL POSTS IN 6" WALLS SHALL BE 6x6, UNLESS NOTED OTHERWISE.

TYPICAL WALL FRAMING SHALL BE:
2x6 @ 16" OC @ ALL EXTERIOR WALLS, UNO
2x6 @ 16" OC @ ALL INTERIOR BEARING WALLS, UNO
2x4 @ 16" @ ALL INTERIOR NON-BEARING WALLS, UNO
- ALL INTERIOR WALLS NOT SHOWN ON THE STRUCTURAL FRAMING PLANS BUT SHOWN ON THE ARCHITECTURAL DRAWINGS SHALL BE CONSTRUCTED PER NON-BEARING PORTION WALL DETAIL 43/S-401, UNO.
- DIAPHRAGM TYPES:
ALL ROOF DIAPHRAGMS SHALL BE TYPE A, UNO REFER TO 12/S-403
- ALL LINES AND/OR MEMBERS INDICATED AS "STRUT" SHALL RECEIVE (2) ROWS OF BOUNDARY NAILING (BN), STGR.

SYMBOL LEGEND

- XX'-X" X
INDICATES SHEAR WALL TYPE AND LENGTH. SEE SCHEDULE ON 13/S-402
- X
INDICATES BLOCKING & STRAPPING ABOVE & BELOW WINDOW OPENINGS PER DETAIL 44/S-402
- INDICATES HEADER @ OPENING, REFER TO 32/S-401 FOR HEADER SIZE, UNO ON PLANS
- X
INDICATES TOP PLATE SPLICE NAILING PER 31/S-403 NOTE THAT NAILING APPLIES TO ENTIRE LENGTH OF TOP PLATE. PROVIDE TYPE (C) SPLICE, UNO
- INDICATES STRAP PER 34/S-403, UNO

SCHEDULES

HOLDOWN SCHEDULE		
SPECIFIES HOLDOWN/STRAP TYPE	INDICATES HOLDOWN/STRAP TYPE	DETAIL
6x	INDICATES SIMPSON SSTB HOLDOWN TO: CONCR FOUNDATION:	12/S-311

ROOF BEAM SCHEDULE		
MARK	SIZE	REMARKS
B1	6x8	
B2	4x8	
B3	6x10	
B4	1 1/2"x 11 1/8" LVL (2.0E)	2 PLY 14/S-401
B5	4x12	

ROOF RAFTER SCHEDULE		
MARK	SIZE	REMARKS
R1	2x8 @ 24" OC	



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU

CITY OF WALNUT CREEK






ROOF FRAMING PLAN


DATE
11/20/2023

SHEET

S-202

N:\2200\2244-01\CI01-WalnutCreek-ADO\Structural\ConDoc3\Sheet\Files\2244-01\CI01 - S312.dwg, PLN1 - S312, Nov 20, 2023 1:23:22pm, dsopez

																	
	51		41	SPREAD FOOTING @ BEARING WALL POST 2244-01-CI01 - S312				3/4" = 1'-0"	11								
	52		42	 <table data-bbox="1828 979 2041 1081"><tr><th>POST SIZE</th><th>MIN. SIDE COVER</th></tr><tr><td>4x4</td><td>0'-3"</td></tr><tr><td>6x6</td><td>0'-3"</td></tr><tr><td>8x8</td><td>0'-3"</td></tr></table> 		POST SIZE	MIN. SIDE COVER	4x4	0'-3"	6x6	0'-3"	8x8	0'-3"				
POST SIZE	MIN. SIDE COVER																
4x4	0'-3"																
6x6	0'-3"																
8x8	0'-3"																
	53		43	PORCH PAD FOOTING 2244-01-CI02 - S312 - 23		1/2" = 1'-0"	23	GRADE BEAM 2244-01-CI01 - S312									
	54		44				24	DEEPEND EXTERIOR FOOTING 2244-01-CI01 - S312									



CITY OF
WALNUT
CREEK

THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK

CONCRETE DETAILS

DATE
11/20/2023

SHEET
S-312



CITY OF WALNUT CREEK

THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU


CITY OF WALNUT CREEK

TYPICAL WOOD DETAILS

DATE
11/20/2023


SHEET

S-402



CORNER W/O POST

INTERSECTION W/O POST



CORNER W/ POST


INTERSECTION W/ POST

Shear Wall Intersection

2264-01-C101 - S402 - 42

NTS

42



STRAP AT STEP IN SHEAR WALL SILL PLATE

2264-01-C101 - S402 - 53

NTS

53

TYPICAL BLOCKING DETAIL

2264-01-C101 - S402 - 43

NTS

43

TYPICAL SHEAR WALL ELEVATION AND SCHEDULE

2264-01-C101 - S402 - 13

NTS

13

MARK	# OF BLKG	SIMPSON STRAP	NAILS EA SIDE OF OPENING	STRAP LENGTH (IN)	ALLOWABLE TENSION LOADS (LBS)
▽	1	CS20	(12) 10d x 2 1/2"	32'	1,030
▽	1	CS16	(20) 10d x 2 1/2"		1,705
▽	1	CS14	(26) 10d x 2 1/2"		2,490
▽	2	CMST16	(50) 10d x 3 1/2"		4,690
▽	2	CMST14	(66) 10d x 2 1/2"	39'	6,475
▽	2	CMST12	(86) 10d x 2 1/2"		9,215

- NOTES:
- 2 BAYS OR 32' MIN STRAP LENGTH
 - BOUNDARY AND EDGE NAILING FROM PLYWOOD TO STUDS / FRAMING SHALL OCCUR ABOVE AND BELOW OPENINGS AT THIS CONDITION
 - SEE TYPICAL SHEAR WALL ELEVATION FOR BALANCE OF INFO NOT SHOWN

FORCE TRANSFER AROUND OPENINGS

2264-01-C101 - S402 - 44

NTS

44

PLATE WASHER DETAIL

2264-01-C101 - S402 - 34

NTS

34

DOUBLE SIDED SHEAR WALL

2264-01-C101 - S402 - 24

NTS


24

2x STUD NAILING @ ADJOINING PANEL EDGES

2264-01-C101 - S402 - 14




NTS


14




SHEAR WALL SHEATHING / NAILING SCHEDULE										
WALL SYMBOL	STRUCT SHEATHING	1,12 FRAMING SIZE	NAILING			2,3,4 SILL NAILING		7 ANCHOR BOLTING		10, 11
			(2) 2x STUD	EDGE	INTERMEDIATE SUPPORTS	NAILS /LAG-SCREWS @ 16" OC	8 SDS SCREWS OPTION	A35s		
	15/32" STRUCT 1 PLYWOOD	2x	10d @ 9" OC	8d @ 6" OC	8d @ 12" OC	16d @ 6" OC	12" OC	24" OC	5/8" DIA @ 48" OC	
	15/32" STRUCT 1 PLYWOOD	2x	10d @ 8" OC	10d @ 6" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	12" OC	16" OC	5/8" DIA @ 48" OC	
	15/32" STRUCT 1 PLYWOOD	2x	10d @ 5" OC	10d @ 4" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	8" OC	12" OC	5/8" DIA @ 32" OC	
	15/32" STRUCT 1 PLYWOOD	2x	10d @ 4" OC	10d @ 3" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	6" OC	8" OC	5/8" DIA @ 32" OC	
	15/32" STRUCT 1 PLYWOOD	2x	10d @ 3" OC	10d @ 2" OC	10d @ 12" OC	5/8" LAG SCREWS @ 8" OC	4" OC	8" OC	5/8" DIA @ 24" OC	
	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 5" OC	10d @ 4" OC	10d @ 12" OC	5/8" LAG SCREWS @ 8" OC	(2) @ 8" OC *	6" OC	5/8" DIA @ 16" OC	
	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 4" OC	10d @ 3" OC	10d @ 8" OC	5/8" LAG SCREWS @ 8" OC	(2) @ 6" OC *	A34 @ 4" OC	5/8" DIA @ 16" OC	
	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 3" OC	10d @ 2" OC	10d @ 6" OC	5/8" LAG SCREWS @ 6" OC	(2) @ 4" OC *	LTP4 @ 15" 4" OC	5/8" DIA @ 8" OC	

- NOTES:
- ALL PLYWOOD SHALL BE 5 PLY MINIMUM WITH A SPAN RATING OF 32/16 AND ALL PANEL EDGES SHALL BE BLOCKED. PROVIDE 1/8" GAP AT ALL PANEL JOINTS.
 - ALL NAILS SHALL BE COMMON NAILS.
 - PROVIDE E.N., AT ALL END STUDS, STUDS/POSTS WITH HOLDOWNS OR THE DOWN STRAPS, SILL PLATES AND TOP PLATES.
 - WHERE 10d NAILS ARE 3 INCHES ON CENTER OR LESS, NAILS SHALL BE STAGGERED.
 - NAILS SHALL BE 1/2 INCH MINIMUM FROM PLYWOOD PANEL EDGE AND 3/8 INCH MINIMUM FROM CONNECTING MEMBER EDGE WHERE SHEAR EXCEEDS 300 PLF.
 - USE 3x FRAMING AT BOTTOM SILL PLATES, BLOCKING AND ALL STUDS AT ADJACENT PANEL EDGES WHERE SHEAR EXCEEDS 300 PLF. STRUCTURALLY ACCEPTABLE TO USE (2) 2x INSTEAD OF 3x FRAMING AT BOTTOM SILL PLATES.
 - WHERE SILL SHEAR TRANSFER IS THROUGH LAG SCREWS, SILL PLATE SHALL BE A MINIMUM OF 2 1/2" THICK.
 - LAG SCREWS SHALL BE 6 INCHES LONG AND HOLES ARE TO BE PRE-DRILLED AS TO NOT SPLIT BLOCKING/RIM.
 - SEE ELEVATION ABOVE FOR TYPICAL CONSTRUCTION.
 - REFER TO PLATE WASHER DETAIL FOR REQUIREMENTS
 - LENGTHEN ANCHOR BOLTS AS REQUIRED FOR EMBEDMENT AND SILL PLATE THICKNESS.
 - ORIENTED STRAND BOARD (OSB) MAY BE SUBSTITUTED FOR PLYWOOD NOTED ABOVE PROVIDED IT IS RATED BY APA'S PERFORMANCE STANDARD RATING AND IS OF THE SAME NUMBER OF LAYERS AS PLYWOOD PLY INDICATED.
 - LIMITATIONS OF MECHANICAL PENETRATIONS IN SHEAR WALLS:
 - A. 4 1/2" MAX PENETRATION.
 - B. NO CUTS OR HOLES IN SHEATHING WITHIN 16" OF CORNERS, SQUARE PENETRATIONS SHALL RADIUS EDGES. DO NOT OVER CUT HOLE WITH SAW.
 - ASSUMES A 1 1/4" MIN LSL RIM BOARD. FASTENER EDGE DIST IS 5/8" MIN & 6" END DISTANCE MIN. 2" MIN PENETRATION INTO RIM BOARD.
 - * WALL W/ DOUBLE SIDED PLYWOOD REQUIRE (2) RIM BOARDS.
 - SIMPSON LTP4 CLIP SHALL BE INSTALLED IN A HORIZONTAL ORIENTATION. IF CLIP IS INSTALLED OVER THE SHEATHING, 0.131" x 2 1/2" NAILS SHALL BE USED.





THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




DIAPHRAGM SCHEDULE												
TYPE	LOCATION	SHEATHING THICKNESS	SHEATHING GRADE	SPAN RATING	BLOCKING	NAILS	BOUNDARY NAILING (BN)	EDGE NAILING AT CONT. PANEL EDGES (EN)	EDGE NAILING AT OTHER PANEL EDGES (EN)	FIELD NAILING (FN)	PANEL EDGE SUPPORT OR NOMINAL MEMBER WIDTH AT PANEL EDGES	LINES OF FASTENERS
A	ROOF	SEE NOTE 5	SHEATHING	32 / 16	NO	10d	6	-	6	12	H-CLIPS	1
B	ROOF	SEE NOTE 5	SHEATHING	32 / 16	YES	10d	4	4	6	12	2x FLAT	1

- NOTES:
- NOT USED.
 - MINIMUM EDGE DISTANCE FOR NAILS SHALL BE 1/2" FROM SHEATHING EDGE AND 3/4" FROM LUMBER EDGE.
 - NAILS SHALL BE DRIVEN TIGHT TO TOP OF PLYWOOD SURFACE AND SHALL NOT PENETRATE THE TOP OF PLYWOOD MORE THAN COMMONLY EXPECTED WITH HAMMER DRIVEN NAILS.
 - WHERE H-CLIPS ARE SPECIFIED, THEY SHOULD BE INSTALLED AS FOLLOWS:
 - ONE H-CLIP SHALL BE PLACED BETWEEN ABUTTING PANELS AT A LOCATION MIDWAY BETWEEN EACH PAIR OF TRUSSES, RAFTERS OR JOISTS. HOWEVER, (2) H-CLIPS ARE REQUIRED BETWEEN SUPPORTS WHEN SPACED 48 INCHES ON CENTER.
 - USE THE SAME SIZE PANEL EDGE CLIP AS THE PANEL THICKNESS. H-CLIPS MUST FIT SNUGLY.
 - ABUTTING WOOD STRUCTURAL PANELS BE FITTED AS CLOSELY AS CLIPS PERMIT. OCCASIONAL MISFIT OF ABUTTING SHEETS MAY BE TOLERATED PROVIDING THAT GAPS DO NOT EXCEED MAXIMUM OPENING OF 1/2".
 - ROOF SHEATHING THICKNESS SHALL BE INSTALLED AS FOLLOWS:
 - 1/2" @ SINGLE PLY OR ASPHALT SHINGLES
 - 3/8" @ TILE
 - 3/4" @ TILE WITH MORTAR
 - STRUCTURALLY ACCEPTABLE TO USE 'SHEATHING' SHEATHING GRADE @ FLOOR LOCATIONS WITHOUT GYPCRETE TOPPING

PLYWOOD DIAPHRAGM SHEATHING

2264-01-C101 - S403 - 12

NTS 12




NOTE: FOR LARGER OPENINGS REFER TO FRAMING PLAN

OPENING AT FRAMING

2264-01-C101 - S403 - 23

NTS 23




MAXIMUM BORED HOLE DIAMETER/NOTCH DEPTH			
STUD SIZE (IN)	APPLICATION	MAX HOLE DIAMETER (IN)	MAX NOTCH DEPTH (IN)
2x4	NON-BEARING	2 1/8"	1 3/8"
	EXTERIOR/BEARING	1 3/8"	7/8"
2x6	NON-BEARING	3 1/4"	2 3/4"
	EXTERIOR/BEARING	2 3/4"	1 3/8"

- NOTES:
- NOTCHING AND BORING NOT PERMITTED IN THE SAME STUD SECTION.
 - NO MORE THAN 2 SUCCESSIVE DBL STUDS ARE PERMITTED TO HAVE 60% MAX BORED HOLES.

DIAPHRAGM PANEL JOINTS

2264-01-C101 - S403 - 13

NTS 13




NOTCH AND HOLE LIMITATIONS						
TOP PL OR SILL PL	A	B	C	D	E	F
2x4	3/4"	1/2"	1/4"	1/2"	3/4"	6
2x6	1/2"	3/4"	1/2"	1/2"	3/4"	9
2x8	3/4"	3"	3/4"	3/4"	1 1/4"	12

TOP PL AND SILL NOTCH AND BORING LIMITATIONS

2264-01-C101 - S403 - 14

NTS 14




TOP PLATE LAP NAILING		
WALL TYPE	MIN LAP SPICE	NAILS EA SIDE
NON-BEARING	2'-0"	(8) 16d

TOP PLATE LAP NAILING			
SYMBOL	MIN LAP SPICE	NAILS EA SIDE	ALLOWABLE TOP CHORD CAPACITY
⊙	4'-0"	(8) 16d	1,800#
⊙	4'-0"	(12) 16d	2,700#
⊙	4'-0"	(16) 16d	3,600#
⊙	4'-0"	(20) 16d	4,500#
⊙	4'-0"	(24) 16d	5,400#
⊙	4'-0"	(28) 16d	6,300#
⊙	4'-0"	(32) 16d	7,200#

DBL TOP PLATE SPICE NAILING

2264-01-C101 - S403 - 32

NTS 31




- NOTES:
- NOTCHING AND BORING NOT PERMITTED IN THE SAME JOIST CROSS SECTION WITHOUT STRUCTURAL ENGINEER'S APPROVAL.
 - NOTCH WIDTHS GREATER THAN SHOWN IN TABLE NOT PERMITTED WITHOUT STRUCTURAL ENGINEER'S APPROVAL.
 - NO NOTCHES OR HOLES PERMITTED ANYWHERE IN CANTILEVERED ELEMENTS WITHOUT STRUCTURAL ENGINEER'S APPROVAL

NOTCH AND HOLE LIMITATIONS				
JOIST SIZE	MAX HOLE	MAX NOTCH DEPTH	MAX END NOTCH	MAX NOTCH LENGTH
2x4	NONE	NONE	NONE	NONE
2x6	1 1/2"	1/2"	1 3/4"	1 1/2"
2x8	2 3/4"	1 1/2"	2 3/4"	2 3/4"
2x10	3"	1 1/2"	2 3/4"	3"
2x12	3 3/4"	1 1/2"	2 3/4"	3 3/4"

SAWN LUMBER AND RAFTER JOIST NOTCHING AND BORING LIMITATIONS

2264-01-C101 - S403 - 42


NTS 42



STRAP AT INTERRUPTED DOUBLE TOP PLATE

2264-01-C101 - S403 - 34

NTS 43



OUTLOOKER @ EXTERIOR SHEAR WALL




2264-01-C101 - S403 - 34

1" = 1'-0"

DRAG STRAP AT BEAM-TO-WALL


2264-01-C101 - S403 - 34

NTS 34



STRAP TO FACE OF DROP BEAM

2264-01-C101 - S403 - 34



STRAP TO TOP OF DROP BEAM


2264-01-C101 - S403 - 34

STRAP MODEL	END FASTENERS	END LENGTH (IN)	ALLOWABLE TENSION LOADS (IN)
CS16	(20) 10d	11	1,705
	(22) 8d	13	
CS14	(26) 10d	15	2,490
	(30) 8d	16	
CMSTC16	(50) 16d	20	4,690
CMST14	(56) 10d	26	6,475
CMST12	(74) 16d	33	9,215
	(86) 10d	39	

TYP WALL NOTCH AND BORING LIMITATIONS

2264-01-C101 - S403 - 24

NTS 24























THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK

ROOF FRAMING DETAILS

DATE
11/20/2023
SHEET

S-421

 2284-01-C101 - S401 - 51	1" = 1'-0"	51	 2284-01-C101 - S401 - 41	1" = 1'-0"	41	 2284-01-C101 - S401 - 31	NTS or 3/4" = 1'-0"	31	 2284-01-C101 - S401 - 21	1" = 1'-0"	21	 2284-01-C101 - S401 - 11	1" = 1'-0"	11
 2284-01-C101 - S401 - 52	1" = 1'-0"	52	 2284-01-C101 - S401 - 42	1" = 1'-0"	42	 2284-01-C101 - S401 - 32	1" = 1'-0"	32	 2284-01-C101 - S401 - 22	1" = 1'-0"	22	 2284-01-C101 - S401 - 12	1" = 1'-0"	12
 2284-01-C101 - S401 - 53	1" = 1'-0"	53	 2284-01-C101 - S401 - 43	NTS	43	 2284-01-C101 - S401 - 33	1" = 1'-0"	33	 2284-01-C101 - S401 - 23	1" = 1'-0"	23	 2284-01-C101 - S401 - 13	1" = 1'-0"	13
 2284-01-C101 - S401 - 54	1" = 1'-0"	54	 2284-01-C101 - S401 - 44	1" = 1'-0"	44	 2284-01-C101 - S401 - 34	1" = 1'-0"	34	 2284-01-C101 - S401 - 24	NTS	24	 2284-01-C101 - S401 - 14	1" = 1'-0"	14

N:\2200\2284-01-C101-WalnutCreek-ADU\Structural\ConDoc\Sheet\2284-01-C101 - S401.dwg, Plan 1, S401, Nov 20, 2023 12:33pm, adopez

BUILDING ENERGY ANALYSIS REPORT

PROJECT:
Walnut Creek ADUs (Plan 1)
Walnut Creek, CA

Project Designer:
RRM Design Group
3765 South Higuera St Ste 102
San Luis Obispo, CA 93401

Report Prepared by:
Timothy Carstairs, CEA, HERS, GPR
Carstairs Energy Inc.
2238 Bayview Heights Drive, Suite E
Los Osos, CA 93402
805-904-9048



Job Number:
23-02066

Date:
8/28/2023

The EnergyPro computer program has been used to perform the calculations summarized in this compliance report. This program has approval and is authorized by the California Energy Commission for use with both the Residential and Nonresidential 2022 Building Energy Efficiency Standards. This program developed by EnergySoft, LLC - www.energysoft.com.

TABLE OF CONTENTS

1	Cover Page
2	Table of Contents
3	Form CFIR-PRF-01-E Certificate of Compliance
15	Form RMS-1 Residential Measures Summary
16	Form MFR Mandatory Measures Summary
21	Room Load Summary

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
Project Name: Walnut Creek ADUs (Plan 1)
Calculation Date/Time: 2023-08-28T14:06:19-07:00
Calculation Description: Title 24 Analysis
Input File Name: Walnut Creek ADUs (Plan 1).rbd22x
CFIR-PRF-01E
(Page 2 of 12)

ENERGY DESIGN RATINGS	Energy Design Ratings			Compliance Margins		
	Source Energy (EDR1)	Efficiency ³ EDR (EDR2Efficiency)	Total ² EDR (EDR2Total)	Source Energy (EDR1)	Efficiency ³ EDR (EDR2Efficiency)	Total ² EDR (EDR2Total)
Standard Design	36.4	31.3	49.1			
Proposed Design						
North Facing	34.2	28.1	47	2.2	3.2	2.1
East Facing	33.8	26.1	45.8	2.6	5.2	3.3
South Facing	34.1	27.4	46.6	2.3	3.9	2.5
West Facing	33.7	26.4	46	2.7	4.9	3.1
RESULT: PASS						
¹ Efficiency EDR includes improvements like a better building envelope and more efficient equipment. ² Total EDR includes efficiency and demand response measures such as photovoltaic (PV) system and batteries. ³ Building complies when source energy, efficiency and total compliance margins are greater than or equal to zero and unmet load hour limits are not exceeded.						
* Standard Design PV Capacity: 0.00 kWdc * Proposed PV Capacity Scaling: North (0.00 kWdc) East (0.00 kWdc) South (0.00 kWdc) West (0.00 kWdc)						

Registration Number: 223-P0100628198-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance
Registration Date/Time: 2023-08-28 15:45:42
Report Version: 2022.0.000
Schema Version: rev 20220901
HERS Provider: CalCERTS inc.
Report Generated: 2023-08-28 14:07:35

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
Project Name: Walnut Creek ADUs (Plan 1)
Calculation Date/Time: 2023-08-28T14:06:19-07:00
Calculation Description: Title 24 Analysis
Input File Name: Walnut Creek ADUs (Plan 1).rbd22x
CFIR-PRF-01E
(Page 5 of 12)

ENERGY USE INTENSITY	Standard Design (kBtu/ft ² - yr)	Proposed Design (kBtu/ft ² - yr)	Compliance Margin (kBtu/ft ² - yr)	Margin Percentage
North Facing				
Gross EU1 ¹	40.81	37.92	2.89	7.08
Net EU1 ²	40.81	37.92	2.89	7.08
East Facing				
Gross EU1 ¹	40.81	37.31	3.5	8.58
Net EU1 ²	40.81	37.31	3.5	8.58
South Facing				
Gross EU1 ¹	40.81	37.73	3.08	7.55
Net EU1 ²	40.81	37.73	3.08	7.55
West Facing				
Gross EU1 ¹	40.81	37.3	3.51	8.6
Net EU1 ²	40.81	37.3	3.51	8.6
Notes 1. Gross EU1 is Energy Use Total (not including PV) / Total Building Area. 2. Net EU1 is Energy Use Total (including PV) / Total Building Area.				

Registration Number: 223-P0100628198-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance
Registration Date/Time: 2023-08-28 15:45:42
Report Version: 2022.0.000
Schema Version: rev 20220901
HERS Provider: CalCERTS inc.
Report Generated: 2023-08-28 14:07:35

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
Project Name: Walnut Creek ADUs (Plan 1)
Calculation Date/Time: 2023-08-28T14:06:19-07:00
Calculation Description: Title 24 Analysis
Input File Name: Walnut Creek ADUs (Plan 1).rbd22x
CFIR-PRF-01E
(Page 3 of 12)

ENERGY USE SUMMARY	Standard Design Source Energy (EDR1) (kBtu/ft ² - yr)	Standard Design TDV Energy (EDR2) (kTDV/ft ² - yr)	Proposed Design Source Energy (EDR1) (kBtu/ft ² - yr)	Proposed Design TDV Energy (EDR2) (kTDV/ft ² - yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	4.26	29.02	4.83	38.5	-0.63	-9.48
Space Cooling	1.79	44.68	1.33	40.21	0.46	4.47
IAQ Ventilation	0.51	5.48	0.51	5.48	0	0
Water Heating	5.45	56.99	3.5	38	1.95	18.99
Self Utilization/Flexibility Credit				0		0
North Facing Efficiency Compliance Total	12.01	136.17	10.23	122.19	1.78	13.98
Space Heating	4.26	29.02	4.83	37.86	-0.57	-8.84
Space Cooling	1.79	44.68	1.02	32.02	0.77	12.66
IAQ Ventilation	0.51	5.48	0.51	5.48	0	0
Water Heating	5.45	56.99	3.5	38.04	1.95	18.95
Self Utilization/Flexibility Credit				0		0
East Facing Efficiency Compliance Total	12.01	136.17	9.86	113.4	2.15	22.77

Registration Number: 223-P0100628198-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance
Registration Date/Time: 2023-08-28 15:45:42
Report Version: 2022.0.000
Schema Version: rev 20220901
HERS Provider: CalCERTS inc.
Report Generated: 2023-08-28 14:07:35

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
Project Name: Walnut Creek ADUs (Plan 1)
Calculation Date/Time: 2023-08-28T14:06:19-07:00
Calculation Description: Title 24 Analysis
Input File Name: Walnut Creek ADUs (Plan 1).rbd22x
CFIR-PRF-01E
(Page 6 of 12)

REQUIRED PV SYSTEMS											
01	02	03	04	05	06	07	08	09	10	11	12
DC System Size (kWdc)	Exception	Module Type	Array Type	Power Electronics	CFI	Asimuth (deg)	Tilt Input	Array Angle (deg)	Tilt: (x in 12)	Inverter Eff. (%)	Annual Solar Access (%)
0		Standard (14-17%)	Fixed	none	true	n/a	n/a	n/a	n/a	n/a	
REQUIRED SPECIAL FEATURES											
The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis. * PV exception 2: No PV required when minimum PV size (Section 150.1(c)(14) < 1.8 kWdc (0 kW) * Variable capacity heat pump compliance option (verification details from VCHP Staff report, Appendix B, and RA3) * Northwest Energy Efficiency Alliance (NEEA) rated heat pump water heater, specific brand/model, or equivalent, must be installed											
HERS FEATURE SUMMARY											
The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis. Additional detail is provided in the building tables below. Registered CF2Rs and CF3Rs are required to be completed in the HERS Registry. * Indoor air quality ventilation * Kitchen range hood * Verified Refrigerant Charge * Airflow in habitable rooms (SC1.1.4.1.7) * Verified heat pump rated heating capacity * Wall-mounted thermostat in zones greater than 150 ft2 (SC1.4.5) * Ductless indoor units located entirely in conditioned space (SC1.1.4.1.8)											
BUILDING - FEATURES INFORMATION											
01	02	03	04	05	06	07					
Project Name	Conditioned Floor Area (ft ²)	Number of Dwelling Units	Number of Bedrooms	Number of Zones	Number of Ventilation Cooling Systems	Number of Water Heating Systems					
Walnut Creek ADUs (Plan 1)	408	1	1	1	0	1					

Registration Number: 223-P0100628198-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance
Registration Date/Time: 2023-08-28 15:45:42
Report Version: 2022.0.000
Schema Version: rev 20220901
HERS Provider: CalCERTS inc.
Report Generated: 2023-08-28 14:07:35

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
Project Name: Walnut Creek ADUs (Plan 1)
Calculation Date/Time: 2023-08-28T14:06:19-07:00
Calculation Description: Title 24 Analysis
Input File Name: Walnut Creek ADUs (Plan 1).rbd22x
CFIR-PRF-01E
(Page 1 of 12)

GENERAL INFORMATION											
01	Project Name		Walnut Creek ADUs (Plan 1)								
02	Run Title		Title 24 Analysis								
03	Project Location										
04	City		Walnut Creek		05	Standards Version		2022			
06	Zip code				07	Software Version		EnergyPro 9.2			
08	Climate Zone		12		09	Front Orientation (deg/ Cardinal)		All orientations			
10	Building Type		Single family		11	Number of Dwelling Units		1			
12	Project Scope		Newly Constructed		13	Number of Bedrooms		1			
14	Addition Cond. Floor Area (ft ²)		0		15	Number of Stories		1			
16	Existing Cond. Floor Area (ft ²)		n/a		17	Penetration Average U-Factor		0.3			
18	Total Cond. Floor Area (ft ²)		408		19	Glazing Percentage (%)		18.14%			
20	ADU Bedroom Count		n/a		21	ADU Conditioned Floor Area		n/a			
22	Fuel Type		All electric		23	Occupancy U		No			
COMPLIANCE RESULTS											
01	Building Complies with Computer Performance										
02	This building incorporates features that require field testing and/or verification by a certified HERS rater under the supervision of a CEC-approved HERS provider.										
03	This building incorporates one or more Special Features shown below										

Registration Number: 223-P0100628198-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance
Registration Date/Time: 2023-08-28 15:45:42
Report Version: 2022.0.000
Schema Version: rev 20220901
HERS Provider: CalCERTS inc.
Report Generated: 2023-08-28 14:07:35

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
Project Name: Walnut Creek ADUs (Plan 1)
Calculation Date/Time: 2023-08-28T14:06:19-07:00
Calculation Description: Title 24 Analysis
Input File Name: Walnut Creek ADUs (Plan 1).rbd22x
CFIR-PRF-01E
(Page 4 of 12)

ENERGY USE SUMMARY	Standard Design Source Energy (EDR1) (kBtu/ft ² - yr)	Standard Design TDV Energy (EDR2) (kTDV/ft ² - yr)	Proposed Design Source Energy (EDR1) (kBtu/ft ² - yr)	Proposed Design TDV Energy (EDR2) (kTDV/ft ² - yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	4.26	29.02	4.8	37.3	-0.54	-8.28
Space Cooling	1.79	44.68	1.29	38.35	0.5	6.33
IAQ Ventilation	0.51	5.48	0.51	5.48	0	0
Water Heating	5.45	56.99	3.5	37.97	1.95	19.02
Self Utilization/Flexibility Credit				0		0
South Facing Efficiency Compliance Total	12.01	136.17	10.1	119.1	1.91	17.07
Space Heating	4.26	29.02	4.7	36.75	-0.44	-7.73
Space Cooling	1.79	44.68	1.11	34.5	0.68	10.18
IAQ Ventilation	0.51	5.48	0.51	5.48	0	0
Water Heating	5.45	56.99	3.5	38.01	1.95	18.98
Self Utilization/Flexibility Credit				0		0
West Facing Efficiency Compliance Total	12.01	136.17	9.82	114.74	2.19	21.43

Registration Number: 223-P0100628198-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance
Registration Date/Time: 2023-08-28 15:45:42
Report Version: 2022.0.000
Schema Version: rev 20220901
HERS Provider: CalCERTS inc.
Report Generated: 2023-08-28 14:07:35

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD
Project Name: Walnut Creek ADUs (Plan 1)
Calculation Date/Time: 2023-08-28T14:06:19-07:00
Calculation Description: Title 24 Analysis
Input File Name: Walnut Creek ADUs (Plan 1).rbd22x
CFIR-PRF-01E
(Page 7 of 12)

ZONE INFORMATION						
01	02	03	04	05	06	07
Zone Name	Zone Type	HVAC System Name	Zone Floor Area (ft ²)	Avg. Ceiling Height	Water Heating System 1	Status
Living Area	Conditioned	HVAC System1	408	8	DHW Sys 1	New
OPAQUE SURFACES						
01	02	03	04	05	06	07
Name	Zone	Construction	Asimuth	Orientation	Gross Area (ft ²)	Window and Door Area (ft ²)
Front Wall	Living Area	R21 Wall	0	Front	96	20
Left Wall	Living Area	R21 Wall	90	Left	272	18
Rear Wall	Living Area	R21 Wall	180	Back	96	4
Right Wall	Living Area	R21 Wall	270	Right	272	32
Roof	Living Area	R-38 Roof Atic.	n/a	n/a	408	n/a
ATTIC						
01	02	03	04	05	06	07
Name	Construction	Type	Roof Rise (x in 12)	Roof Reflectance	Roof Emittance	Radiant Barrier
Attic Living Area	Attic Roof/Living Area	Ventilated	4	0.1	0.85	Yes
FENESTRATION / GLAZING						
01	02	03	04	05	06	07
Name	Type	Surface	Orientation	Asimuth	Width (ft)	Height (ft)
Door 01	Window	Front Wall	Front	0	1	20
01	Window	Left Wall	Left	90	1	6
02	Window	Left Wall	Left	90	1	12

Registration Number: 223-P0100628198-000-000-0000000-0000
CA Building Energy Efficiency Standards - 2022 Residential Compliance
Registration Date/Time: 2023-08-28 15:45:42
Report Version: 2022.0.000
Schema Version: rev 20220901
HERS Provider: CalCERTS inc.
Report Generated: 2023-08-28 14:07:35



THESE PLANS ARE PROVIDED BY THE CITY OF WALNUT CREEK AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

WALNUT CREEK ADU
CITY OF WALNUT CREEK
ENERGY COMPLIANCE - PLAN 1

