

Quick guide: Virtual Worksite Marker Boards for Engineering Supervisors

Once you're trained on Virtual Worksite Marker Boards (VWSMB), use this guide alongside the Operations Manual for support

1

Prepare devices

- Ensure you have the correct amount of devices and suitable attachments - including spares
- Check devices are fit for use i.e. charged & undamaged



2

Geofence project checks - ES only tasks

- Log-in to the Tended Dashboard and confirm the project is approved for use
- Verify geofence(s) is accurate in line with the published limits in the briefing pack and WON



3

Assign devices and brief your team

- Assign Tended devices to the project via the Tended Dashboard with the correct asset types and nicknames that correspond to the OTP they'll be attached to
- Ensure VWSMB is included in the shift briefing



4

Start the works

- First, start the correct site via the Tended Dashboard once you are granted the worksite by the PICOP
- Check devices are turned on and reporting their location to the Dashboard before authorising site access



5

Monitor and complete the project

- Use the Dashboard's RAG view to monitor the OTP movements throughout the shift, make relevant calls if issues arise
- Start/Stop any applicable geofences if limits are changing
- Stop the site(s) when you are handing back to the PICOP



VWSMB Operation Manual

Scan here to view the up-to-date version of the operation manual. Find information on device checks, guidance for fitting and activating the equipment, and much more!

