




Wall Stacker

SPECIFICATIONS

Overall length, width, height	48.25 x 5.9 x 6.5ft
Min/Max frame height	6.5 - 12ft
Max frame length	20ft
Working height	19.75 - 78.75in
Safe working load	2200lb
Machine mass	7920lb
Operational noise	50db
Operating temperature	32 - 104°F
Electrical requirement	460V 25A 3Ph + 110V 10A 1Ph
Air requirement	0.706 CFM @ 87 psi

* Specifications & design are subject to change, please confirm details when placing your order.

OVERVIEW

The Wall Stacker provides automated lifting, moving and stacking of finished wall frame sections at the end of a frame line.

FEATURES

- Automated lifting and stacking of frames eliminates operator fatigue and lifting injuries
- Centering positioning – reversible drive to center the bundle as you stack
- Designed to handle 2200lb frames with ease
- Operator control station removed from lifting area
- Side chains to progress frame over the lifting device
- Stopper pins on infeed side of machine to prevent the next frame entering the lifting area
- Toothed safety mechanism on lifting ram
- UL Listed Industrial Control Panels



OPTIONS

- Can be made to match your existing outfeed height, common sizes vary from 18 - 40in
- Ideally setup with a Chain Conveyor on the infeed and a Wall Stacker Outfeed

