



OPTI CONTROL PANEL NOTES:

OPTI CERTIFIED HARDWARE

1. CONTACT OPTI SALES AT [HTTPS://OPTIRTC.COM/CONTACT/](https://optirtc.com/contact/) OR (844) 678-4782 EXT. 3 FOR OPTI CERTIFIED HARDWARE
 - 1.1. 22 IN. x 18 IN. x 10 IN. NEMA 4X CABINET WITH CELLULAR ANTENNA AND CHANNEL STRUT MOUNTING CLIPS
 - 1.2. UPS SYSTEM: 23 IN. X 20 IN. X 20 IN. NEMA 4X CABINET WITH MOUNTING BRACKETS
 - 1.3. POLYWATER FOAM DUCT SEALANT (SENT WITH OPTI CONTROL PANEL)

ALL OTHER HARDWARE AND EQUIPMENT

2. GALVANIZED STEEL CHANNEL STRUT TO BE MOUNTED TO WALL. CONTROL PANEL TO BE BOLTED TO CHANNEL STRUT (CHANNEL STRUT MOUNTING CLIP TO BE SHIPPED WITH CONTROL PANEL). PANEL TO BE MOUNTED MINIMUM 3 FT. FROM GROUND.
3. ALL CONDUIT PENETRATIONS ARE TO BE IP68 RATED AND SEALED WITH POLYWATER FOAM DUCT SEALANT. SEE ELECTRICAL DIAGRAM FOR CABLE AND CONDUIT SPECIFICATION.
 - 3.1. ALL RIGID AND FLEXIBLE CONDUIT TO BE PROCURED BY CONTRACTOR
4. ALL EQUIPMENT TO BE GROUNDED TO CONTROL PANEL GROUNDING LUGS. OPTI CONTROL PANEL TO BE GROUNDED TO A GROUNDING ROD, GALVANIZED STEEL POLE, OR CONCRETE-ENCASED GROUNDING ELECTRODE. (SEE ELECTRICAL DIAGRAM)

2

 1

V3 OPTI CONTROL PANEL DETAIL
LINE POWER WITH UPS (WALL MOUNTED)



OPTIRTC, INC.
 98 NORTH WASHINGTON ST.
 SUITE 210
 BOSTON, MA 02114
 (844) 678-4782

OPTI V3 CONTROL PANEL WALL MOUNTED (LINE POWERED)

NOT FOR CONSTRUCTION
 REFERENCE USE ONLY
 NOT TO SCALE
 © OPTIRTC, INC. 2026
 ALL RIGHTS RESERVED

REVISED: 04/14/2026

DRAWING NUMBER:
 OCP-2_V3