Hospital Systems

750 Garcia Ave, Pittsburg
CA 94565
+1.925.427.7800
HSIheadwalls.com

Slimline

Surface Mounted Patient Headwall

100% USA Manufactured

12 Year Product Warranty

All specifications are nominal and subject to change without notice. Hospital Systems, Inc. makes no warranty, expressed or implied, except for the express written warranty extended on the sale of its products.

SLIMLINE basic unit shall be manufactured by Hospital Systems, Inc., Pittsburg CA 94565 USA, in accordance with shop drawings and documents. The following is a general specification, and components listed may not be present or required in final product.

The SLIMLINE is listed by Underwriters Laboratories Inc. (UL) in Canada and the United States of America. This product also complies with the seismic requirements of, and is approved by, the State of California's Office of Statewide Health Planning and Development (OSPHD). HSI manufactures all products in accordance with the National Fire Protection Association (NFPA), NFPA-99 (current edition) and National Electric Code (NEC).

The installation contractor is responsible for compliance with all local, state, and federal codes applicable to the installation of medical gas and electrical systems.

1. Submittals and Approvals:

Job specific shop drawings shall be produced for each project. These shop drawings will clearly indicate the area of Medical Gas termination, and electrical connection points inside or outside the SLIMLINE. Drawings of Record will be produced, and emailed at the time of shipment, on request.

HSI will manufacture equipment as per signed approval drawings and verification documents, which are provided in the job specific submittal package.

2. Basic Construction

Enclosure shall be constructed of extruded, heat-treated, anodized aluminum alloy sections to provide a surface-mounted unit. Unit shall be factory assembled to include mechanical and electrical components as shown on the plans and specifications, and wired in accordance with HSI shop drawings. Anodized aluminum fascias shall be removable for access to individual components mounted within the SLIMLINE. Removable, Spectrum Duracore™ fire-retardant panels shall be finished with high-pressure plastic laminate on the outside face and a fire retardant

backing sheet on the reverse. The color of the laminate shall be selected by the hospital or architect from HSI standard colors. Device cover plates shall be constructed of clear anodized aluminum. Primary electrical conduit runs to the wall unit are provided by the electrical contractor and shall be accommodated by a terminal enclosure furnished as an integral part of the SLIMLINE. All secondary wiring within the SLIMLINE shall be fixed wiring, and terminate in the terminal enclosure. All wiring shall be marked, color-coded and tie wrapped to facilitate easy circuit identification.

3. Components

A. Electrical

WIRING

Wire for standard and critical branch power circuits shall be #12 AWG THHN stranded copper wire, 600 volt, with heat resistant thermoplastic insulation for hot (black) and neutral (white). Grounds shall be #10 AWG stranded copper wire (green). All ground conductors shall be installed in conduit.

INTERNAL GROUND BUS

A ground bus shall be included.

ELECTRICAL RECEPTACLES

Receptacles shall be the type and quantity as shown on the drawings and specified.

Unless otherwise noted 2 pole, 3 wire, rated at 20 amps, 120 Volt, Hospital Grade shall be provided. Also available: BS, DIN, and others.

- **Duplex receptacles** shall be NEMA style 5-15R or 5-20R, color Ivory for use on normal power circuits, and color Red for use on critical branch power circuits.
- **Simplex receptacles** shall be NEMA style 5-15R or 5-20R, color Ivory for use on normal power circuits, and color Red for use on critical branch power circuits.
- **Safety receptacles** (if required) shall be duplex type, be NEMA style 5-15R or 5-20R, color Ivory for use on normal power circuits, and color Red for use on critical branch power circuits. Receptacles shall limit proper access to energized contacts.

GROUNDING JACKS

Externally accessible grounding jacks shall be provided in the unit as shown in these shop drawings. The solid brass receptacle shall be enclosed in a non-conductive housing and shall be spring loaded, with a twist-to-lock action and shall be manufactured to the requirements of NEC article 517, and NFPA 99.

SWITCHING

Switches shall be Industrial Grade 120 or 277 volt, 15 or 20 amps. Switch type options

HSI Hospital Systems

750 Garcia Ave,
Pittsburg
CA 94565
+1.925.427.7800

c UL us LISTED

HSI Hospital Systems

750 Garcia Ave,
Pittsburg
CA 94565
+1.925.427.7800

include SPST, 3-Way or Momentary, and shall be provided as shown on submittal shop drawings. Low Voltage Switching will be 0-12 volts, 15 amps unless otherwise noted. HSI shall furnish, pre-install and wire all switches.

B. Med Gas

MEDICAL GAS PIPING

Oxygen, vacuum, medical air, evacuation, and nitrous oxide outlets shall be as indicated in plans and specifications. All outlets will be installed by HSI at the factory, manifolded and tested in accordance with NFPA 99c. All Medical Gas piping shall be Type L copper pipe. The mechanical contractor will bring the primary supply lines of the medical gases to the singular terminal connections at locations shown on the drawings.

C. Lighting (Optional)

AURORA™ LIGHTING FIXTURE

When indicated on the drawings, the overbed safety lighting fixture shall be provided. Lamps are provided by others.

AMADEA LIGHTING FIXTURE

When indicated on the drawings, the high end overbed lighting fixture shall be provided. Lamps are provided by others.

MULTI-FUNCTION CEILING LIGHT

When indicated on the drawings, a ceiling mounted multi-function lighting fixture shall be provided. Lamps are provided by others.

D. Provisions

NURSE CALL EQUIPMENT

All nurse call equipment shall be furnished and installed by others as indicated in the plans and specifications. A labeled pull-cord shall be provided by HSI for use by the nurse call installer.

MONITORING EQUIPMENT

Monitor equipment shall be provided and installed by others. HSI shall provide a matching blank plate for the monitor receptacle to the monitor supplier when requested. The Axiom wall unit will include a factory installed raceway and labeled pull cord to accommodate the monitor wiring. Where specified a monitor slide and optional pivot/tilt arm shall be provided to support the physiological monitor.

COMPUTER INTERCONNECT

A computer system furnished by others shall be installed at locations as shown on the plans and specifications. HSI shall provide a matching blank plate for the computer jack when requested. The unit will include a factory installed raceway and labeled pull cord to accommodate the computer system wiring.

c UL us LISTED

E. Accessory Rails

The SLIMLINE does not have integrated accessory rails. However, additional wall-mounted horizontal or vertical accessory rail/track may be included.

UNIMOUNT VERTICAL TRACK

Unimount™ Accessories shall be provided in the quantities and types as shown in the submittal. Unimount accessories shall be installed by others in the locations as determined by the end user group. Unimount accessories shall be attached using patented Unimount brackets. [Patent #4,725,030]

ECLIPSE HORIZONTAL RAIL

Eclipse™ Accessories shall be provided in the quantities and types as shown in the submittal. Eclipse accessories shall be installed by others in the locations as determined by the end user group. Eclipse accessories shall be attached using Eclipse brackets.

4. Installation

HSI shall provide rail mounting bracket. The installer shall mount the headwall units and make all primary medical gas and electrical connections. The installer or contractor shall make connection of building services to pre-wired terminal enclosure as shown on the electrical drawings and as herein specified. Customer shall coordinate with Hospital Systems, Inc for equipment supplied by others to ensure compatibility of this equipment with the headwall. The installer or contractor shall provide primary connections to the medical gas system in the access area of headwall unit as detailed on drawings. It shall be the responsibility of the mechanical contractor to perform and certify all pressure tests as required by NFPA 99c, and to install the gas outlet finishing assemblies. Please refer to the installation instructions for further details

5. Ordering Information

All HSI headwalls are Build-to-Order and will be assigned their own unique model numbers during the submittal phase.

Please visit our website at www.HSIheadwalls.com for the contact information of your local sales representative.

HSI Hospital Systems

750 Garcia Ave,
Pittsburg
CA 94565
+1.925.427.7800

c UL us LISTED