

MOBILE KITCHEN TRAILER RENTALS FOR TEMPORARY FOODSERVICE OPERATIONS

Purpose & Scope

This checklist applies to the temporary deployment of mobile commercial kitchen trailers in the State of Oregon for use during:

- Commercial kitchen renovations
- Emergency response or disaster recovery
- Seasonal or peak-demand foodservice operations
- Temporary continuity of operations for existing facilities

Typical users include hospitality businesses, senior living communities, healthcare facilities, universities, corporate campuses, and professional foodservice operators.

This checklist is not intended for permanent installations, street food vending, or independent food truck operations.





MOBILE™ CULINAIRE

Oregon Permit Requirements Checklist

Building & Temporary Use Permits

temporary trailers supporting existing permitted kitchens.

Purpose: Approve temporary placement of the mobile kitchen trailer on private property during renovation, emergency, or seasonal use.

Primary Stakeholders Involved:

- Client / Facility Operator
- General Contractor (if applicable)
- City or County Building Department

Checklist:	
☐ Temporary Structure or Temporary Use Permit issued by the city or county	
Approval for temporary placement duration	
Site plan submitted if required, showing:	
 Trailer location Access routes Utility connection points 	
Zoning confirmation for temporary use on private property	
Approval for long-term temporary parking if applicable	



Note: Requirements vary by municipality; some jurisdictions waive certain building permits for



MOBILE™ CULINAIRE

Oregon Permit Requirements Checklist

Health Department / Environmental Health Approvals

Purpose: Ensure food safety compliance for temporary foodservice operations supporting an existing facility.

Primary Stakeholders Involved:

- Client / Foodservice Operator
- County Environmental Health Department
- Mobile Culinaire (documentation support)

Checklist:

Checklist:	
Temporary foodservice approval or Mobile Food Unit authorization, as required by the county	
Menu submitted for review if required	
Kitchen layout and equipment list provided (from Mobile Culinaire)	
Potable water system meets Oregon food safety requirements	
Wastewater tank sized at least 15% larger than potable water tank	
Commissary agreement secured only if required by the county	
Pre-operational inspection scheduled and passed	
Ongoing health inspections approved	
All foodservice staff hold valid Oregon Food Handler Cards	
Note: Counties often evaluate mobile kitchen trailers used during renovations differently from public food trucks. Existing permitted facilities may receive modified requirements.	









Fire Department / Life Safety Approvals

Purpose: Verify fire safety, ventilation, fuel systems, and emergency controls.

Primary Stakeholders Involved:

- **Client / Facility Operator**
- **Fire Marshal / Fire Department**
- **Propane Provider or Gas Contractor (if applicable)**

Mobile Culinaire (system documentation)
Checklist:
Fire marshal review of the temporary kitchen installation
Fire suppression system inspected and certified
Type I ventilation hood approved
Class K fire extinguisher installed
Additional ABC extinguishers if required
Propane use permit obtained (if propane is used)
Propane tanks properly located, secured, and labeled
Generator inspected and approved if used
Emergency shut-offs clearly identified and accessible





MOBILE™ CULINAIRE

Oregon Permit Requirements Checklist

Utility & Infrastructure Approvals

Purpose: Ensure safe temporary connections to site utilities.

Primary Stakeholders Involved:

- Client / Facility Operator
- General Contractor
- Licensed Electrician
- Licensed Plumber
- Wastewater / Grease Disposal Provider
- Local Utility Providers

Checklist:
Approved fresh water supply connection method
Approved wastewater disposal method
Plumbing connection permit if required by jurisdiction
Electrical connection permit if connecting to site power
Licensed Oregon electrician used for electrical work
Backflow prevention installed if required
Grease and greywater servicing arranged with approved provider
☐ Temporary utility installations inspected as required









Final Pre-Opening Verification

Purpose: Confirm all approvals are in place before foodservice begins.

Primary Stakeholders Involved:

- Client / Facility Operator
- General Contractor (if applicable)
- Health Department
- Fire Marshal

Checklist:

All required permits issued and available on-site
Fire marshal approval completed
Health department approval completed
Utilities safely connected and operational
Commissary relationship documented if required
All equipment powered, tested, and temperature-verified
Staff trained on emergency procedures and equipment operation

Mobile kitchen trailer fully compliant and ready for operation







Key Oregon Regulatory References

- Oregon Health Authority Food Safety Program
 https://www.oregon.gov/oha/ph/healthyenvironments/foodsafety/pages/index.aspx
- County Environmental Health Departments
 https://www.oregon.gov/oha/ph/healthyenvironments/pages/index.aspx
- Oregon Building Codes Division
 https://www.oregon.gov/bcd
- Oregon State Fire Marshal / Oregon Fire Code
 https://www.oregon.gov/osfm



