

PARISH OF ASCENSION

BUILDING DEPARTMENT



SEQUENCE OF INSPECTIONS FOR NEW RESIDENCE ON PIERS

House Wrap (Brick)

House Wrap (Stucco)

House Wrap (Hardi/Vinyl)

House Wrap (All)

Temporary Meter

*THESE INSPECTIONS CAN BE
SCHEDULED AT ANY TIME DURING
THE CONSTRUCTION PROCESS.
HOUSE WRAP INSPECTIONS MUST BE
DONE BEFORE INSTALLING EXTERIOR
COVERINGS.*

1.) Foundation

****SLAB CAN BE POURED AT THIS POINT****

2.) Foundation on Piers (Inspection for Floor Framing and Anchoring)

3.) Plumbing Rough-in

4.) Plumbing Top-out (GAS IF APPLICABLE)

5.) Electrical Rough-In

6.) Mechanical Rough-In

*NO SPECIFIC ORDER FOR THESE
INSPECTIONS*

7.) Framing

****INSULATION AND INTERIOR WALL COVERINGS CAN BE INSTALLED AT THIS POINT****

8.) TCI (APPROVAL OF THIS INSPECTION WILL RELEASE PERMANENT POWER)

9.) Electrical Final

10.) Plumbing Final

11.) Mechanical Final

*NO SPECIFIC ORDER FOR THESE
INSPECTIONS*

12.) Building Final

13.) Certificate of Occupancy

****If any plumbing will be under the slab, please schedule a Plumbing Rough-In before the foundation inspection.**

*****TO SCHEDULE INSPECTIONS PLEASE CALL (225)450-1002*****