

- 1. Set door speeds, force, time delay and verify proper door operation prior to final connection of sensors system.**
- 2. Primary activation must be Knowing Act. If not then technician MUST WALK TEST to verify function and detection patterns comply with ANSI/BHMA A156.10 requirements.**
- 3. On Knowing Act applications, push/pull activation must be disabled.**

