

Addendum Number: 01  
Date of Issue: 03/30/2026  
Project Title: Klamath River Rural Broadband Initiative  
Project Number: 962  
Owner: Karuk Tribe

This addendum provides changes and/or clarifications, to the Contract Documents. These modifications pertain to the sections referenced below and to all other referenced or applicable sections in the Contract Documents and Plan Set. Each Item is presented in question/answer format.

Please sign the addendum receipt acknowledgment form and return, to the Owner, with your bid.

Responses to questions and/or clarifications to the bidding and contracting documents are as follows:

Clarifications / Modifications:

1. The proposed project is for Middle Mile installation only. The only connections for this project will be to the anchor institutions as shown in the project plans.
2. The Contractor will be required to obtain a Stormwater Pollution Prevention Plan (SWPPP) for the entire project. Plan will meet all requirements of Caltrans, County of Humboldt, and other property owners. Contractor will include all monitoring and reporting as required by the SWPPP.
3. Quantities shown in the Bid Schedule reflect actual quantities of the material to be installed, and not necessarily the length of the Segment. Quantities of conduit will be paid for by the linear foot for both the conduit to receive fiber and the empty conduit. Installation of overhead lines will be paid separately by the foot for the 144 strand and the 288 strand, even when installed on the same poles.
4. Bids must be received in person per the bid documents.
5. Schedule Modifications:
  - a. Work on Segment 4 will commence between March 1 and September 15.
  - b. Work Shall be completed on Segments 3 and 4 by April 30, 2028
  - c. Contract time to be adjusted to 680 calendar days
6. Project plans have been updated to show environmental constraints (see revised planset)
7. Attachments listed in the RFP (permits, plans, agreements, etc. are attached to the Bid Package file on the Builder's Exchange.

Questions:

1. Question: Are all of the permits approved for this work?

Response: All permits have been obtained at this time with the exception of two, which will be approved prior to the end of April (before start of construction).

Approvals for the remaining pole attachments will be completed by the end of June 2026.

2. Question: Would you please specify which make ready lists for PG&E, Verizon, and AT&T contractors must be qualified on?

Contractors shall be pre-approved for communications systems installation for these providers

3. Is slack line accounted for in the quantities?

No. Slack line shall be installed per industry standard, but is not included in the installed quantities listed in the Bid Schedule. All cable will be provided by the Owner.

4. Will a KMZ or excel file of the route be provided?

No electronic files will be provided other than the project plans and Bid Package

5. Would you add a unit for surveying, permitting billback costs?

No.

6. Upon eventual contract issuance, would you consider modifying the language found in sample contract document section 28.2 and omitting the portion referring to taking possession “of all materials, equipment, tools, construction equipment and machinery theron owned by the Contractor”?

Final contract can be modified prior to contract approval

7. Would you confirm the HDD/trench conduit footages for the Central Ave and Railroad Dr sections of Segment 5? On Sheet 5.119 the “Installation Description” calls out 1 – 2” conduit of HDD, but the “Legend” calls out 1 – 1.25” and 1 – 2” conduits. The trench unit for Central Ave and HDD unit for Railroad Dr only call out the 1.25” conduit size, but on Sheet 5.120 the drawings call out both 1 – 1.25” and 1 – 2” conduits.

Plan sheets revised to resolve. See revised plan sheets.

8. Will there be an allowance for extra costs for rock drilling?

Yes – A line item has been added to the Bid Schedule to allow for a per foot unit price for rock drilling. Payment will be for linear feet drilled rather than length of conduit installed. See revised Bid Schedule.

9. Is the contractor responsible for security?

Yes. Some areas of concern are known by utility companies to require security while working in the vicinity. This information will be conveyed to the contractor, and the contractor shall be responsible for notification prior to working at these locations.

Attachments:

Revised Planset  
Revised Bid Schedule  
Pre-Bid Meeting Agenda  
Pre-Bid Meeting Sign-In Sheet

Addendum Receipt Acknowledgement Form

Receipt of Acknowledgement:

My firm received Addendum No. 01, for the Klamath River Rural Broadband Initiative Project on Tuesday, March 31, 2026.

Name of Firm \_\_\_\_\_

Name (Print) \_\_\_\_\_

Name (Signature) \_\_\_\_\_

Date: \_\_\_\_\_

***Note: please submit this receipt of acknowledgement with your formal bid.***

**BID SCHEDULE**  
**KLAMATH RIVER RURAL BROADBAND INITIATIVE**  
**ORLEANS, CA TO MCKINLEYVILLE, CA**  
**KARUK TRIBE**

LINE ITEM	DESCRIPTION	QUANTITY	UNIT OF MEASURE	UNIT COST	TOTAL
1	Mobilization and Demobilization	1	LS		
2	Traffic Control system	1	LS		
3	Water Pollution control Program	1	LS		
<b>Segment 1</b>					
4	2" Conduit System Installation - HDD	59,320	LF		
5	1.25" Conduit System Installation - HDD	59,320	LF		
6	Conduit System Installation (1.25" & 2") -Trenching	60	LF		
6.1	HDD - Rock Drilling	3400	LF		
7	Handhold / Vault Installation	66	EA		
8	Trace Wire - Furnish and Installation	59,320	LF		
9	Fiber Optic Cable Installation - 144 Strand - UG	60,320	LF		
10	Fiber Optic Cable Installation - 288 Strand - UG	60,320	LF		
11	Fiber Optic Cable Installation - 144 Strand - Overhead	15,760	LF		
12	Fiber Optic Cable Installation - 288 Strand - Overhead	7,250	LF		
13	Bridge Hang - Aikens Creek (#04-0059)	1	LS		
14	Bridge Hang - Bluff Creek #1 (#04-0025)	1	LS		
15	Bridge Hang - Bluff Creek #2 (#04-0063)	1	LS		
16	Bridge Hang - Slate Creek (#04-0061)	1	LS		
17	Surface Restoration	3,450	SF		
<b>Segment 3</b>					
18	1.25" Conduit System Installation - HDD	179,560	LF		
19	Handhold / Vault Installation	44	EA		
20	Trace Wire - Furnish and Installation	89,780	LF		
21	Fiber Optic Cable Installation - 144 Strand	89,780	LF		
22	Surface Restoration	2,200	SF		
<b>Segment 4</b>					
23	1.25" Conduit System Installation - HDD	111,990	LF		
24	Conduit System Installation -Trenching	50	LF		
25	Handhold / Vault Installation	31	EA		
26	Trace Wire - Furnish and Installation	55,995	LF		
27	Fiber Optic Cable Installation - 144 Strand - UG	56,067	LF		
28	Fiber Optic Cable Installation - 144 Strand - OVERHEAD	6,472	LF		
29	Bridge Hang - Prarie Creek	1	LS		
30	Surface Restoration	1,640	SF		

LINE ITEM	DESCRIPTION	QUANTITY	UNIT OF MEASURE	UNIT COST	TOTAL
<b>Segment 5</b>					
	<u>Orick to Murray Road</u>				
31	2" Conduit System Installation - HDD	392	LF		
32	1.25" Conduit System Installation - HDD	392	LF		
33	Conduit System Installation (1.25" & 2") -Trenching	20	LF		
34	Handhold / Vault Installation	1	EA		
35	Trace Wire - Furnish and Installation	412	LF		
36	Fiber Optic Cable Installation - 144 Strand - UG	412	LF		
37	Fiber Optic Cable Installation - 288 Strand - UG	412	LF		
38	Fiber Optic Cable Installation - 144 Strand - Overhead	139,632	LF		
39	Fiber Optic Cable Installation - 288 Strand - Overhead	139,632	LF		
40	Surface Restoration	136	SF		
	<u>Murray Road</u>				
41	2" Conduit System Installation - HDD	20,220	LF		
42	1.25" Conduit System Installation - HDD	20,220	LF		
43	Handhold / Vault Installation	22	EA		
44	Trace Wire Furnish and Installation	20,220	LF		
45	Fiber Optic Cable Installation - 144 Strand - UG	20,220	LF		
46	Fiber Optic Cable Installation - 288 Strand - UG	20,220	LF		
47	Fiber Optic Cable Installation - 144 Strand - Overhead	3,137	LF		
48	Fiber Optic Cable Installation - 288 Strand - Overhead	3,137	LF		
49	Surface Restoration	872	SF		
	<u>Central Avenue</u>				
50	2" Conduit System Installation - HDD	192	LF		
51	1.25" Conduit System Installation - HDD	236	LF		
52	Conduit System Installation (1.25") -Trenching	15	LF		
53	Handhold / Vault Installation	2	EA		
54	Trace Wire Furnish and Installation	443	LF		
55	Fiber Optic Cable Installation - 144 Strand - UG	251	LF		
56	Fiber Optic Cable Installation -288 Strand - UG	192	LF		
57	Fiber Optic Cable Installation - 144 Strand - Overhead	3,420	LF		
58	Fiber Optic Cable Installation - 288 Strand - Overhead	1,910	LF		
59	Surface Restoration	188	SF		
	<u>Railroad Drive</u>				
60	1.25" Conduit System Installation - HDD	278	LF		
61	Conduit System Installation (1.25") -Trenching	12	LF		
62	Handhold / Vault Installation	2	EA		
63	Trace Wire Furnish and Installation	290	LF		
64	Fiber Optic Cable Installation - 144 Strand	290	LF		
65	Surface Restoration	156	SF		
66	TERO Tax (2%)	1	LS		

**BID TOTAL**

--

Respectfully Submitted:

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Title

\_\_\_\_\_  
License No.

SEAL - (if BID is by a corporation)

\_\_\_\_\_  
Address

\_\_\_\_\_  
Date

\_\_\_\_\_  
Expiration Date

**PRE-BID CONFERENCE AGENDA**

Project No.: 0962.0

Project Name: Klamath River Rural Broadband Initiative

Owner: Karuk Tribe (KT)

Date/Time: Wednesday, March 25, 2026 at 10:00 am PST

Location: Karuk Dept. of Natural Resources - Orleans & Site

---

**A. Introductions/Sign-in Sheet**

Project Management Team:

Owner: Karuk Tribe

Project Management: Enertribe

Project Engineer: Trinity Valley Consulting Engineers /  
Rapid Systems Engineering

Environmental Compliance: Ecocene

Tribal Monitors: Karuk Tribe

**B. Licensing Requirements**

1. Class A license is required of the prime/bidding Contractor.

**C. Construction Estimate**

1. \$13.7 million

**D. Alternates, allowances, and unit prices**

1. B. Bid Schedule

**E. Work and Services by others**

1. Subcontracting per Section 007200
2. Must provide list of Subcontractors and Major Suppliers per Section 004336 with Bid
3. Materials provided by Owner

**F. Indian Preference**

1. F. Statement of Qualifications
2. M. TERO

**G. Bid Addendum**

1. All requests submitted by Friday 04/03/2026
2. Addenda issuance Tuesday 04/07/2026

**H. Bid Opening**

1. Thursday 04/10/2026 @ 2:00 pm PST at KT Pithvuyraam Meeting Room located at 64236 Second Avenue, Happy Camp, CA 96039.

**I. Timeline**

1. Notice of Intent to Award: Wednesday 04/15/2026
2. 2 weeks to submit all required docs:
  - a) Bonding
  - b) Insurance
  - c) TERO permit
  - d) Wage Determination Schedule
  - e) Tentative Construction Schedule
  - f) Schedule of Amounts for Contract Payments
  - g) Company Safety Plan
3. Notice to Proceed: Friday 04/24/2026
4. 550 Calendar Day Contract
5. Start/Finish Dates to be established under the Notice to Proceed
  - a) Tentative start date: Monday 05/06/2026

- b) Tentative completion date: 12/31/2027
6. Liquidated Damages: \$1,500 per day
- J. Obtaining Bidding & Contracting Manuals and Plans**
1. Send request to [tvce@tvce.biz](mailto:tvce@tvce.biz)
  2. Humboldt Builders' Exchange
  3. Karuk Tribe Website
- K. Complete Bid (Minimum Requirements)**
1. 004000 Bid Form
  2. 004100 Bid Schedule
  3. 004300 Bid Security
  4. 004336 Subcontractor Schedule
  5. 004500 Bidder's Qualifications
  6. 004505 Indian Enterprise Qualifications Statement (if claimed)
  7. 004519 Non-Collusive Affidavit
  8. 005300 TERO 01 Form (ready to submit to TERO)
  9. 009100 Addenda Acknowledgement (if applicable)
- L. Bid Security**
1. No less than 5% of total Bid
- M. General Safety Requirements**
1. Personnel Protective Equipment (required)
  2. Traffic Control Plan
  3. Company Safety Plan (copy on file with Owner)
  4. Biweekly Tool Box Meeting (mandatory)
  5. Daily Safe Plan of Action Reports (reserved)
- N. Special Considerations**
1. Multiple agency / owner requirements.
  2. work time limits: 0700 – 1800
  3. Compliance with permit requirements
- O. Staging, Access, Parking, Use of facilities**
- Within Designated Right of Way
  - Controlled Access Through Green Diamond
- P. Clean up, Protection of Site, and Environmental Considerations**
1. Temporary Protection, Barricades, Gates, Staging areas
  2. Ingress / Egress to site
  3. Air Quality (Odor, Noise, Dust Control)
  4. Keep paved roads clean – broom/mechanical sweeping daily
  5. Solid Waste Management and Removal weekly
- Q. Insurance**
1. 007200 General Conditions, Section 16
    - a) General Public Liability & Property Damage - \$1 Million minimum
    - b) Workers' Compensation
    - c) Auto Liability - \$1 Million minimum
- R. Prevailing Wage**
1. California State Prevailing Wages
- S. Project Description and Scope of Work**
1. Section B: Bid Schedule
  2. Section 011000: Summary of Work
- T. Questions / Site Tour – Orleans to McKinleyville**

Karuk Tribe  
 64236 Second Avenue  
 Happy Camp, CA 96039  
 530.493.5257

PREBID CONFERENCE  
 KLAMATH RIVER RURAL  
 BROADBAND INITIATIVE PROJECT

3/25/2026  
 10:00 AMPST

POINT OF CONTACT COMPANY	ADDRESS	TELEPHONE EMAIL
Josh McKnight Trinity Valley Consulting Engineers	67 Walnut Way Willow Creek, CA 95573	530.629.3000 <a href="mailto:josh@tvce.biz">josh@tvce.biz</a>
Josh Stewart Utilities One	Vochees NJ	916-873-5190 <a href="mailto:JoshS@utilitiesone.com">JoshS@utilitiesone.com</a>
Trish Parry Utilities One		530-598-4935 <a href="mailto:trishp@utilitiesone.com">trishp@utilitiesone.com</a>
Jesus Loreto Glass Roots Construction	Nor Cal	818 489 9625 <a href="mailto:jloreto@glassrootsconstruction.com">jloreto@glassrootsconstruction.com</a>
Randy Hawks Glass Roots Construction	Utah	435-841-2169 <a href="mailto:RHawks@glassrootsconstruction.com">RHawks@glassrootsconstruction.com</a>
RAY THOMASON	SAINT FRANCIS Electric, CA	510-750-8256 <a href="mailto:rthomason@sfe-inc.com">rthomason@sfe-inc.com</a>
Tom Gallup	SN N	707 236-0400
Shawn Reyes Josiah Kuersten	H.P. Communications, Inc. HP Communications, Inc.	951 382 2719 (951) 667 9451 <a href="mailto:josiah.kuersten@hpcomminc.com">josiah.kuersten@hpcomminc.com</a>
Brian Redding	MERIK B.Redding @ pgns.us	(530) 784 3636 (707) 617-0965
Dylan Duan	Lava remedial services	606 548 8901
Kory Wright	Lava remedial services	812-697-4738
Kristen King Karuk Tribe	Orleans, CA	530 691 2203
Penny Eckert	Orleans, CA	425 241-0415
Greg Hyfford Wahlund Construction, Inc	690 Indiana Rd Eureka, CA 95503	Bids@wahlund.com 707-268-0150