
CONTENTS

	Pages
ABBREVIATIONS, ACRONYMS AND UNITS OF MEASUREMENT.....	8
ADVERTISERS' INDEX	9
INTRODUCTION.....	11
ESTIMATING	
• BUILDING COSTS PER SQUARE METRE	13-23
• ELEMENTAL COSTS OF BUILDINGS	25-42
• COMPARATIVE COSTS	43-65
DETAILED PRICES	
• Preliminaries.....	69-94
• Demolitions and Alterations	95-99
• Earthworks	100-103
• External Works.....	104-109
• Concrete Work	110-119
• Brickwork and Blockwork.....	120-130
• Masonry	131-133
• Structural Steelwork.....	134-136
• Metalwork.....	137-146
• Carpentry	147-169
• Joinery	170-176
• Windows and Doors.....	177-187
• Hardware and Door Sundries.....	188-190
• Roofing and Roof Plumbing	191-201
• Partitions	202
• Plastering	203-206
• Suspended Ceilings	207
• Pavior and Terrazzo	208-209
• Tiling, Non-Resilient	210-211
• Resilient Finishes.....	212-215
• Glazing	216-218
• Painting	219-222
• Sanitary Plumbing	223-237
• Drainage.....	238-243
• Electrical Services	244-259
• Mechanical Services	260-263
• Transportation Systems	264
• Miscellaneous.....	265-268
• Wage Rates	269
• Plant Hire Rates.....	270-272
RENOVATIONS.....	273-278
LABOUR CONSTANTS.....	279-288
BUILDING INDICES	289
• Price	291
• Regional	292-304
MEASUREMENT OF BUILDING AREAS	305-306
PROPERTY INSURANCE.....	307
INDEX	309-330

INDEX

A

- Access
 - covers, gratings, 139
 - flooring, 137
 - ladder, 141
 - panels (duct), 140
- Accessories, toilet, 144-146
- Accordion door, 185
- Acid, etc.h finish, 113
- Acoustic ceiling tiles
 - metal, 61, 207
 - plaster, 61, 207
- Acratex applications, 204
- Acrow prop hire, 270
- Acrylic
 - baked paint finish, 137
 - bath, 223
 - glaze, 222
 - latex, 58, 61, 220
 - liquid roofing, 194
 - paint, 58, 219, 220
 - paving treatment, 104
 - self-levelling topping, 208
 - sheet glazing, 217
 - shower base, 224
 - spa bath, 225
 - water based glaze, 222
- Administrative buildings, 14
- Aerated concrete
 - blocks, 53
 - panels
 - cladding, 119
 - floor, 119
 - wall, 119
- Aged persons homes, 23
- Agricultural
 - buildings, 14, 15
- Air
 - bricks, 124
 - compressor, hire, 270
 - conditioning
 - cost per square metre, 260
 - diffusion equipment, 263
 - domestic ducted, 260
 - ductwork, 262
 - insulated, 262
 - evaporative systems, 260
 - registers, 263
 - room air-conditioners, 260
 - diffusion equipment, 263
 - hoses, hire, 270
 - relief grilles, 138
 - thrust floors, 164
 - tools, hire, 270
- Alarm
 - smoke, 257
 - systems, security, 251
- Alkyd enamel, 58, 219, 220
- Alterations, etc.
 - cleaning, 99
 - kitchen, bathroom and similar type work,
 - refer RENOVATIONS, 273-278
 - openings, 98
 - preparatory work, repairs, 98
 - ceilings, 98
 - floors, 98
 - walls, 98
 - protection, 99
 - temporary screens, 99
 - work in connection with plumbing, 99
- Aluminium
 - air relief grilles, 138
 - angle trim, 138
 - balustrade, 143
 - concertina corrugated foil, 160
 - cored dpc, 129
 - curtain
 - track, 187
 - walling, 178
 - doors, 184, 185
 - downpipes, 197, 198
 - ducted skirting, 252
 - ducting, 262, 263
 - flashings, 197
 - foil insulation, 51, 160, 161
 - closed cell, 160
 - corrugated, 160, 161
 - glazed
 - doors, 184
 - screens, 179
 - gutters, 198, 199
 - handrails, 143, 144
 - insect screens, 180
 - insulation
 - foil, 51, 160, 161
 - reflective closed cell, 160
 - louvred
 - panels, 179
 - windows, 180
 - louvres, sunscreen, 187
 - matwell surround, 141
 - patent glazing, 179
 - rainwater goods, 198
 - reflective air cell insulation, 160
 - roofing, 192
 - sarking, 160
 - security door, domestic, 56
 - sheet cladding, 142
 - shop fronts, 179
 - skirting duct, 252
 - slip joint, 128
 - strip, suspended ceilings, 61, 207
 - sunscreens, 187
 - suspended ceilings, 207
 - tread nosing, 215
 - trim, 138
 - venetian blinds, 186
 - wall cladding, ribbed, 200
 - windows, etc., 177, 178
- American shingles, 195
- Anchor
 - base for post, 169
 - fixing to concrete, 136
 - masonry, 169
 - sleeve type, 136
 - stud type, 136
- Angle
 - guards, 138
 - trim, 138
- Annealed glass, refer Clear Float Glass, 216
- Anodising
 - metalwork, 137
 - windows, 177
- Ant capping, 124
- Antenna
 - cable, 256
 - television, 251

Anti

- slip treatment, 211
- termite control, 103
- Anticon, 161
- Anvil Top 3000, 113
- Apex tile, 191
- Aquapel, 111
- Arches, brick, 124
- Architraves, 181
- Area lighting, 249
- Areas, measurement of building areas, 305, 306
- Artificial surfaces, finishes, 109
- Asbestos
 - removal
 - ceiling linings, 96
 - roofing, 96
- Ashford formula surface hardener, 112
- Asphalt
 - bituminous concrete paving, 104
 - impregnated roofing, 193
- Awnings, canvas, 187

B

- Baby change station, 146
- Backfilling
 - drainage, trenches, 238
 - excavations, 102
- Bagged finish, 123
- Baked finishes, metalwork
 - acrylic, 137
 - enamel, 137
- Balconies, 22
- Ball catch, cupboard, 189
- Balustrade
 - aluminium, 143
 - glazed, 143
 - Monowills, 143
 - steel, 143
 - timber, 172
- Bank
 - building, 15
 - fit-out, 15
- Bar
 - reinforcement, 116
 - place and fix, 110
 - supply only, 110
 - sink, 225
- Barbed tape, 106
- Barge
 - board, 160
 - capping, 192, 193
- Bark chips, 108
- Barrel bolt, 189
- Barricade etc. fees (Sydney), 92
- Barrier
 - log, 108
 - site, polyethylene, 70
- Barrow
 - hire, 271
 - hoist, 69
- Base course, paving, 104
- Basement excavation, 101
- Base plate, 135

- Basin
 - combination set, 228
 - mixer, 228
- Bath, 223
 - combination set, 228
 - sauna, 266
 - shower, 225
 - spa, 225
- Bathroom
 - combined radiant heater, fan, light, 249
 - exhaust fan, light, 250
 - fit-out, 21
- Battens, 155, 159
 - shelf, 173
- Battery charger, hire, 271
- Beads
 - casing, 205
 - corner, 205
 - glazing, 182
 - stopping, 205
- Beams
 - concrete
 - attached
 - all-up, 46
 - concrete, 110
 - formwork, 114
 - foundation
 - all-up, 46
 - concrete, 110
 - precast, 118
 - laminated timber, 156, 157
 - steel, 134
 - timber, 150, 152, 153
- Bearers
 - floor framing
 - steel, 158
 - timber, 150, 153
- Bed
 - mortar, 104
 - sand, , 102
- Belling bored piers, 102
- Belt conveyor, hire, 271
- Bench
 - tops, 173
- Bib Tap, 228
- Bidette
 - electronic, 223
 - manual, 223
- Biflex barrier treatment, 103
- Bin
 - disposal, toilet, 146
 - to suit garbage compactor, 266
- Bitumat
 - Bituseal, 195
 - Polyflame, 193
 - Synroof, 194
 - Torchseal, 194
- Bitumen
 - impregnated
 - fibreboard strip, 112
 - paint, , 103
 - paving
 - base course, 104
 - break up, 100
 - sprayed surfacing, 104
 - spray, hire, 271
 - tanking, 103
 - waterproofing, , 103
- Bituminous
 - concrete, 104
 - felt
 - damp proof course, 129
 - roofing, 193
 - tanking, 103, 194
 - waterproofing, , 103
 - paint
 - tanking, 103
 - waterproofing, , 103
 - tanking, 103
 - waterproofing, 103
- Blinds
 - blocking, 150
 - free hanging, 186
 - roller, 186
 - roof window, 196
 - venetian, 186
 - integral, 178
 - Verosol, 186
 - vertical, 186
- Blocking, 150
- Blocks, blockwork
 - blocks, concrete
 - plain face, 50, 51, 54, 126
 - split face, 126
 - cavities, 127
 - composite prices, 53
 - coping, 127
 - core filling, 110, 127
 - cutting, 127
 - damp proof courses, 129
 - finishes, 127
 - glass blocks, 129
 - joints, 127, 128
 - labours, 127
 - laying cost, 121
 - lintels, 127
 - parapet walls, 49
 - paving, 104
 - pointing and cleaning, 127
 - reinforcement, 129
 - retaining walls, 107
 - screen walls, 107
 - sealants, 127, 128
 - solid top course, 127
 - splitter, hire, 270
 - walls, 50, 51, 54, 126
- Blue metal
 - base course, 104
 - chips, 108
- Bluestone
 - facing, 133
 - paving, 133
- Boarded formwork, 115
- Boiling water unit, 228
- Bollards, 105
 - lighting, 246
- Bolts
 - barrel, 189
 - carpentry, 168, 169
 - cutter, hire, 271
 - flush, 189
 - holding down, 136
 - indicator, 189
 - panic, 189
 - patio, 188
 - purlin, 136
 - skeleton, 189
 - steelwork, 136
 - strap, 189
- Bond breaker, 112
- Bondek, 115
- Bonding agent, 203
- Bored piers, 102
- Bowling green, 19
- Box
 - drain, 105
 - gutters, various, 199
 - hose tap, 140
 - stop cock, 140
- Bracing
 - steel, 134
 - wall framing, 151, 158
- Brackets
 - raiser, 245
 - shelving, 173
- Brass
 - cocks and valves, 230
 - division strips, 209
 - hinges, 188
 - matwell surround, 141
 - waste and grating, 231
 - weather bars, 209
- Breaker, hire, 270
- Bricks, brickwork
 - air bricks, 124
 - ant capping, 124
 - arches, 124
 - bagged finish, 123
 - break up and remove, 100
 - building up existing openings, 123
 - cavities, 123
 - chasing, 123
 - circular walling, 123
 - clay, 50, 53, 54, 120, 122
 - cleaning down, 99, 127
 - common
 - clay, 50, 53, 54, 120, 122
 - concrete masonry, 50, 120, 122
 - composite costs, 53, 54
 - concrete masonry, 53, 120, 122
 - copings, 125
 - corbelling, 124
 - cramps, 125
 - cutting
 - generally, 123
 - holes for pipes, 99
 - openings, 98
 - damp proof courses, 129
 - demolition, 95
 - facings, 50, 53, 54, 120
 - fair face, 53, 54, 123
 - finishes, 123
 - joints and sealants, 127, 128
 - labours, 123, 124
 - laying cost, 121
 - lintels, 124
 - load bearing, 122
 - manhole, 242
 - maxibrick, 122
 - modular, 50, 54, 120, 122
 - mortar, 121
 - oversailing, 124
 - parapet walls, 49
 - paving, 104
 - piers, 46, 122
 - pit, 242
 - pointing reverse face, 123

Bricks, brickwork (cont'd)
 projections, 124
 rake out joints and hack face, 98
 recesses, 124
 reinforcement, 129
 retaining walls, 107
 saw, hire, 270
 screen walls, 107
 sealants, 127, 128
 setting back/forward, 124
 sills, 125
 splitter, hire, 270
 sump, 242
 supply cost, 120, 121
 ties, 125
 toothing and bonding, 123
 walls, 50, 53, 54, 122, 123, 130
BRICKWORK AND BLOCKWORK, 120-130
 base prices, 120, 121, 122
 blockwork, 126
 labours, etc., 127
 brickwork, 122
 labours, etc., 123, 124
 sundries, 124, 125
 damp proof courses, 129
 glass block panels, 129
 joints and sealants, 127, 128
 laying rates, 121
 monolithic stabilised rammed earth
 walls, 130
 protective treatments, 130
 reinforcement, 129
 silicone solution, 130
 Bridging member, 135
 Brightonlite cement, 111
 Brisbane city council, fees, 78-82
 Broomed finish, 113
 Brush fence, 105
Building
 areas, measurement, 305, 306
 Control Commission (Melbourne) fees, 85
 fees
 Adelaide, 75-77
 Brisbane, 78-82
 Hobart, 82, 83, 84
 Melbourne, 85-87
 Perth, 88-90
 Sydney, 91-93
 paper, 103
BUILDING COSTS PER SQUARE METRE
 refer ESTIMATING BUILDING COSTS
 PER SQUARE METRE, 14
BUILDING INDICES
 anticipated, 2024, 291
 building price index
 all cities, 291
 regional indices, 292-304
 New South Wales, 292, 293
 Northern Territory, 304
 Queensland, 294, 295
 South Australia, 296, 297
 Tasmania, 302, 303
 Victoria, 298, 299
 Western Australia, 300, 301
 Built-up roofing, 193, 194
 finishes, protection, 194
 insulation, 194
 Bulkheads, 207

Bulking factors, excavation, 100
 Bumper and hook, 190
 Bush hammer, 113
 Butt hinges, 188

C

 Cabinets, paper towel, waste, 145
 Cabinetwork, 173-176
 Cabin hook, 190
Cable
 carriers
 conduit, 254
 skirting duct, 252
 duct, 252
 management floor system, 137
 pits, 254
 tray, 252
 troughing, 252
Cables
 consumer mains, 245
 copper, 254, 255
 data, 256
 high fire resistant, 256
 overhead aerial, 254
 telephone, 256
 television, 256
 Caltite, 111
 Caneite sheeting, 164
 Canvas awnings, 187
 Cap plate, 135
Car
 park lighting pole, 246
 track, 104
 Caravan parks, 19, 20
 Carborundum grains, 208
Carpentry
 connectors, 169
 fixings, 169
 framing, 150, 151, 153
 material supply cost, 147-149
CARPENTRY, 147-169
 barges, 160
 base material prices, 147-149
 battens, 155, 159
 beams, 150, 152, 153
 fascias, 160
 fixings, 168, 169
 flooring, 162-164
 framing
 ceiling, 151, 154
 eaves, 155
 floor, 150, 153, 158
 pergola, 155
 roof, 151, 155
 wall, 150, 151, 153, 154, 158
 grounds, 159
 insulation, 160, 161
 laminated beams, 156, 157
 linings
 ceiling, 168
 eaves, 168
 wall, 164-168
 posts, 152
 roof trusses, 155

Carpet, 59, 212
 cleaning, 99, 212
 modular, 212
 underlays, 212
 Carports, 23
 Cartage, excavated materials, 101
Casement
 fasteners, 189
 friction stay, 189
 spring catch, 189
 Casing bead, 205
 Casing to structural steel, 111
 Cast-in sundries, 113
Cast iron
 covers and gratings, 139, 140
 sewer drains, 238
 soil waste vent pipe, 231-233
 tree grille, 108
 Catches and fasteners, 189
 Caulk and seal, 127, 128
Cavity
 close, 123
 filing, mortar, 123
 form, 123, 127
 ties, 125
CCTV, 251
Ceiling
 fan, 250
 circuit connection, 247
 finishes, applied
 painting, 62
 plaster, 61, 205
 render, 203
 sprayed vermiculite, 61, 205
 framing, timber, 151, 154
 heating, 250
 joists, timber, 151, 154
 linings, 168
 fibre cement, 61, 162, 164, 165, 168
 plasterboard, 61, 205
 timber, 165-167
 preparatory work, repairs, 98
 suspended, 61, 207
 take down, 96
Ceiling Finishes, Estimating - Comparative
 Costs, 61
 on concrete soffit, 61
 on framed soffit, 61
 painting, 61
 suspended ceilings, 61
Cement
 based paving, granolithic, 208
 mortar, 121
 render, 57, 203
 hack off, 96
 Cementitious liquid underlay, 208
 Cements, concrete, 111
Ceramic
 fittings, 210
 sill, 125
 tiles, 57, 210
 cleaning, 99
 fittings, 210
 sill, 125

- Chain
 - block, hire, 271
 - saw, hire, 270
 - wire
 - mesh fence, 106
 - partitions, 138
 - screens, 202
 - site fence, 70
- Chair, office, 267
 - stack type, 267
- Change rooms, 18
- Channel, drainage, 241
- Chapel, 20
- Chase brickwork, 99, 123
- Check valve, 230
- Chemical
 - pan toilet, 71
 - waterstop, 112
- Cherry pickers, 70
- Child care centre, 15
- Chromium plated piping, 234
- Church, 20
 - hall, 20
- Chute, refuse disposal, 266
- Circuitry
 - light point, 246
 - power point, 246, 247
- Circular brick walling, 123
- Cisterns, 224
 - cock, 230
- Civic
 - buildings, 14
 - centre, 14
- Cladding
 - aerated concrete panels, 119
 - aluminium, 200
 - blockwork, 50, 51, 126
 - bluestone, 133
 - brickwork, 50, 122
 - curtain walling, 178
 - external insulated, 142
 - fibre cement, 51, 164, 165
 - fibreglass, 200
 - granite, 131
 - hardboard, 166
 - limestone, 131
 - marble, 132
 - perforated metal, 142
 - sandstone, 131
 - sheet metal, 142
 - shop fronts, 179
 - slate, 132
 - steel, 51, 200
 - timber, 51, 165, 166, 167
- Cleaning
 - brick, masonry, 99
 - carpets, 99, 212
 - ceramic tiles, 99
 - ducted vacuum system, 266
 - face brickwork, 123
 - waste disposal, 266
 - windows, 99
- Cleansers, hand, 145
- Clear
 - finish, 219
 - float glass, 216
 - site, 100
- Closed circuit television, 251
- Closers, door, 189
- Clothes
 - hoist, 139
 - line, 139
- Club
 - house, 18
 - premises, 16
- Coachscrew, 169
- Coat
 - hooks, 190
 - rails, 171
- Cocks and valves, 230
- Coir mat, 141
- Colour
 - additive, granolithic, 208
 - coating, metal roofing, 192
- Column
 - concrete
 - all-up, 46
 - concrete, 110
 - formwork, 114-116
 - foundations
 - all-up, 45
 - concrete, 110
 - formwork, 114
 - heater, 249
 - in situ, all-up, 46
 - mounted luminaires, 248
 - precast, 118
 - steel, 134
 - timber post, 46
- Columns, Upper Floors, Estimating
 - Comparative
 - brick piers, 46
 - costs, 46
 - reinforced in situ concrete, 46
 - timber, 46
- Combustion heater, 261
- Common brickwork, 50, 53, 54, 122
 - labours, etc., 123, 124
- Community recreation centre, 18
- Compaction, 102
 - equipment hire, 270
- Compactors, garbage, 266
- COMPARATIVE COSTS, ESTIMATING, 44-65
- Compressors, air, hire, 270
- Computation fee, refer Notices and Fees, 75-93
- Computer
 - flooring, refer Access Flooring, 137
- Concertina/corrugated foil insulation, 160, 161
- Concrete
 - acid etc.h, 113
 - aerated
 - blocks, 53
 - panels
 - cladding, 119
 - floor, 119
 - wall, 119
 - base price, 110
 - beams, 46, 118
 - blinding layer, 110
 - blocks, refer Blocks, blockwork, 126
 - bored piers, 102
 - box drain, 105
 - break up and remove, 100
- Concrete (cont'd)
 - bricks, 50, 120, 122
 - broomed finish, 113
 - bush hammer, 113
 - cartage, additional, 110
 - car track, 104
 - casings to structural steel, 111
 - cast-in sundries, 113
 - cements, 111
 - column foundations, 45
 - columns, 46, 118
 - construction joints, 112
 - core filling, 127
 - curing, 112
 - cutting, 95, 113, 114
 - demolition, 95
 - drilling, 113
 - edging strip, 105
 - expansion joints, 112
 - exposed aggregate finish, 118
 - filling
 - cores, 110
 - lintel blocks, 110
 - piers, 110
 - finishes, 113
 - floors, prepare for new, 96
 - footings, 45
 - footpath, 104
 - foundation beams, 45
 - foundations, 45
 - grading, 113
 - grinder, hire, 270
 - grinding surface, 98
 - ground slab, 45
 - hack for key, 98
 - hardeners, 113
 - kerbs
 - extruded, 105
 - in situ, 105
 - landings, 110
 - micro reinforcing system, 111, 117
 - monolithic finish, 113
 - parapet wall, 49
 - paving
 - in situ, 104
 - precast, 104
 - pier foundation, 46
 - pipe
 - sewer drains, 239
 - surrounds, 242
 - pit, 242, 243
 - pneumatically placing, 111
 - power float monolithic finish, 113
 - precast
 - aerated panels, 119
 - flooring
 - beam and infill system, 118
 - hollow core, 118
 - in situ, 104
 - manhole, 242
 - soakwells, 242
 - sumps, pits, 242, 243
 - tilt-up panels, 118, 119
 - walling, 117
 - pretensioned hollow units, 118
 - pumping, 111
 - raft slab, 45
 - retaining walls, 107

Concrete (cont'd)
 roof tiles, 191
 samples and testing, 111
 sand blast finish, 113
 saw, hire, 270
 sawing
 slab, 114
 wall, 114
 sealer, 113
 separation strips, 112
 slabs
 on fill, 45
 suspended, 46
 sprayed, pneumatically placed, 111
 staircases, 47
 steel trowel finish, 113
 strengths, 111
 strip footings, 45
 sump, 242, 243
 sundries, cast-in, 113
 supply cost, 110
 surface
 finishes, 110
 architectural, 113
 hardeners, 113
 suspended slabs, 46
 testing, 111
 tilt-up panels, 118
 walls
 general, 50, 53
 retaining, 107
 waterproofing, 113
 agents, 111
 waterstops, 112
 water, wash finish, 113
 wood float finish, 113
CONCRETE WORK, 110-119
 base prices, 110
 concrete, 110, 111
 cutting and drilling, 113, 114
 finishes, 113
 labours and sundries, 112, 113
 formwork, 114-116
 precast
 aerated concrete, 119
 concrete, 117, 118
 reinforcement, 110, 116, 117
 tilt-up panels, 118, 119
 Condek, 115
 Conduit
 telephone, pre-conduiting, 250
 UPVC
 HD, 252, 253
 flexible corrugated, 252, 253
 MD, 252, 253
 flexible corrugated, 252, 253
 Connections, plate steel, 135
 Connectors, timber, 169
 Constants, labour, refer Labour and Plant
 Constants, 280-288
 Construction
 joints, 112
 safety fee, refer Notices and Fees, 75-94
 Consumer mains, 245
 Contract works insurance, 73
 public liability, 74

Control
 joint, brickwork, 127
 systems, 251
 unit, security, 251
 Convection heater, 261
 Conveyor, hire, 271
 Cooking
 equipment, domestic, 265
 plate, 265
 top, 265
 circuit, 247
 Cooling units, evaporative, 261
 Cool rooms, 266
 Copings
 block, 127
 brick, 125
 sandstone, 131
 Copper
 cable, 254, 255
 downpipes, 197, 198
 flashings, 197
 gutters, 198, 199
 piping and fittings
 chromium plated, 234
 soil, waste, vent, 231, 232
 water, 234
 rainwater goods, 197-199
 roofing system, 192
 strip, slip joint, 128
 sump outlet, 200
 traps, 231
 Corbelling, 124
 Core filling, blocks, 127
 Cork
 self expanding separation strip, 112
 tiles, 59, 214
 Corner
 beads, 205
 guard
 stainless steel, 138
 steel, 138
 Cornice
 plasterboard, 205
 Corrugated
 foil insulation, 160, 161
 roofing
 fibreglass, 192
 polycarbonate, 192
 steel, 192, 193
 walling
 fibreglass, 200
 steel, 200
 Cover moulds, 171
 Covers and gratings
 cast iron, 139, 140
 ductile iron, 139
 galvanised steel, 139
 precast, 243
 Cramps, hoop iron, 125
 Cranes, mobile, 69
 Crash rails, 140
 Crushed
 recycled aggregate, 102
 rock
 backfilling drainage trenches, 238
 basecourse, 104
 filling, 45, 102

Cupboard
 catch, 189
 kitchen, 175
 linen, 175, 176
 lock, 188
 residential, 174, 175
 track, 190
 under bench, 173
 wall, 175
 Cup head bolt, 168
 Curing, 112
 Curtain
 rail, shower, 144
 track, 186, 187
 walling, 178
 Curtains, 186, 187
 track, 187
 Cut and fill, balanced, 101
 Cutting
 blockwork, 127
 brickwork, 123
 chases, 99, 123
 concrete, 95, 114
 formwork, 115
 hole for pipes, 99
 openings, 98
 toothings and bonding, 123
 trees, 100
 turf, 100
 Cyclone resistant glass, 216
 Cylinder mortice lock, 188
 Cylindrical latch, lock, 188

D

Damp proof
 courses, 129
 plastic membranes, 103
 Deadbolt, 188
 Deadlock, 188
 Debris removal, 97, 98
 Decking
 pencil rounded, 163
 reeded, 163
 Deflection register, 263
 Dehumidifier, hire, 270
 Dektite flashing, 195
 Demolish
 concrete, 95
 external brick walls, 95
 internal walls, various, 96
 partial demolitions, 95-98
 whole structures, 95
DEMOLITIONS AND ALTERATIONS, 95-99
 alterations
 ceilings, 98
 cleaning, 99
 floors, 98
 openings, 98
 preparatory work, repairs, 98
 protection, 99
 temporary screens, 99
 walls, 98
 work in connection with plumbing, 99
 demolitions
 partial, 95-98
 whole structures, 95-99

Demolition saw, hire, 270
 Demountable partitions, 202
 Denso tape, 236
 Desks, 268
 Detection equipment, 251
 Detectors
 motion, 251
 smoke, 257
 Development and Planning Fees
 Adelaide, 76
 Hobart, 82
 Melbourne, 85
 Perth, 88
 Sydney, 91
 Diffusers
 air, 263
 plenum, 262
 Digital lock, 188
 Diminishing strips, 215
 Dimmers, 246
 Disable Access Lift, 264
 Disabled persons door, 184
 Disconnect electrical, 97
 Dishwasher, 265
 Dispensers
 facial tissues, 145
 hand cleansers, 145
 paper
 towel, 145
 towel/waste, 145
 soap, 145
 toilet tissue, 145
 Disposal
 bins, 146
 chute system, 266
 debris, 97
 excavated material, 101
 Distribution switchboards, 245, 246
 Division strips, 209
 Doctor's surgery, 15
 Domestic appliances
 cooking, 265
 dishwasher, 265
 dryers, 265
 exhaust fans, 250
 food waste, 266
 freezers, 265
 refrigerators, 265
 stove hoods, 266
 washing machine, 265
 Door/doors
 accordion, 185
 architraves, beads, 181
 disabled person, 184
 feature, 183
 fire, 56, 185
 flush
 hollow core, 55, 182
 solid core, 55, 183
 frames, linings
 metal, 180
 take out, 97
 timber, 180
 glazed entry, 184
 grilles, 138
 hardware and door sundries, 188-190

Door/doors (cont'd)
 metal
 aluminium, 184
 disabled persons, 184
 fire, 56, 185
 glazed entry, 184
 insect screen, 180
 roller
 domestic/commercial, 55
 industrial, 55
 sectional overhead, 55
 security, domestic, 56
 sheet steel clad, 184
 operable walls, 202
 protection seals, 190
 roller, 55, 184, 185
 domestic/commercial, 184, 185
 industrial, 185
 seals, etc., 190
 sectional overhead, 185
 security, domestic, 185
 selector, 189
 sheet steel clad, 184
 sliding tracks, 190
 stops
 cushioned, 190
 floor, 190
 timber, 182
 take out, 97
 timber
 feature, 182, 183
 framed and ledged, 183
 glazed, 55, 183
 hollow core, 55, 182
 panelled, 183
 repairs, 98
 solid, 183
 solid core, 55, 183
 Doors, Estimating - Comparative Costs, 55
 fire, 56
 metal, 55
 timber, 55
 Double
 action floor springs, 189
 glazed windows, 177, 178
 glazing, 217
 Dowel rods, 112
 Downlights, 249
 Downpipes
 aluminium, 197, 198
 copper, 197, 198
 PVC, 198
 sundries, 198
 zincalume steel, 198
 colour coated, 198
 DRAINAGE, 238-243
 beds and surroundings, 242
 manholes, 242
 septic systems, 243
 sewer drains, 238, 239
 soakwells, 242
 stormwater drains, 239, 240
 subsoil drains, 240
 sumps and pits, 242, 243
 surface drainage systems, 241, 242
 trench excavation, 238
 Drainage, surface system, 241, 242
 Drain rod, hire, 271

Drains and kerbs, in situ concrete, 105
 Drawer, 174
 lock, 188
 Drill, hire, 270
 Drilling
 concrete, 113
 plugging for screw fixing, 169
 Driwal, 113, 130
 Dryer
 hand, 146
 tumble, 265
 Dubbing out, 98, 203
 Duct
 access panels, 140
 cistern, 224
 covers, 139
 skirtings, 252
 Ducted
 air-conditioning system, 260
 skirtings, 60
 vacuum cleaning system, 266
 Ductile iron access covers, 139
 Ducting
 flexible, 262, 263
 skirting, 252
 Ductwork, mechanical services, 262
 insulated, 262
 Dumbwaiter, 264
 Dumpy level, hire, 271
 Duraduct, 116
 Dustproofing concrete, 113

E

Earth
 auger, hire, 271
 leakage unit, hire, 271
 walls, 130
 EARTHWORKS, 100-102
 bored piers, 102
 bulking factors, 100
 carting, additional, 101
 cut and fill, 101
 disposal, 101
 excavation, 100, 101
 filling, 102
 paper and plastic membranes, 103
 planking and strutting, shoring, 102
 sheet steel piling, 102
 site preparation, 100
 surface treatments, 102
 tanking, 103
 waterproofing, 103
 weed and termite control, 103
 Easycraft
 panelling, 164
 Eaves
 framing, timber, 155
 gutters, various, 198, 199
 sundries, 198, 199
 linings, 168
 soffit treatment, 49
 Ecclesiastical buildings, 20
 Edge
 processing, glass, 218
 strip doors, 183
 Edging strip, 105
 Educational buildings, primary schools, 15

Electric
bidette, 223
boiling water units, 228
domestic appliances, 265
heaters, 249
hot water units, 227
tools and equipment, hire, 270
Electrical, disconnect and seal, 97
ELECTRICAL SERVICES, 244-257
cable
pits, 254
tray and troughing, 252
cables, 254-256
ceiling heating, 250
circuits, power and lighting, 246, 247
closed circuit television, 251
conduits, 252, 253
consumer mains, 245
costs per square metre, 244
exterior lighting points, 246
fans, 250
floor heating, 250
heaters, 249
intercom, 251
lighting point, 246
luminaires, 248, 249
mains pole, 245
power and lighting circuits, 246, 247
raiser bracket, 245
security systems, 252
skirting duct, 252
smoke detectors, 257
submains, 245
switchboards, 245
telephone
cable, 256
equipment, 251
key operated systems, 251
pre-conduiting, 250
television
antenna, 251
cable, 256
closed circuit, 251
home automation system, 257-259
Electricity, site, 72
Elemental Costs of Buildings, 26-42
Enamel painting, 58, 62, 219, 220
baked finish, 137
Engineered timber joist, 150, 153
Environmental septic systems, 243
EPDM roof penetration flashing, 195
Epoxy
mastic, 220
self levelling topping, 208
water based paint, 220
Escalation, anticipated 2018, 291
ESTIMATING, BUILDING COSTS PER
SQUARE METRE, 13-24
administration, civic, 14
agricultural, 14, 15
banks, 15
educational, 15
health, 15
industrial, 16, 17
offices, 13, 17, 18
parking, 18
recreational, 18-20
religious, 20
residential, 20-22, 23-24
retail, 23
taverns, clubs, motels, 13-16

ESTIMATING - COMPARATIVE COSTS,
44-65
ceiling finishes, 61, 62
columns, upper floors, 46
doors, 55, 56
electrical services, 65
floor finishes, 59, 60
mechanical services, 65
preliminaries, 44
roofs, 48, 49
sanitary plumbing and drainage, 63-65
substructure, 45
wall finishes, 57, 58
walls
external, 50-52
internal, 53, 54
ESTIMATING, ELEMENTAL COSTS OF
BUILDINGS, 26-42
administration, civic, 27
banks, 28
educational, 28
element definitions, 26
health, 29
industrial, 31-33
offices, 34
recreational, 35, 36
religious, 37
residential, 38-42
taverns, clubs, motels, 30
Etc.hing, anti slip treatment, 211
Etc.h primer, 220
Evaporative cooling
systems, 260
units, 261, 262
Excavate
balanced cut and fill, 101
basements, 101
confined space, 101
hand, 101
pits, 101
reduce levels, 100
site, 100
thickenings, 101
trenches, 101
drainage, 238
Exhaust
fan, 247
circuit, 249
in-line, 247, 250
Expanded, metal lath, 205
Expanding masonry anchor, 169
Expansion joint, 112
Exposed aggregate finish, 113
Extendable clothes line, 139
Extension lead, hire, 270
Exterior lighting, 246
External Walls, Estimating - Comparative
Costs, 50-52
block, 50, 51
brick, 50
concrete
in situ, 50
precast, 117
aerated, 119
tilt-up, 118, 119
stud framed, 51

EXTERNAL WORKS, 104-109
artificial surfaces, finishes, 109
bollards, 105
fencing and gates, 105, 106
kerbs and drains, 105
landscaping
ground finishes, 108
planting, 108
protection, 108
pavings, 104
retaining walls, 107
reticulation, 107
road marking, 105
screen walls, 107
soiling and grassing, 107, 108
Extruded concrete kerbs, 105

F

Fabric
reinforcement, 116
supply only, 110
vinyl, 58, 212
Face brickwork
arches, 124
cleaning down, 123
cutting, 123
facings, 50, 53, 54, 122, 130
oversailing, 124
setting back or forward, 124
Facial tissue dispenser, 145
Factories, 17
Fair face, brickwork, 53, 54, 123
Family centre, 15
Fans
electric
ceiling, 250
exhaust, 250
in-line, 250
oscillating, 250
outlet, 247
exhaust, hire, 271
heater, 249
Farm buildings, 14, 15
Fascia
board, 160
purlin, steel, 135
treatment, 48
Fasteners, windows, 189
Feature doors, 183
Fees, refer Notices and Fees, 72-93
Felt roofing, 193
Fences
barbed tape, 106
metal
mesh, 106
palisade, 106
ribbed sheet, 105
security, 106
swimming pool, 106
temporary site, 70
hire, 70
tennis court, 106
take down, 100
timber, 105
Fibermesh, 111, 117

Fibreboard
 bitumen impregnated separation strip, 112
 compressed cellular toilet screens, 202
 medium density, wall lining, 164

Fibre cement
 bracing, 151
 ceilings, 61, 168
 compressed
 flooring, 162
 wall lining, 164, 165
 decorative, 165
 eaves lining, 168
 flooring, 162
 suspended ceiling panels, 61, 207
 underlay, 162
 wall linings, 51, 164, 165

Fibreglass
 roofing, 192
 wall cladding, 200

Fibre, tube formers, 115

Fibrillated polypropylene fibres, 117

Fillets
 quadrant, 171

Filling
 concrete to
 cores, 110
 lintel blocks, 110
 piers, 110
 cut and fill, 101
 materials, various, 45, 102
 top soil, 107

Film, solar control, 218

Filter fabric faced or wrapped drainage, 240

Finishes to
 blockwork, 127
 brickwork, 123
 built-up roofing, 194
 concrete, 113

Fire
 brigade board fees
 (Hobart), 84
 brigade board fees (Melbourne), 87
 doors, 56, 185
 extinguishers, 267
 recharge, 267
 hose, 267
 reel, 267
 hydrant
 point, 267
 valve, 267

rated
 plasterboard
 linings, 52, 57, 61, 205
 suspended ceilings, 61, 207

resistant cable, 256

sealant, 128

service
 levy, 73

Fit-out
 bank, 15
 motel, 16
 offices, 17, 18, 267, 268
 retail, 23

Fittings, cabinetwork, 173-176
 take-out, 97

Fixings to
 brick, 168, 169
 concrete, 136, 168, 169
 timber, 168, 169

Flagpoles, 140

Flagstones
 limestone, 131
 sandstone, 131
 slate, 60, 132

Flashing lights, hire, 271

Flashings
 aluminium, 197
 copper, 197
 flexible, 195
 lead, 197
 roof penetration, 195, 196
 zinc, 197
 zincalume steel, 197
 colour coated, 197

Flat roof framing, timber, 155

Flexible
 coil pipe, 240
 ducting, 262
 flashings, 195

Float glass, 216

Floodlights, 249
 floodlighting, 246
 hire, 271

Floor
 access, 137
 aerated concrete panels, 119
 finishes
 carpet, 59, 212
 concrete in situ, 113
 granite, 131
 granolithic, 208
 marble, 60, 132
 slate, 60, 132
 take up or strip, 96
 terrazzo, 208
 tile and sheet, resilient
 cork, 59, 214
 rubber, , 60
 vinyl, 60, 214
 tile, non-resilient
 ceramic, 210
 mosaic, 59, 210
 quarry, 59, 211
 tactile, 211
 terracotta, 211
 terrazzo, 208
 vitreous, 211
 timber
 air thrust, 164
 decking, 163
 generally, 59
 laminated, 163
 parquetry, 59
 reeded decking, 163
 sheet, 59, 162
 tongued and grooved, 59, 162

framing
 steel, 158
 timber, 45, 150, 153

grinder, hire, 270

heating, 250

hollowcore planks, 118

protection, 99

sander, hire, 270

self levelling toppings, 208

soundfloor, 119

springs, 189

Floor (cont'd)
 systems, precast concrete, 118
 take-up, 96
 tiles, 59, 60, 210, 211, 212, 214, 215
 tile stripper, hire, 270
 waste and grating, 231

Floor finishes, Estimating - Comparative
 Costs, 59, 60
 carpet, 59
 marble, 60
 skirtings, 60
 slate, 60
 tiles and sheet, resilient, 59
 tiles, non resilient, 59
 timber, 59

Flooring
 access, 137
 air thrust, 164
 hollowcore, 118
 take up, strip, 96
 timber, generally, 162-164

Floors, preparatory works, repairs, 98

Flourescent
 luminaires, 248

Fluoro polymer coating, windows, 177

Flush
 bolt, 189
 doors, 55, 182

Food waste disposer, 266

Footings, strip
 all-up, 45
 concrete, 110
 formwork, 110

Footpath, 104

Footrest, tile, 210

Formers, tube, 115, 116

Formwork, 114-116
 boarded
 attached beam, 115
 column, 115
 suspended slab, 115
 wall, 115
 column foundations, 114
 column or pier, 114
 cutting, 114
 generally, 115
 metal tray, 115
 off-form, 115
 pier, 114
 staircases, 114
 suspended slab, 114, 115
 tube formers
 fibre, 115
 FRC, 115
 plastic spirally wound, 116
 walls, 114, 115

Foundation
 beams
 all-up, 45
 concrete, 110
 column or pier
 all-up, 45
 concrete, 110
 formwork, 114, 115

raft
 all-up, 45
 concrete, 110

Framed
 ledged door, 183
 partitions, 202
 roof, 151, 154
 walls, 51, 52
 Framing
 anchors, connectors, 168, 169
 carpentry, 150, 151, 153
 floors
 timber, 45, 150, 153
 roofs, 151, 155
 walls
 steel, 51, 158
 timber, 51, 150, 151, 153, 154
 FRC tube formers, 115
 Freeform pool, 19
 Free hanging blinds, 186
 Freezers, domestic appliances, 265
 French
 polish, 219
 roof tiles, 191
 Fungus protection, 130
 Furniture, offices, 267, 268
 Furring
 metal, 205

G

Galvanised steel
 access covers, 139
 Galvanising
 metalwork, 137
 reinforcement, 116
 structural steel, 136
 Garage
 domestic, 23
 service station, 17
 Garbage
 compactor, 266
 disposer, sink type, 266
 Gas
 connection appliances, 237
 cooking equipment, 265
 heater, 261
 hot water units, 227
 pipe, polyethylene, 237
 Gates, 105, 106
 Gate valve, 230
 Gatic covers, gratings, 139, 140
 Generator, hire, 271
 Girts, steel, 134, 135
 Glass
 blocks, 129
 screens, glazed internal, 179
 Glass and glazing
 acrylic, 217
 applied film, 218
 balustrade, 143
 blocks, 129
 clear float, 216
 cyclone, 216
 double glazing, 217
 edge processing, 218
 heat absorbing, 216, 217
 holes, 218
 laminated, 216, 217
 louvres, 217
 Glass and glazing (cont'd)
 mirrors, 217
 patent, 179
 polycarbonate, 217
 reflective, 217, 218
 shower screens, 218
 solar control, 216, 217
 film, 218
 squash court wall, 18
 toughened, 216, 217
 wired, 216
 Glasswall, squash courts, 18
 Glasswool insulation, 51
 Glazed
 aluminium door, 184
 balustrade, 143
 screens, 179
 timber door, 55, 183
 GLAZING, 216-218
 acrylic sheet, 217
 double glazing, 217
 edge processing, 218
 glass and glazing, 216, 217
 louvres, 217
 mirrors, 217
 polycarbonate sheet, 217
 shower screens, 218
 solar control film, 218
 Glazing beads, timber, 182
 Grab rail, 144
 Grade ground, 102
 Grading to falls, concrete, 113
 Grand masterkeying, 190
 Granite
 bench top, 173
 facing, 131
 filling (rock), 102
 Granitgard termite barrier, 103
 paving, 131
 Granitgard, 103
 Granolithic, 208
 colour additive, 208
 skirtings, 60, 208
 Granosite applications, 204
 Grassing, 107
 artificial surfaces, 109
 turf
 cutting, 100
 laying, 107
 roll type, 107
 Gratings, 139, 140
 surface drainage system, 241, 242
 Grilles
 air relief, 138
 louvred, 180
 openings in doors, 183
 tree, 108
 Grinder, hire, 270
 Grip rail, 144
 Ground
 cover, 108
 finishes, 108
 floor framing
 steel, 158
 timber, 45, 150, 153
 slabs
 all-up, 45
 concrete, 110
 formwork, 114, 115

Grounds, timber, 159
 Grout, steel wedge and,, 136
 Guard
 angle, 138
 leaf, 200
 rail, 140
 tree, 108
 Guardrail
 roof, 70
 Gully gratings, 139
 Gutter boarding, 151
 Gutters
 box, 199
 eaves, 198, 199
 valley, 199
 Gymnasium, 18

H

Hack
 brickwork, 98
 concrete for key, 98
 finishes from walls, 96
 Hall, church, 20
 Hand
 cleansers, 145
 dryers, 146
 excavation, 101
 Handrails
 aluminium, 143
 stainless steel, 144
 steel, 144
 timber, 172
 Hands free tap, 229
 Hangers, timber, 151, 154
 Hardboard
 bracing, 151
 flooring, 59, 162
 underlay, 162
 wall lining, 166
 Hardeners
 aerated concrete, 119
 surface, 113, 208
 Hardwall
 plaster, 57, 61, 203
 skim coat, 61, 203
 HARDWARE AND DOOR SUNDRIES,
 188-190
 hardware generally, 188-190
 hinges, 188
 keying, 190
 seals, 190
 sliding track, 190
 Hasp and staple, 189
 Hat and coat rails, 171
 Health buildings, 15
 Heat absorbing glass, 216, 217
 Heaters
 electric
 connection, 249
 fan type, 249
 infra red strip, 249
 oil filled type, 249
 gas, 261
 solid fuel, 261
 space, hire, 272

Heating
 ceiling, 250
 floor, 250
 Hexagonal head bolt, 168
 High bay luminaires, 249
 Hinges, 188
 Hip
 boards, timber, 151
 capping, 192, 193
 tile, 191
 Hoarding fee
 Adelaide, 76
 Melbourne, 85
 Sydney, 92
 Hoardings, 70
 Hobart City Council, plumbing and drainage
 fees, 82, 83
 Hoeing, rotary, 107
 Hoists, hoisting, 69
 hire, 271
 Holding down bolts, 136, 168
 Holiday units, 22
 Holland blinds, 186
 Hollow
 core
 doors, 55, 182
 section steel, 134
 Hollowcore flooring, 118
 Hood stove, 266
 Hooks, etc., 190
 shower curtain, 144
 Hoop iron cramp, 125
 Hose
 cock, 230
 fire, 267
 hire, 270, 271
 reel, 267
 tap box, 140
 Hot
 water
 unit heaters
 boiling water, 228
 electric, 227
 gas, 227
 solar, 227, 228
 House, mains, electrical, 245
 Houses, refer Residential Buildings, 20-24
 additions, 21
 Hydrant point, 267
 Hydraulic lift, 264
 Hydro mulch, 108

I

Incandescent lights, 246
 Indicator bolt, 189
 Industrial
 buildings, 13, 16, 17
 luminaires, 248
 roller doors, 55, 185
 sectional overhead doors, 55, 185
 Infra red
 heater, 249
 motion detector, 251
 Inlet louvres, 187
 In-line exhaust fan, 250
 Insect screens, 180

Instantaneous hot water unit, 227
 Insulation
 aluminium, 160
 batts, 161
 blanket
 suspended ceilings, 207
 built-up roofing, 194
 expanded polystyrene, 194
 foil, 160, 161
 perforated, 160
 framed walls, 51
 glasswool, 161
 piping, 236
 polyester, 161
 sarking, 160
 solar control film, 218
 Insurance
 contract works
 insurance, 73
 public liability, 74
 property, 307
 valuing for insurance, 307
 Intelligent home management systems,
 257-259
 Intercom systems, 251
 Internal walls, Estimating - Comparative
 Costs, 53, 54
 block, 53, 54
 brick, 53, 54
 concrete
 aerated block, 53
 in situ, 53
 precast, 117
 fire resistance levels, 54
 stud framed, 51

J

Jack, hire, 271
 JOINERY, 170-176
 base material prices, 170
 cover moulds, 171
 cupboards, fittings, 173-176
 handrail, 172
 hat and coat rails, 171
 pelmet, 171
 pinboard, 176
 seat battens, 172
 shelving, 173
 skirtings, 171, 172
 staircases, balustrades and handrails, 172
 whiteboard, 176
 Joints
 construction, 112
 control, brickwork, 127
 expansion, concrete, 112
 sealants, 127, 128
 Joist, hanger connectors, 169
 Joists
 steel, 158
 timber, 150, 151, 153, 155
 engineered, 150, 153

K

Kango hammer, hire, 270
 Kerbs, concrete, 105
 Keyed construction joint, 112
 Keying, 190
 Key operated telephone system, 251
 Keys, lifting, 140
 Kick plates, 189
 Kitchen
 appliances, 265, 266
 cupboards, 173
 fit-out, 21
 sink, 225
 Kordon termite barrier, 103
 Krystol, 113

L

Laboratory, tap set, 229
 LABOUR CONSTANTS, 279-288
 brickwork and blockwork, 281
 carpentry, 282-285
 concrete work, 280, 281
 drainage, 288
 excavation, 280
 glazing, 286
 hardware, 285
 joinery, 284
 metalwork, 282
 painting, 286
 pavior, 286
 plastering, 285, 286
 resilient finishes, 286
 roofing, roof plumbing, 285
 sanitary plumbing, 286-288
 structural steelwork, 282
 suspended ceilings, 286
 tiling, non-resilient, 286
 windows and doors, 284
 Ladder
 access, 141
 framing, 173
 hire, 272
 Laminated
 benchwood top, 174
 flooring, 163
 glass, 216, 217
 plastic bench top, 174
 timber beams, 156, 157
 Landscaping
 generally, 19
 ground finishes, 108
 planting, 108
 protection, 108
 Latches, 188
 Latex paint, 58, 62, 220
 Latham joint, 209
 Lath, expanded metal, 205
 Laundry
 mixer set, 228
 trough, 225
 Leach drain, 243
 Lead
 flashing, 197
 penetrations, 196
 Leaf guard, 200

Leisure pool, 19
 Lettering, signwriting, 221
 Letter plate, 189
 Levelling
 ground, 102
 toppings, 208
 Libraries, 14
 Lift and Escalator Inspection fee, refer
 Notices and Fees, 75-93
 Lifting keys, 140
 Lifts, 264
 Light
 fightings, 248, 249
 point, circuitry
 commercial, circuit, 246
 disconnect, 97
 exterior, 246
 industrial, circuit, 247
 residential, circuit, 247
 Lighting
 bollard, 246
 columns, 246
 commercial circuit, 246
 dimmer, 246
 domestic, circuit, 246
 downlights, 249
 exterior, 246
 flood light
 hire, 271
 floodlighting, 249
 flourescent, 248
 industrial, circuit, 246
 luminaires, generally, 248, 249
 outlet, 246
 point, 246, 247
 pole, 245
 tower, hire, 271
 Lightweight
 planting mixture, 108
 Limestone
 facing, 131
 paving, 131
 walling, 131
 Linen cupboard, 174
 Lining paper, 222
 Linings
 ceiling, refer ceiling finishes, 168
 door, 180
 eaves, 168
 Link mesh partitions, 138
 Lintels
 blockwork, 127
 brickwork, 124
 concrete filling, 110
 steel, 111
 timber, 151
 Liquid acrylic membrane roofing, 194
 Load bearing brickwork, 122
 Local alarm system, 251
 Local Authority Fees, refer Notices and Fees,
 72-93
 Lockers, 141
 Locks
 general, 188
 security, 188
 Log barrier, 108

Louvred
 panels, 179
 sunscreens, 187
 vergola system, 201
 windows, 180
 Louvres
 glass, 217
 panels, 179
 sunscreens, 187
 Luminaires, 248, 249
 Lunchroom (on-site), 71

M

Magnetic
 cupboard, catch, 189
 reed door contact, 251
 Mains
 consumer, 245
 switchboard, 245, 246
 Making good openings, 98
 Manholes, 242, 243
 covers, 139, 140
 Man, material hoist, 69
 Marble
 facing, 132
 paving, 60, 132
 Masonry
 anchors, 169
 blocks, 50, 51, 54, 120, 121
 bricks, 50, 120, 122
 equipment hire, 270
 reinforcement, 129
 MASONRY, 131-133
 bluestone, 133
 granite, 131
 limestone, 131
 marble, 132
 sandstone, 131
 slate, 132
 Masterkeying, 190
 Mastertop finishes, 113
 Mastic sealant, 127
 Mats, 141
 Matwell surrounds, 141
 Maxibrick, 122
 MEASUREMENT OF BUILDING AREAS,
 305, 306
 MECHANICAL SERVICES, 260-263
 air-conditioning
 costs per square metre, 260
 diffusion equipment, 263
 ducted domestic system, 260
 evaporative systems, 260
 room units, 260
 ductwork, 262, 263
 evaporative
 cooling units, 261
 systems, 260
 heaters
 gas, 261
 solid fuel, 261
 room air-conditioning units, 260
 ventilation
 costs per square metre, 260
 Medium density fibreboard, 164

Membranes
 paper, polythene, 103
 waterproof, 194, 195
 Mesh
 fencing, 106
 reinforcement, 116, 117
 safety, 160
 Metal
 chips, 108
 door frames, 180
 doors, 55, 56, 184, 185
 fencing, 105, 106
 furring, 205
 lath, 205
 perforated, cladding, 142
 suspended ceilings, 61, 207
 tray formwork, 115
 METALWORK, 137-146
 access
 covers, 139
 flooring, 137
 air relief grilles, 138
 aluminium trim, 138
 angle guards, 138
 balustrades, 143
 chainwire partitions, 138
 cladding
 external insulated, 142
 perforated, 142
 sheet, 142
 clothes
 hoist, 139
 line, 139
 computer flooring
 refer access flooring, 137
 covers and gratings, 139, 140
 crash and guard rails, 140
 duct access panels, 140
 ducted skirtings, 252
 external insulated cladding, 142
 flagpoles, 140
 handrails, 143, 144
 ladders, 141
 lockers, 141
 mats, 141
 matwell surrounds, 141
 perforated, cladding, 142
 protective treatments, 137
 roof safety system, 146
 shelving, 142
 skirtings, 143
 staircases, 143
 sump and gully gratings, 139
 toilet accessories, 144-146
 trench gratings, 140
 Metropolitan Fire Brigade's Board fees,
 (Melbourne), 87
 Micro
 reinforcing system, 111, 117
 venetian blind, 186
 Microwave oven, domestic, 265
 Mineral fibre tile ceilings, 207
 Mirrors, 217
 Miscellaneous
 costs, Preliminaries, check list, 94

MISCELLANEOUS, 265-268
 cleaning, 266
 cool rooms, 266
 domestic appliances, 265, 266
 fire
 extinguishers, 267
 hose reel, 267
 hydrant points, 267
 office furniture, 267, 268
 saunas, 266
 spa pools, 266
 waste disposal, 266
 Mixing
 tap, 228
 valve, thermostatic, 229
 Mobile
 cranes, 69
 scaffolds, 70
 Modular
 bricks, 50, 54, 122
 carpet, 59, 212
 partitions
 demountable, 202
 screen, 202
 Monowills balustrade, 143
 Mortar
 bed, 104
 brickwork, 121
 cavity filling, 123
 damp proof course, 129
 Mortice
 deadlock, 188
 lock, latch, 188
 Mosaic
 tiles, 210
 Mosaic tiles, 57, 59
 Motels, 16
 Motion detector, 251

N

Nail
 gun, hire, 272
 stainless steel, 169
 Neighbourhood shops, 23
 Night latch, 188
 Noggings
 steel, 158
 timber, 151
 Nosings, stair, 215
 Notices and fees
 Adelaide, 75-77
 Brisbane, 78-82
 Hobart, 82, 83, 84
 Melbourne, 85-87
 Perth, 88-90
 Sydney, 91-93
 Nursing home, 23

O

Observation mirror, 217
 Off-form formwork, 115
 Office
 administration, 14
 buildings, 17
 fitting out, 17, 18
 furniture, 267, 268

Offices and sheds (on-site), 71
 Oil filled column heater, 249
 Old peoples homes, refer Aged persons
 homes, 23
 Openings, cutting, making good, 98
 Operable walls, 202
 Orbital sander, hire, 270
 Oscillating fan, 250
 Outdoor gas heater, 261
 Outlets
 plumbing, 229
 power, 246, 247
 sump, 200
 Ovens, domestic, 265
 Overhead
 mains, 245
 sectional door, 55, 185
 sliding track, 190
 Oversailing brickwork, 124

P

Painting
 artificial surfaces, 109
 Paint
 acrylic, 58, 62, 219, 220
 acrylic glaze, 222
 bituminous, 103
 burner, hire, 272
 clear finish, 219
 enamel, 57, 58, 61, 62, 219, 220
 epoxy mastic, 220
 latex, 57, 58, 61, 62, 220
 polish
 french, 219
 wax, 219
 polyurethane, 219
 preparation of existing, 221
 rag rolling effect, 220
 road marking, 105
 sealer, 220
 stain, 219
 textured finish, 204
 timber finish acrylic, 219
 water
 based epoxy, 220
 repellent, 220
 PAINTING, 219-222
 external, 221
 fabrics, 222
 internal, 219, 220
 masonry, 220
 metalwork, 219, 220
 plaster, 220
 preparation of existing, 221
 signwriting, 221
 wall
 fabrics, 222
 paper, 222
 walls, 220
 woodwork, 219
 Paling fence, 105
 Palisade fence, 106
 Panelled door, 183
 Panelling, 164

Panels
 duct access, 140
 louvred, 179
 Paper hanging, 57, 58, 222
 Paper towel
 dispenser, 145
 waste cabinet, 145
 Parapet walls, 49
 Parking
 office buildings, 18
 open, 18, 23
 Parquetry
 block, 59, 163
 mosaic, 59, 163
 Particle board
 cored partitions, 202
 flooring, 59, 162
 shelving, 173
 veneered, 166
 wall lining, 166
 Partitions
 chain wire, 138
 framed, 202
 modular, 202
 PARTITIONS, 202
 chain wire screens, 202
 framed, 202
 modular
 demountable, 202
 screen, 202
 operable walls, 202
 toilet screens, 202
 Passenger lift, 264
 Patent glazing, 179
 Patio door bolt, 188
 Paving
 bitumen, 104
 block, 104
 bluestone, 133
 brick, 104
 concrete, 104
 granite, 131
 granolithic, 208
 limestone, 131
 marble, 132
 sandstone, 131
 slab, 104
 slab roof protection, 194
 slate, 132
 surface treatment, 104
 terrazzo, 208
 PAVIOR AND TERRAZZO, 208, 209
 division strips, 209
 granolithic, 208
 self levelling toppings, 208
 terrazzo paving, 208
 weather bars, 209
 Pebbles, river, 108
 Pedestal basin, 223
 Pegboard
 lining, 166
 Pelmets, 171
 Penetrations, roof, 195, 196
 Penetrometer, hire, 272
 Perforated
 foil insulation, 160
 metal cladding, 142
 Pergola framing, 155

Perimeter angle, plasterboard ceilings, 205
 Permastop, 161
 Pest control, 103
 Picket fence, 105
 Pier
 bored, 102
 brick, 46, 122
 formwork, 114
 Piling, sheet steel, 102
 Pillar tap, 228
 Pine
 bark chips, 108
 log barrier, 108
 Pipe
 bender, hire, 272
 insulation, 236
 threader, hire, 272
 wrapping, 236
 Pipework
 Chromium plated, 234
 cutting into, 97, 99
 gas, polyethylene, 237
 insulation, 236
 sewer
 cast iron, 238
 concrete, 239
 pvc, 239
 soil, waste, vent
 copper, 232, 233
 pvc, 233
 stormwater
 polyethelene - HDPE, 240
 pvc, 239, 240
 subsoil
 polyethylene, 240
 thermoplastic cored, 240
 water
 copper, 234
 polyethylene, 235
 pvc, 236
 Pit
 brick, 242
 cable, 254
 concrete, 242
 precast, 243
 covers, 139, 243
 Planking and strutting, 102
 Plant
 hire rates
 cranes, 69
 general, 270-272
 hoists, 69
 scaffolding, 69, 70
 site offices and sheds, 71
 small plant, 270-272
 Planting
 ground cover, 108
 landscaping generally, 19
 mixture, 108
 shrubs, 108
 trees, 108
 Plaster
 acoustic tile ceilings, 207
 beads, 205
 ermiculite, 61
 hardwall, 57, 61, 203
 skim coat, 61, 203
 preparatory work, 203
 vermiculite, 205

Plasterboard
 fire rated
 linings, 52, 57, 61, 205
 linings
 ceilings, 61, 205
 walls, 52, 57
 suspended ceilings, 61, 207
 tile ceilings, 61, 207
 PLASTERING, 203-206
 beads, 205
 cement render, 203
 expanded metal lath, 205
 hardwall plaster, 203
 plasterboard, 205
 preparatory work, 203
 textured finishes, 204
 vermiculite plaster, 205
 wall framing, 206
 Plastic
 cistern, 224
 plug and screw, 169
 Spirally wound tube formers, 116
 surface drainage channel, 241
 toilet seat, 224
 Plate
 compactor, hire, 270
 connections, 135
 Plates
 kick, 189
 letter, 189
 push, 189
 steel, 158
 timber, 150, 151
 Platform
 hoist, 69
 lift, 264
 Plenum diffuser, 262
 Plexicushion, 109
 Plexiflor, 109
 Plexipave, 109
 Plumbing, refer Sanitary Plumbing
 fees
 Adelaide, 76, 77
 Brisbane, 79, 80, 81, 89
 Hobart, 82, 83
 Melbourne, 85, 86
 Perth, 89
 Sydney, 93
 take out fixtures, 97
 Plumbing, refer Sanitary Plumbing
 alterations, 99
 Plywood
 ceiling linings, 166, 167
 floor panels, 59, 162
 gutter boarding, 151
 wal linings, 167
 wall linings, 166
 Pneumatically placing concrete, 111
 Pole
 lighting, 246
 mains, 245
 Polishing
 french, 219
 wax, , 162
 Polycarbonate
 domed rooflight, 196
 roofing, 192
 sheet glazing, 217

Polyester
 insulation, 161
 powder coat finish, 177
 Polyethylene
 barriers, screens, 70
 flexible coil, 240
 leaf guard, 200
 piping, 235
 Polypropylene
 carpet, 212
 micro reinforcing system, 111
 Polystyrene
 insulation, 194
 Polysulphide sealant, 127
 Polythene
 orange, 103
 sheeting, 103
 underlay, 45
 underlay to paving, 104
 Polyurethane
 clear finish, 219
 sealant, 128
 Polyurethane
 floor finish, 162
 Pools, swimming, 19
 Portal frames, 134
 Post
 anchor base, 169
 timber, 152
 Powder coat finish
 metalwork, 137
 windows, 177
 Power
 circuits, 246, 247
 consumer mains, 245
 outlets, 246, 247
 weatherproof, 247
 point
 disconnect, 97
 points, 246, 247
 Precast
 aerated concrete panels, 119
 columns, 118
 concrete
 aerated panels, 119
 beams, 118
 covers, 243
 flooring
 Beam and infill system, 118
 hollowcore, 118
 load bearing, 117
 manhole, 242
 slab roof protection, 194
 soakwells, 242
 sumps, pits, 243
 walling, 117
 flooring, 118
 terrazzo
 paving, 208
 PRELIMINARIES, 69-94
 hoardings and fences, 70
 hoisting, 69
 insurance, 73, 74
 miscellaneous costs, 94
 notices and fees, 75-93
 Adelaide, 75-77
 Brisbane, 78-82
 Hobart, 82, 83, 84

PRELIMINARIES (cont'd)

- Melbourne, 85-87
- Perth, 88-90
- Sydney, 91-93
- offices and sheds, 71
- plant and scaffolding, 69, 70
- roof guardrail, 70
- scaffolding, 69, 70
- temporary services, 72
- Preliminaries, Estimating - Comparative Costs, 44
- Preparatory work and repairs
 - ceilings, 98
 - floors, 98
 - plastering, 98
 - re-decoration, 221
 - walls, 98
- Pretensioned hollow floor planks, 118
- Pricking up coat, 203
- Primary schools, 15
- PROPERTY INSURANCE**, 307
- Prop, hire, 270
- Proprietary steel
 - floor framing, 158
 - girts, 135
 - purlins, 135
 - wall framing, 158
- Protection
 - built-up roofing, 194
 - floors, 99
 - fungus, 130
 - handrails, 99
 - log barriers, 108
 - roof openings, 99
 - stair treads, 99
 - tree grilles, 108
 - tree guards, 108
 - walls, 99
- Protective treatments
 - metalwork, 137
 - paint finishes, 219-221
 - steel, 136
 - windows, 177
- P trap, 231
- Public**
 - liability insurance, 74
 - toilet, 14
- Pull handle, 189
- Pump hire, 271
- Pumping concrete, charges, 111
- Purlin
 - bolts, 136
 - steel, 136
 - timber, 151, 154
- Push plate, 189
- PVC**
 - conduits, 252
 - downpipes, 198
 - gutters, 198
 - leach drain, 243
 - pipng and fittings
 - sewer drains, 239
 - soil, waste and vent, 233
 - stormwater, drains, 239, 240
 - water, 236
 - traps, 231
 - waterstops, 112

Q

- Quadrant fillet, 171
- Quarry tiles, 59, 211
- sills, 125
- Quartz
 - chip, roof protection, 194
 - glass heater, 249

R

- Radiant heater
 - gas heater, 261
 - heat globe unit, 249
- Rafters, timber, 151, 154
- Raft slabs
 - all-up, 45
- Rag rolling, paint finish, 220
- Rails
 - crash guard, 140
 - grab, 144
 - shower curtain, 144
 - towel, 144
- Rainwater
 - disposal, 49, 197, 198, 199
 - recycling pipework, 236
- Raised panel access flooring, 137
- Raiser bracket, 245
- Rammed earth walls, 130
- Ramset gun, hire, 272
- Raven seals, 190
- Rebound artificial surfaces, 109
- Recreational buildings and facilities, 18, 19
- Recreation centre, 18
- Recycled water pipework, 236
- Reduced pressure zone device, 230
- Reduce level excavation, 100
- Reeded decking, 163
- Reflective
 - closed air cell insulation, 160
 - film, 218
 - glass, 217
- Refrigerator, 265
- Refuse
 - disposal chute system, 266
- REGIONAL INDICES**
 - New South Wales, 292, 293
 - Northern territory, 304
 - Queensland, 294, 295
 - South Australia, 296, 297
 - Tasmania, 302, 303
 - Victoria, 298, 299
 - Western Australia, 300, 301
- Register, air diffusion, 263
- Reinforcement
 - bar
 - placing and fixing, 116
 - supplied and fixed, 116
 - supply only, 110
 - base prices, 110
 - blockwork, 129
 - bored piers, 102
 - brickwork, 129
 - fabric, 116
 - supply only, 110
 - galvanising, 116
 - micro systems, 111, 117
 - polypropylene fibres, 117
 - Polypropylene fibres, 111
 - supply only, 110
 - trench mesh, 117

Religious buildings, 20

- Render
 - cement, 57, 203
 - hardwall, 57, 203
 - tiling, 57, 203
- RENOVATIONS, 273-278**
 - demolition, 274, 275
 - new and remedial work, 275-278
- Repairs
 - ceilings, 98
 - floors, 98
 - walls, 98
- Residential buildings, 20-24
 - aged persons home, 23
 - Bathroom fit-out, 21
 - carpet, 212
 - carports, 23
 - cork, 214
 - diminishing strips, 215
 - garages, 23
 - holiday units, 22
 - house additions, 21
 - houses, 20, 21
 - individual, 21
 - kitchen fit-out, 21
 - multi unit, 22
 - nosings, 215
 - nursing home, 23
 - parking, 23
 - project house, 20
 - rubber, 214
 - town house, 22
 - vinyl, 214
- RESILIENT FINISHES, 212-215**
- Retail
 - buildings
 - neighbourhood shops, 23
 - suburban, 23
 - fit-out, 23
 - parking, 23
- Retaining walls, 107
- Reticulation, 107
- Re-use, demolitions, 97
- Ribbed
 - aluminium
 - roofing, 192
 - wall cladding, 200
 - fibreglass roofing, 192
 - polycarbonate roofing, 192
 - steel
 - fencing, 105
 - lintel, 124
 - roofing, 193
 - wall cladding, 200
- Ridge
 - capping, 192, 193
 - timber, 151
 - ventilator, 201
- Rim**
 - latch, 188
 - lock, 188
- Rings, towel, 144
- Ripple
 - sound, 160
 - tone, 160
- River pebble
 - gravel, roof protection, 194
 - landscaping, 108

Road
 marking, 105
 warning signs, hire, 272
 Roadworks, external works, 104
 Rock
 crushed
 backfilling, drainage trenches, 238
 basecourse, 104
 filling, 45, 102
 drill, hire, 270
 Roller
 blinds, 186
 doors, 55, 184, 185
 Rollers, hire, 271
 Roof
 addition, house, 21
 comparative costs, 48, 49
 decking, 192
 demolition, stripping, 96
 framing
 timber, 151, 154
 guardrail, 70
 penetrations, 195, 196
 ridge ventilators, 201
 safety system, 146
 shingles, 195
 slate, 191
 steel framed, 48
 system, vergola, 201
 tiles, 191
 trusses, 134
 timber, 155
 windows, 196
 Roofing
 aluminium, 192
 timber framed, 48
 ROOFING, 191-201
 built-up, 193, 194
 finishes, 194
 insulation, 194
 protection, 194
 roofing, 193, 194
 concrete, 191
 copper, 192
 fibreglass, 192
 leaf guard, 200
 liquid acrylic membrane, 194
 membrane applications, 194, 195
 polycarbonate, 192
 ridge ventilators, 201
 rooflights, 196
 roof penetrations, 195
 roof plumbing
 downpipes, 197, 198
 flashings, 197
 gutters, 198, 199
 roof windows, 196
 shingles, 195
 skylights, 196
 slate, 191
 steel, 192, 193
 tanking, 194, 195
 terracotta, 191
 tiles, 191
 vergola roofing system, 201
 wall cladding, 200

Rooflights
 windows, 196
 Roofs, Estimating - Comparative Costs, 48, 49
 eaves treatment, 49
 fascia treatment, 48
 parapet walls, 49
 rainwater disposal, 49
 steel framed construction, 48
 timber framed construction, 48
 Room air-conditioning units, 260
 Rotary
 clothes hoist, 139
 hoeing, 107
 Rubber
 tiles, , 60
 underlay, 59, 212
 Rural, farm buildings, 14, 15

S

Saferidge fall arrest system, 146
 Safe tray, 231
 Safety
 fence, 106
 film, glass, 218
 glass, 218
 mesh, 160
 nosing, 215
 roof system, 146
 Samples, testing of concrete, 111
 Sand
 backfilling drainage trenches, 238
 beds, , 102
 blast finish, 113
 filliing, 45
 filling, 102
 Sander, 270
 floor, hire, 270
 grinder, hire, 270
 orbital, hire, 270
 Sandstone
 copings, 131
 facing, 131
 paving, 131
 sills, 131
 walling, 131
 Sanitary fixtures
 bar sink, 225
 bath, 223
 bidette, 223
 cistern, 224
 composite cost including pipework, 63-65
 shower
 bath, 225
 enclosure, 225
 shower base, 224
 sink, 225
 spa bath, 225
 take out, 97
 toilet seat, 224
 trough, 225
 urinal, 226
 water cooler, 226
 wc, 224

SANITARY PLUMBING, 223-237
 cocks and valves, 232
 floor wastes, 231
 hot water units, 227, 228
 pipework, 231-237
 sanitary fixtures, 223-226
 stainless steel connectors, 231
 taps and outlets, 228, 229
 thermostatic mixing valves, 229
 traps, 231
 Sanitary Plumbing and Drainage, Estimating - fixtures, composite prices, 63-65
 outside building, 65
 Sanitary Plumbing and Drainage, Estimating - Comparative Costs, 63-65
 Sarking, foil, 160
 Sash
 fastener, 189
 lift, 189
 Saunas, 266
 SA Water Corporation fees, 76, 77
 Saw, hire, 270
 Sawing concrete, 114
 Scabbler, hire, 270
 Scabbling rock, 102
 Scaffolding
 mobile, 70
 tubular, 69
 Scaffolding Inspection Fee, refer Notices and Fees, 75-93
 School buildings, primary, 15
 Scissor platforms, 70
 Scotia, 171
 Screens
 chain wire, 138, 202
 glazed internal, 179
 hoardings, fences, 70
 insect, 180
 modular, 202
 shower, 218
 site, 70
 temporary, 99
 toilet, 202
 Screen walls, 107
 Sealants, 127, 128
 Sealed glazed units, 217
 Sealer
 concrete, 113
 masonry, 220
 Seals, door, 190
 Seat
 battens, 172
 toilet, 224
 Sectional
 overhead doors, 55, 185
 Security
 doors, domestic, 56, 185
 fence, 106
 site, 70
 hinges, 188
 locks, 188
 systems, electronic, 252
 Self levelling toppings, 208
 Separation strips, 112
 Septic system
 environmental, 243
 standard, 243

- Service
 - lift, 264
 - station, 17
 - temporary, on site, 72
- Sewer drains
 - concrete, 239
- Sewer drains, pipes and fittings
 - cast iron, 238, 239
 - manholes, 242
 - covers, 139, 140, 243
 - PVC, 239
- Shadecloth, 108
- Shades, sunscreens, 187
- Shear studs, 115
- Sheds
 - farm, 14, 15
 - site, 71
- Sheetmetal
 - cladding, 142
 - perforated, 142
- Sheet steel
 - clad door, 184
 - piling, 102
- Shelf
 - brackets, 173
 - framing strip, 173
 - particle board, 173
 - timber, 173
- Shelving systems, adjustable units, 142
- Shingles
 - american, 195
 - porcelain enamelled, 195
 - timber, 195
- Shiplap panelling, 51, 167
- Shop
 - fronts, 179
 - treatment, steel, 136
- Shops, 23
- Shoring excavations, 102
- Shoring, excavations, 102
- Shot fixings, 169
- Shower
 - base, 224
 - bath, 225
 - curtain
 - hook, 144
 - rail, 144
 - enclosure, 225
 - glass screens, 218
 - mixer set, 228
 - waste and grating, 231
- Shrubs, 108
 - landscaping generally, 19
- Shutter
 - timber, 186
- Signwriting, 221
- Silicone
 - sealants, 128
 - water repellent, , 130
- Sills
 - brick, 125
 - sandstone, 131
 - tile, 125
- Sink
 - bar, 225
 - cleaner's, 225
 - combination set, 228
 - kitchen, 225
 - water heaters, 227
- Site
 - barriers and screens, 70
 - clearing, 100
 - excavation, 100
 - fence, 70
 - lunchroom, 71
 - office, 71
 - preparation, 100
 - sheds, 71
 - toilets, 71
- Skeleton bolt, 189
- Skim coat hardwall, 61, 203
- SKIRTING
 - carriers
 - skirting duct, 252
 - duct, 252
- Skirtings
 - ducted, 60, 252
 - granolithic, 60, 208
 - terrazzo, 60, 208
 - tile, 60, 211
 - timber, 60, 171, 172
 - versiclad finish, 143
 - vinyl, 60, 214
- Skylight, 196
- Slabs, concrete
 - ground
 - all-up, 45
 - formwork, 114
 - precast paving, 104
 - raft
 - all-up, 45
 - sawing, 114
 - suspended
 - all-up, 46
 - formwork, 114, 115
- Slate
 - facing, 132
 - paving, 60, 132
 - roofing, 191
- Slat shelving, 173
- Sleeve anchor, 136
- Sliding
 - doors
 - glazed entry, 184
 - door track, 190
- Slimline venetian blind, 186
- Slow combustion stove heater, 261
- Smoke alarm (detectors), 257
- Soakwell, 242
- Soap
 - dispenser, 145
 - holder, tile, 210
- Soil
 - backfilling drainage trenches, 238
 - filling, 107
 - pipes, fittings
 - copper, 232, 233
 - pvc, 233
- Solar
 - control
 - film, 218
 - glass, 216, 217
 - water heating, 227, 228
- Sola-tube skylight, 196
- Solid
 - core doors, 55, 183
 - door, 183
 - fuel heater, 261
 - top course, blockwork, 127
- Sonomatt, 161
- Sound attenuation panel, 207
- Spa
 - bath, 225
 - pool, 266
- Space
 - heater
 - hire, 272
 - rental fee, (Melbourne), 85
- Spirally wound tube
 - formers, 116
- Spiral staircase
 - steel, 47, 143
- Splitter, brick/block, hire, 270
- Sport Grass, 109
- Spotlights, 248
- Sprayed
 - bitumen seal, 104
 - grass seed, 108
 - vermiculite plaster, 61, 205
- Squash courts, 18
- Stabilised rammed earth walls, 130
- Stainless steel
 - angle guards, 138
 - balustrades, 143
 - basin, 223
 - bollard, 105
 - cavity ties, 123
 - cistern, 224
 - cladding, 142
 - eaves gutter, 198, 199
 - facial tissue dispenser, 145
 - flashings, 197
 - grab rail, 144
 - gutters, 199
 - handrails, 143
 - hinges, 188
 - kick plate, 189
 - nails, 169
 - paper towel dispensers, 145
 - Pull handle, 189
 - push plate, 189
 - rainwater goods, 197-199
 - sheet cladding, 142
 - shower
 - base, 224
 - curtain rail, 144
 - hook, 144
 - sink, 225
 - sump outlet, 200
 - termite barrier, 103
 - tissue dispensers, 145
 - toilet
 - accessories, 145
 - roll holder, 145
 - tissue dispenser, 145
 - towel
 - dispenser, 145
 - rails, 144
 - rings, 144
 - trough, 225
 - urinal, 226
 - wall ties, 123
 - wc
 - pan, 224
- Stain on timber, 219
- Stair
 - lift, 264
 - nosing, 215
 - tread protection, 99

Staircases
 concrete
 all-up, 47
 steel, 47, 143
 spiral, 47, 143
 timber, 47
STAIRCASES
 concrete, 47
 Estimating - Comparative Costs, 27
 spiral, 47
 steel framed, 47
 timber, 47
 Stamp duty, refer Notices and Fees, 75-93
 Standard framing anchor, 169
 Static line roof safety system, 146
Steel
 access
 ladder, 141
 acoustic ceilings, 61, 207
 angle
 guards, 138
 ant capping, 124
 balustrades, 143
 bollards, 105
 clad doors, 184
 covers and gratings, 139
 crash and guard rails, 140
 door frames, 180
 fencing, 105, 106
 flagpole, 140
 formwork, 115
 framed
 partitions, walls, 51, 206
 roof, 48
 staircase, 47
 girts, 134, 135
 handrails, 144
 holding down bolts, 136
 hollow sections, 134
 ladder, 141
 ladders, 141
 lintels, 124
 lockers, 141
 louvred panels, 179
 nogging, 158
 palisade fence, 106
 piling, 102
 plate connections, 135
 portal frame, 134
 purlins, 135, 136
 purlins, girts, 135
 reinforcement, 110, 116, 117
 roofing, 192, 193
 roof trusses, 134
 sheet
 cladding, 142
 perforated, 142
 piling, 102
 shelving, 142
 brackets, 173
 framing strip, 173
 skirting, 143
 ducted, 252
 staircases, 47, 134, 143
 strap bracing, 151
 strip suspended ceilings, 61, 207
 structural steelwork, supply and erect, 134, 135

Steel (cont'd)
 stud, 158
 surface treatment, 136
 taper flange sections, 134
 tray formwork, 115
 universal sections, 134
 wall
 cladding, 51, 200
 framing, 51, 158
 wedge and grout, 136
 Stop cock
 box, 140
 Stopping bead, 205
 Stop, timber, 182
Storage
 floor heating, 250
 hot water
 systems, 227, 228
 units, 228
 sheds
 farm, 14, 15
 on-site, 71
 shelving, 142
 Stormwater drains, pipes and fittings, 239, 240
Stove
 circuit, 247
 cooking, 265
 hood, 266
S trap, 231
Strap
 bolt, 189
 bracing, 151
Strip
 drainage, 240
 footings
 all-up, 45
 heater, 249
 sunscreens, 187
 suspended ceiling
 metal, 61, 207
Stripping
 flooring, 96
 roof coverings, 96
 wall cladding and linings, 96
 wallpaper, 221
Structural
 flooring systems, precast concrete, 118
 steel casing, 111
 timbers, 150-155
STRUCTURAL STEELWORK, 134-136
 architectural, 134
 bolts, 136
 fixings, 136
 plate connections, 135
 proprietary purlins, girts, 135
 roof trusses, 134
 staircases, 134
 supply and erect, generally, 134, 135
 surface treatments, 136
 wedge and grout, 136
Struts, timber, 151
Stud
 anchor, 136
 framed walls
 demolition, 96
 steel, 51, 202, 206
 timber, 51, 150

Studs
 steel, , 158
 timber, 150
Subboard, 245
Sub-frame, timber, 180
Submains, 245
 disconnect, 97
Subsoil drains
 polyethylene, 240
 thermoplastic cored, 240
Substructure, Estimating - Comparative
 Costs, 45
 filling, 45
 footings, 45
 foundations, 45
 ground slabs, 45
 raft slabs, 45
 timber ground floor framing, 45
Sump
 brick, 242
 concrete, 242
 precast, 243
 cover, 139, 243
 grating, 139
 outlets, 200
 surface drainage system, 241, 242
Sun control
 blinds, 186
 canvas awnings, 187
 curtains, 186, 187
 louvres, 187
 shutters, 186
 strip, 187
Sunscreens
 external, 187
Surface
 drainage system, 241, 242
 finishes, concrete, 113
 hardeners
 aerated concrete, 119
 concrete, 113
 granolithic, 208
 treatment
 earthworks, 102
 paving, 102
 treatments
 steel, 136
Surgery, 15
Surrounds, matwells, 141
SUSPENDED CEILINGS, 207
 bulkheads, 207
 metal, 207
 mineral fibre, 207
 plasterboard, 207
 timber board, 207
Suspended floor slabs
 all-up, 46
 formwork, 114, 115
Swimming pools, 19
 safety fence, 106
Swing check valve, 230
Swinging frame clothes line, 139
Swiss roof tiles, 191
Switchboards, 245, 246
Switches, 246
Sydney Water fees, 93
Synagogue, 20
Synpave (Rebound) surfaces, 109
Synthetic turf, 109

T

- Tactile tiles, 211
- Take down
 - ceilings, 96
 - fences, 100
 - roofing, etc., 96
 - suspended ceilings, linings, 96
- Take out
 - air-conditioner, 97
 - built-in items, 97
 - counter/bench unit, 97
 - door frames, 97
 - doors, 97
 - sanitary fittings, 97
 - windows, 97
- Take up or strip floors and flooring, 96
- Tanking, 103, 194
- Tap
 - box, 140
 - generally, 228
 - hands free, 228
 - mono mixing, 228
- Taper flange steel sections, 134
- Tape wrapping, pipework, 236
- Taps, tap sets, 228
 - cost range, 229
- Tavern, 16
- Telephone
 - cable, 257
 - equipment, 251
 - executive type, 250
 - installation and connection, 250
 - key operated system, 251
 - line rental, 251
 - pre-conduiting, 250
 - site, 72
- Television
 - antenna, 251
 - cable, 257
 - closed circuit systems, 251
- Temporary
 - screens, 99
 - services, on-site, 72
- Tennis courts, 19
 - fencing, 106
- Tension wrench, hire, 272
- Termimesh, 103
- Termite control, 103
- Terracotta
 - air bricks, 124
 - floor tiles, 211
 - roof tiles, 191
 - tile sill, 125
- Terrazzo
 - paving, in situ/precast, 208
 - set, 189
 - skirtings, 60, 208
 - tiles, 208
- Testing and samples, concrete, 111
- Textured finishes, 204
- Thermoplastic cored drainage, 240
- Thermostatic mixing valve, 229
- Ties
 - timber, 151
 - wall, 125
- Tiles, tiles
 - acoustic plaster ceilings, 207
 - carpet, 212
 - cleaning, 99
 - cork, 214
 - cutter, hire, 272
 - marble, 132
 - metal acoustic ceilings, 207
 - mineral fibre ceilings, 207
 - plasterboard, ceilings, 207
 - rubber, 214
 - saw, hire, 272
 - sills, 125
- Tile, tiles
 - acoustic plaster ceilings, 61
 - anti slip treatment, 211
 - ceramic, 57, 210
 - concrete, roof, 191
 - cork, 59
 - fittings, 210
 - marble, 60
 - metal acoustic ceilings, 61
 - mosaic, 57, 59, 210
 - plasterboard, ceilings, 61
 - quarry, 59, 211
 - roofing, 191
 - rubber, 60
 - skirtings, 60, 211
 - terracotta
 - floor, 211
 - roof, 48, 191
 - terrazzo, 211
 - treads and risers, 211
 - vinyl, 60, 215
 - vitreous, 211
- TILING, NON RESILIENT, 210, 211
 - floor tiling, 210
 - wall tiling, 210
- Tilt-up wall panels, 118, 119
- Timber
 - architraves, 181
 - balustrade, 172
 - barge boards, 160
 - base material prices
 - carpentry, 147-149
 - joinery, 170
 - battens, 155, 159
 - beams, 150, 152, 153
 - laminated, 156, 157
 - bearers, carpentry, 150, 153
 - blocking, 150
 - boarding, 167
 - board, suspended ceiling, 207
 - carpentry, 150-169
 - ceiling
 - framing, 151, 153
 - joists, 151, 153, 154
 - ceilings, 61, 207
 - connectors, 169
 - cover moulds, 171
 - cupboards and fittings, 173-176
 - decking, 163
 - pencil rounded, 163
 - reeded, 163
 - door frames, linings, 180
 - doors, 55, 182, 183
 - eaves framing, 155
 - engineered joist, 150, 153
- Timber (cont'd)
 - fascias, 160
 - fencing, 105
 - fibreboard, 164
 - fillets, 182
 - flat roof framing, 155
 - floor framing, 45, 46, 150, 153
 - filling openings, 98
 - flooring
 - air thrust, 164
 - decking, 163
 - fibre cement, 162
 - flooring system, 164
 - hardboard, 59, 162
 - laminated, 163
 - parquetry
 - block, 59, 163
 - mosaic, 59, 163
 - particle board, 59, 162
 - plywood, 59, 162
 - reeded decking, 163
 - tongued and grooved, 59, 162
 - filling openings, 98
 - framed roof, 48, 151, 154
 - glazed screens, 179
 - glazing beads, 182
 - ground floor framing, 45, 150, 153
 - grounds, 159
 - gutter boarding, 151
 - handrails, 172
 - hangers, 151, 154
 - hat and coat rail, 171
 - hip board, 151
 - joists, 150-154
 - laminated beams, 156, 157
 - linings
 - boarding, 167
 - caneite, 164
 - lintels, 151
 - log barrier, 108
 - louvred shutter, 186
 - noggings, 151
 - pelmet, 171
 - pencil rounded decking, 163
 - pergola framing, 155
 - pitched roof framing, 154
 - planks, scaffolding, 69
 - plates, 150, 151
 - plywood, 166, 167
 - posts, 152
 - purlins, 151, 154
 - quadrant fillet, 171
 - rafter, 151, 154
 - reeded decking, 163
 - ridge, 151
 - roof
 - framing, 151, 154, 155
 - trusses, 155
 - scotia, 171
 - seat battens, 172
 - shelving, 173
 - shingles, 195
 - shutters, 186
 - skirting, 60, 171, 172
 - staircases, 47, 172
 - stops, 182
 - structural, 150-155
 - struts, 151
 - studs, 150
 - ties, 151
 - trusses, 155
 - upper floor framing, 46, 150, 153
 - valley board, 151
 - venetian blinds, 186

Timber (cont'd)
 wall
 fibre cement, 165
 framing, 51, 150-154
 hardboard, 166
 particle board, 166
 plywood, 166, 167
 shiplap panelling, 51, 167
 timber boarding, 167
 tongued and grooved, 167
 weatherboarding, 51, 167
 windows, 178
 frames, 180
 Tip fees, 97
 Toilet
 accessories, 144-146
 buildings, 14, 18
 chemical pan, 71
 partitions/screens
 compressed fibreboard, 202
 particle board, 202
 roll holders, 145
 seats, 224
 site, 71
 terrazzo set, 189
 tissue dispenser, 145
 Tongued and grooved
 flooring, 59, 162
 wall lining, 164, 167
 Toothing and bonding, 123
 Toppings, self levelling, 208
 Top soil filling, 107
 Toughened glass, 216, 217
 Towel
 dispenser, 145
 rail, 144
 rings, 144
 waste cabinet, 145
 Town house, 22
 TPI cable, 254
 Tracks
 curtain, 187
 sliding doors, 190
 Traffic lines, refer road marking, 105
 Translucent fibreglass
 roofing, 192
 sectional overhead doors, 185
 TRANSPORTATION SYSTEMS, 264
 dumbwaiter, 264
 passenger lifts, 264
 platform lift, 264
 service lift, 264
 stair lift, 264
 Traps, plumbing, P or S, 231
 Tread
 nosings, 215
 protection, 99
 safe treatment, 211
 Tree
 cutting, 100
 grilles, 108
 guards, 108
 planting, 108
 Trench
 covers, 140
 drainage, 238
 excavation
 general, 101
 gratings, 140
 mesh, 117
 Trestles, hire, 272
 Trimming
 ground, 102
 rock, 102

Troughs, laundry, 225
 Trunking, pvc, 252
 Trusses
 steel, 134
 timber, 155
 Tube
 formed columns, 46
 formers, 115, 116
 Tubular
 balustrade, 143
 deadbolt, 188
 fencing, gates, 106
 handrails
 aluminium, 143, 144
 stainless steel, 144
 steel, 144
 scaffolding, 69
 structural steelwork, 136
 Tumble dryer, 265
 Turf
 cutting, 100
 laying, 107
 roll type, 107
 synthetic, 109
 TV
 antenna, 251
 cable, 256
 closed circuit system, 251

U

Underfloor heating, 250
 Underground
 conduits, 253
 mains, 245
 Underlay
 carpet, 212
 fibre cement, 162
 foam, 212
 polythene, 104
 rubber, 212
 self levelling, 208
 Universal
 beams, 134
 columns, 134
 Upper floor framing timber, 46, 150, 153
 Upper floors, Estimating - Comparative
 Costs, refer Columns, Upper Floors, 46
 Urinal, 226

V

Vacuum
 cleaning system, ducted, 266
 Valley
 boards, timber, 151
 gutters, 199
 Valuing buildings for insurance, 307
 Valves, 229
 mixing, 229
 reduced pressure zone device, 230
 Vandal resistant board, 165
 Vanity
 basins, 223
 Venetian blinds, 186
 integral, 178
 Ventilated rooflight, 193
 Ventilation, mechanical, costs/sqm, 260

Ventilator, ridge, 201
 Vent pipes, fittings
 cast iron, 231, 232
 copper, 232, 233
 pvc, 233
 Verge, bedding and pointing, 191
 Vergola roofing system, 201
 Vermiculite
 planting mixture, 108
 plaster, 61, 205
 Vermin proofing, 103
 Vertical blinds, 186
 Vibrator, hire, 270
 Video, CCTV and intercom, 251
 Vinyl
 diminishing strip, 215
 fabric, 58, 222
 kickplate, 189
 push plate, 189
 sheet flooring, 60
 acoustic, 61, 214
 skirtings, 60, 214
 tiles, semi-rigid, 60, 214
 tread nosing, 215
 Vitreous
 china sanitary fixtures, 223-226
 tiles, 211
 tile skirting, 60

W

WAGE RATES, 269
 Wall
 basin, 223
 block, 126
 bluestone, 133
 brick, 122
 brickwork, 50, 122
 cistern, 224
 cladding, facing
 aluminium, ribbed, 200
 blockwork, 51
 brickwork, 50
 curtain walling, 178
 fibre cement, 51, 164, 165
 fibreglass, corrugated, 200
 granite, 131
 hardboard, exterior, 166
 limestone, 131
 marble, 132
 sandstone, 131
 shop fronts, 179
 slate, 132
 steel, corrugated, ribbed, 51, 200
 stripping, 96
 timber, generally, 51, 165-167
 earth, 130
 fan, 250
 finishes
 ceramic tile, 57, 210
 concrete surface finishes, 113
 fabric coverings, 58, 222
 mosaic, 210
 mosaic tile, 57
 painting, 58, 219, 220
 plaster, 57, 203
 plasterboard, 57, 205
 render, 57, 203
 textured finish, 204
 wallpaper, 57, 222
 formwork, 114, 115

- Wall (cont'd)
 - framing
 - steel, 51, 206
 - timber, 51, 150-154
 - linings
 - boarding, 164-167
 - caneite, 164
 - fibreboard, 164
 - fibre cement, 51, 164, 165
 - hardboard, 166
 - particle board, 166
 - plasterboard, 52, 57, 205
 - plywood, 166, 167
 - stripping, 96
 - timber boarding, 51, 167
 - panels
 - precast concrete, 117
 - tilt-up, 118, 119
 - rammed earth, 130
 - sawing, concrete, 114
 - ties, 125
 - tiles, 57, 210
 - hack off, 96
- Wall finishes, internal, Estimating - Comparative Costs, 57, 58
- painting, 58
- paper hanging, 57, 58
- plaster, 57
- plasterboard, 57
- render, 57
- tile, 57
- Wallpaper, 57, 222
 - stripping, 222
- Walls
 - aerated concrete
 - blocks, 53
 - panels, 119
 - block, 50, 51, 54
 - brick, 50, 53, 54
 - concrete
 - all-up, 50
 - formwork, 114, 115
 - sawing, 114
 - curtain, 178
 - cutting openings, 98
 - demolition, 95
 - framed, 51, 202
 - glass, squash courts, 18
 - limestone, 131
 - masonry, 131
 - operable, 202
 - parapet, 49
 - protection, 99
 - retaining, 107
 - sandstone, 131
 - screen, 107
 - stud framed, 51, 202
 - framing, 150, 153, 154
 - tilt-up, 118, 119
- Warehouse buildings, 16
- Washing machine
 - dish, 265
 - laundry, 265
 - set, 228
- Waste
 - disposal, 266
 - floor, 231
 - gratings, 231
 - pipes, fittings
 - cast iron, 231, 232
 - copper, 232, 233
 - pvc, 233
 - shower, 231
- Water
 - based epoxy paint, 220
 - closets, 224
 - coolers, 226
 - Corporation fees (Perth), 89
 - heaters, refer Hot Water Unit, 227, 228
 - pipes, fittings
 - copper, 234
 - pipe insulation, 236
 - polyethylene, 235
 - pvc, 236
 - supply mains, 234, 235, 236
 - tank, hire, 272
 - wash exposed aggregate finish, 113
- Waterproofing, 103
 - agents, 111
 - applications to concrete
 - aerated concrete, 119
 - concrete, 113
 - silicone, repellent, 220
- Waterstops, 112
- Wax polish, , 162
- WC
 - pan, 224
 - suite, 224
- Weather bars, 209
- Weatherboarding, 51
- Wedge and grout, 136
- Weed control, 103
- Welded mesh fencing, 106
- Welding equipment, hire, 271
- Wheelchair lift, 264
- Window
 - fan, 250
- Windows
 - aluminium
 - commercial standard, 178
 - curtain walling, 178
 - domestic standard, 177
 - shop fronts, 179
 - timber sub-frame, 180
- Windows (cont'd)
 - blinds, 186
 - catches, fasteners, 189
 - cleaning, 99
 - curtains, 186, 187
 - frame, timber, 180
 - glass blocks, 129
 - glazed screens, 179
 - insect screens, 180
 - locks, 188
 - louvred
 - panels, 179, 180
 - windows, 180
 - patent glazing, 179
 - preparatory work, repairs, 98
 - protective treatments, 177
 - roof, 196
 - solar control film, 218
 - sunscreens, 187
 - taking out, 97
 - timber domestic, 178
- WINDOWS AND DOORS, 177-187
 - curtains and blinds, 186, 187
 - curtain walling, 178
 - door frames, linings, etc.
 - metal, 180
 - timber, 180-182
 - doors
 - accordion, 185
 - fire, 185
- WINDOWS AND DOORS (cont'd)
 - doors (cont'd)
 - metal, 184, 185
 - aluminium, 184
 - disabled persons, 184
 - roller doors, 184, 185
 - sectional overhead, 185
 - security, domestic, 185
 - sheet steel clad, 184
 - timber, 182, 183
 - feature, 183
 - framed and ledged, 183
 - glazed, 183
 - hollow core, 182
 - solid core, 183
 - glazed screens, 179
 - insect screens, 180
 - louvred panels and windows, 179, 180
 - patent glazing, 179
 - protective treatments, 177
 - shop fronts, 179
 - sunscreens, 187
 - canvas awnings, 187
 - fixed louvres, 187
 - horizontal strips, 187
 - windows, etc.
 - aluminium
 - curtain walling, 178
 - shop fronts, 179
 - windows, 177
 - timber, 180
 - Winter film, glass, 218
 - Wired glass, 216
 - Witches hat, hire, 272
 - Wood
 - bark, 108
 - chips, 108
 - Workplace, Health and Safety Regulations (Brisbane), 81
 - Wrench
 - tension, line, 272

X

Xypex Admix, 111

Z

- Zinc
 - flashings, 197
 - phosphate treatment
 - structural steel, 136
 - phosphat treatment
 - primer, 220
 - rainwater goods, 199, 200
 - silicate treatment
 - metalwork, 137
 - structural steel, 136
 - sump outlet, 200
- ZINCALUME® steel
 - box gutter, 199
 - colour coated rainwater goods, 198, 199
 - downpipes, 198
 - flashings, 197
 - penetrations, 196
 - gutters, 198, 199
 - rainwater goods, 197-199
 - roofing, 192, 193
 - slip joint, 128
 - sump outlet, 200
 - wall cladding, 200
- ZINCANNEAL® steel
 - door frames, 180