



---

To: **Scott Beedie BURPI** Company: **Urban Solutions**  
From: **Sam Ziemann, P.Eng.** Project Ref. #: **221655**  
c.519-404-4529  
Copy: Date: **October 14, 2022**  
Subject: **117 Forest Avenue & 175 Catherine Street South Watermain Hydraulic Analysis**

---

*The contents of this memorandum are intended only for the recipient. Any other use and/or reproduction without prior consent of C3 Water Inc. is strictly prohibited.*

---

**Urban Solutions**

**117 Forest Avenue & 175 Catherine Street South  
Watermain Hydraulic Analysis**

**C3 WATER INC.**

**October 14, 2022**



VERSION	DATE	DESCRIPTION OF REVISIONS	REVISED BY	REVIEWED BY
1	September 2, 2022	Draft Report	Alec Orr	Sam Ziemann
2	October 14, 2022	Final Report	Alec Orr, Michelle Scott	Sam Ziemann

**SIGN OFF**

This document, entitled “**117 Forest Avenue & 175 Catherine Street South Watermain Hydraulic Analysis**”, was prepared by C3 Water Inc. for **Urban Solutions**

C3W certifies that the information contained in this report is accurate, complete and in accordance with the terms of our engagement. This assessment is based, in part, on information provided by others. Unless specifically noted, C3W has assumed that this information is correct, and has relied on it in the development of conclusions.

The material herein reflects C3 Water’s best judgement based upon the information available at the time of preparation. Any use which a third party makes of this report or any reliance on or decisions made based on it, are the responsibilities of such third parties. C3 Water Inc. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based upon this report.

DATE:           October 14, 2022

Prepared by: **Alec Orr, B.A.Sc., E.I.T.**  
**Water Specialist**, C. 226-339-6822

Reviewed by: **SAM ZIEMANN, P.Eng.,**  
**PRESIDENT**, C. 519-404-4529



## Table of Contents

1.0	Introduction .....	1
1.1	Background.....	1
1.2	Limitations.....	2
2.0	Criteria .....	2
2.1	Pressure Requirements .....	2
2.2	Domestic Demand .....	2
2.3	Fire Flow Demand .....	3
3.0	Hydraulic Water Model.....	3
3.1	Boundary Conditions.....	3
3.2	Model Verification .....	4
3.2.1	Dual Hydrant Test Results .....	8
3.3	Development.....	9
4.0	Analysis .....	9
4.1	Available Fire Flow .....	9
4.2	System Pressures.....	10
4.3	Flushing .....	11
5.0	Conclusions .....	12

## List of Figures

Figure 1-1.	Proposed Development Area (Approximate) .....	1
Figure 3-1.	Field Testing Hydrant used for Model Verification .....	5
Figure 3-2.	Verification Results - Hydrant HA15H025 on Forest Avenue .....	7
Figure 3-3.	Verification Results - Hydrant HA15H027 on Young Street.....	7
Figure 3-4.	Model Layout for the Proposed Development Area.....	9



## List of Tables

Table 2-1. Pressure Requirements .....	2
Table 2-2. Estimated Domestic Demands for the Proposed Development (SLA) .....	3
Table 2-3. Hamilton Residential Fire Flow Requirements .....	3
Table 3-1. Model Boundary Conditions – Base Configuration .....	3
Table 3-2. Hydrant Field Testing Results – HA15H025 – July 21, 2022 .....	4
Table 3-3. Hydrant Field Testing Results – HA15H027 – July 21, 2022 .....	4
Table 3-4. Summary of Boundary Conditions at Time of Hydrant Testing .....	5
Table 3-5 Theoretical Fire Flows at Hydrants HA15H025 and HA15H027 at 20 PSI .....	8
Table 3-6 Summary of Hydrant and Model Data for Dual Hydrant Tests .....	8
Table 4-1. Available Fire Flow Results (L/s) for the Proposed Development .....	10
Table 4-2. Pressure Results (kPa) with Tanks Set at 50% .....	11
Table 4-3. Pressure Results (kPa) with Tanks Set at 75% .....	11
Table 4-4. Flushing Results with Tanks set to 50% (ADD 2021) .....	11

## List of Appendices

<b>APPENDIX A</b>	Site Plan
<b>APPENDIX B</b>	Field Testing Report
<b>APPENDIX C</b>	Model Verification – C-factor Change Log
<b>APPENDIX D</b>	Fire Flow Results
<b>APPENDIX E</b>	System Pressures
<b>APPENDIX F</b>	Flushing Results

## 1.0 INTRODUCTION

### 1.1 Background

The proposed development at 117 Forest Avenue & 175 Catherine Street South is located in Pressure District 2 (PD2) in the City of Hamilton (City). The development area is located on the northeast corner of the intersection between Forest Avenue and Catherine Street South. Figure 1-1 illustrates the proposed development area and nearby watermain, all of which are cast iron (CI). The development includes a 14-storey multiple dwelling building in addition to the existing 11-storey building located on the subject lands. The development area is currently supplied by a 300 mm watermain on Forest Avenue and a 150 mm watermain on Catherine Street South. A site plan is available in Appendix A.



**Figure 1-1. Proposed Development Area (Approximate)**

PD2 is supplied by Pressure District 1 through pumping station HD002, which consists of four (4) pumps. PD2 has two (2) storage reservoirs HDR02 and HDR2A that provide storage.



C3 Water Inc (C3W) has been retained by Urban Solutions to complete a watermain hydraulic analysis for the proposed development. This report provides the watermain hydraulic analysis in accordance with the City of Hamilton’s Comprehensive Development Guidelines (2018) (Hamilton Guidelines) and the Ministry of Environment, Conservation and Parks (MECP) Design Guidelines for Drinking-Water Systems (2008) (MECP Guidelines). The hydraulic assessment was completed using the City’s full pipe model, titled “Hamilton\_EPS\_200625\_include\_PD9\_10” using Bentley WaterCAD Connect Edition Update 3 10.03.02.75 software.

**1.2 Limitations**

This TM is intended to provide servicing results for the proposed development based on the City’s hydraulic water model. This water model was built and coarsely calibrated by others. As with any modelling assignment, limitations related to the state of the model, the software capabilities, and theoretical data inputs should be considered. The model software also has inherent limitations and assumptions related to the calculation engine and inputs.

**2.0 CRITERIA**

**2.1 Pressure Requirements**

The MECP Guidelines outline maximum and minimum system pressures for standard operating conditions as well as fire flow conditions. As outlined in the City of Hamilton’s Water and Wastewater Masterplan (KMK, 2006), acceptable hydrant and service connection pressures under normal conditions range from 275 kPa to 690 kPa. Standard operating conditions were assessed for the proposed development to ensure that water services maintained acceptable pressure under various demand and fire flow conditions for existing (2021) and future (2031) scenarios. Table 2-1 provides the pressure criteria that were utilized.

**Table 2-1. Pressure Requirements**

<b>Pressure Requirement</b>	<b>Minimum</b>	<b>Preferred</b>	<b>Maximum</b>
Standard Operating Conditions	275 kPa (40 psi)	350 to 480 kPa (50 to 70 psi)	690 kPa (100 psi)
Maximum Day Demands + Fire Flows	140 kPa (20 psi)		

**2.2 Domestic Demand**

The domestic demands for the proposed development were calculated by S. Llewellyn & Associates Limited (SLA) using the Ontario Building Code (OBC) fixture unit method. Demands are only for the new 14-storey multiple dwelling building as it was assumed that the demands for the existing building were already accounted for in the City’s existing water model. The ADD, MDD and PHD for the development are summarized in Table 2-2.



**Table 2-2. Estimated Domestic Demands for the Proposed Development (SLA)**

Development	Demand (L/s)		
	ADD	MDD	PHD
117 Forest Avenue	1.96	5.39	8.09

### 2.3 Fire Flow Demand

The fire flow requirements for the proposed development were estimated by the Hamilton Watermain Fire Flow Requirement Design Guidelines Policy (PW19096). The City’s residential fire flow requirements are summarized in Table 2-3 below. The development is required to meet a minimum fire flow of 150 L/s at a residual pressure of 140 kPa under MDD conditions, as specified in Table 2-1.

**Table 2-3. Hamilton Residential Fire Flow Requirements**

Development Type	Target Fire Flow (L/s)
<b>Residential Multi (&gt; 3 Units)</b>	<b>150</b>
Residential Medium (≤ 3 Units)	125
Residential Single	75
Residential Single (Dead End)	50

## 3.0 HYDRAULIC WATER MODEL

### 3.1 Boundary Conditions

The proposed development was modelled under the following demand scenarios under both existing (2021) and ultimate build-out (currently 2031) conditions:

- Average Day Demand (ADD)
- Maximum Day Demand (MDD)
- MDD plus Fire Flow
- Peak Hour Demand (PHD)

Table 3-1 summarizes the initial boundary conditions set up in the model for PD2. The pumps at the water treatment plant (WTP) were turned off (reservoir only conditions). All pumps at pump station HD002 were turned off. The tank levels for reservoirs HDR02 and HDR2A were set to 50% full (144.33 m) and 75% full (146.08 m), respectively, as specified by the City.

**Table 3-1. Model Boundary Conditions – Base Configuration**

Element	Initial Status – HGL	
PD2 Tank Levels	144.32 m (50%)	146.08 m (75%)
WTP Pumps	<b>Off</b>	<b>Off</b>



Element	Initial Status – HGL	
HD002-PMP-1	Off	Off
HD002-PMP-2	Off	Off
HD002-PMP-3	Off	Off
HD002-PMP-4	Off	Off

### 3.2 Model Verification


The accuracy of the model in the area of the proposed development was verified using hydrant field test results, completed by SCG Flowmetrix on July 21, 2022. The hydrant field test results for Forest Avenue and Young Street are summarized in Table 3-2 and Table 3-3. Figure 3-1 provides the location of the residual and flow hydrants that were used for verification. Pressures were measured at the residual hydrants. Two hydrant ports were opened at each flow hydrant during the hydrant tests. The hydrant testing reports are available in Appendix B.

**Table 3-2. Hydrant Field Testing Results – HA15H025 – July 21, 2022**

Forest Avenue	
Flow (L/s) at Hydrant HA15H025	Pressure (kPa) at Hydrant HA15H026
0	435
61.33	414
Theoretical Flow at 20 psi	
253.98	140

**Table 3-3. Hydrant Field Testing Results – HA15H027 – July 21, 2022**

Young Street	
Flow (L/s) at Hydrant HA17H027	Pressure (kPa) at Hydrant HA017028
0	435
34.96	410
Theoretical Flow at 20 psi	
134.21	140



**Figure 3-1. Field Testing Hydrant used for Model Verification**

PD2 SCADA data was requested from the City to determine the boundary conditions during the field testing. A summary of the boundary conditions used for model verification is provided in Table 3-4. The model was compared to the hydrant test results under 2021 ADD conditions.

**Table 3-4. Summary of Boundary Conditions at Time of Hydrant Testing**

Element	Flow Hydrant	Flow Hydrant
	HA15H025	HA15H027
Time of Test	12:00 PM	11:30 AM
Average Tank HDR02 Level	143.70 (41%)	143.66 m (41%)
Average Tank HDR2A Level	144.31 (50%)	144.28 m (49%)



Element	Flow Hydrant	Flow Hydrant
	HA15H025	HA15H027
WTP Pump 1	Off	Off
WTP Pump 2	On	On
WTP Pump 3	On	On
WTP Pump 4	Off	Off
WTP Pump 5	On	On
WTP Pump 6	Off	Off
HD002-PMP-1	Off	Off
HD002-PMP-2	Off	Off
HD002-PMP-3	Off	Off
HD002-PMP-4	On	On
PD2 Discharge Flow – Average (L/s)	455	456


Figure 3-2 and Figure 3-3 illustrate the field test and model verification results for the hydrants on Forest Avenue (HA15H025) and Young Street (HA15H027). Field results beyond maximum testing flows are extrapolated. The focus of the model verification was on the drop in pressure caused by the hydrant test.

When using the original C-factors in the City’s model, the pressure drop caused by the hydrant flows on Forest Avenue and Young Street were found to be significantly less than what was recorded in the field. C-factors were adjusted in the model such that the model results more closely represented the field test results. In general, the C-factors for the existing 150-300 mm CI watermains between the PD2 pump station (HD002) and the development area were reduced from between 80 and 130 to between 20 and 25. A detailed C-factor change log can be found in Appendix C.


The C-factor changes were made to the model to provide a better fit to the field tests. In C3W’s opinion the C-factor adjustments required to match the field testing data are lower than expected as a C-factor of 20 is very conservative for a CI pipe. There may be other factors involved in the limited hydraulic capacity of the system that could be considered such as accuracy of data such as watermain diameters, valve status, system connectivity and other C-factors throughout the PD2 zone.

Additionally, the theoretical fire flows at 140 kPa (20 psi) on Forest Avenue and Young Street were extrapolated based on only a 21 kPa (3.1 psi) and 25 kPa (3.6 psi) difference, respectively, between the field testing static and residual pressures. Typically, it is recommended that a 25% drop in pressure be required to adequately estimate the pressures at 20 psi. Pressure drops of 109 kPa (15.8 psi) would be required at both hydrants to satisfy this recommendation, based on the field testing static pressures.

The model was updated to best match the field results within reasonable accuracy, and the adjusted C-factors were used for the remaining analysis.



**Figure 3-2. Verification Results - Hydrant HA15H025 on Forest Avenue**



**Figure 3-3. Verification Results - Hydrant HA15H027 on Young Street**



### 3.2.1 Dual Hydrant Test Results

Additional hydrant tests were completed by SCG Flowmetrix on September 13, 2022, that involved running hydrants HA15H025 and HA15H027 simultaneously on Forest Avenue and Young Street, respectively. The residual pressures were measured at hydrants HA15H026 and HA15H028 on Forest Avenue and Young Street, respectively, during the tests. The purpose of the tests were to confirm the fire flow near the development when a second nearby hydrant was flowing in the distribution system. The theoretical fire flows at hydrants HA15H025 and HA15H027 at 20 PSI with one (1) and two (2) hydrants running are summarized in Table 3-5. With a second hydrant running, the fire flow near the development drops by approximately 20 L/s. The additional hydrant testing results are included in Appendix B.

**Table 3-5 Theoretical Fire Flows at Hydrants HA15H025 and HA15H027 at 20 PSI**

Hydrant	Theoretical Flow at 20 PSI (1 hydrant running)	Theoretical Flow at 20 PSI (2 hydrants running)
HA15H025	253.98 L/s	235.14 L/s
HA15H027	134.21 L/s	113.06 L/s

The additional hydrant testing data was also used to confirm the model verification results. Table 3-6 summarizes the residual pressures and flows during both hydrant tests as well as the residual pressures estimated by the model at the field tested flows. The model boundary conditions were updated to reflect system conditions on September 13, 2022. The model results were more conservative than the field test results for the range of flows seen during both tests. This was also shown by the original model verification results in Figure 3-2 and Figure 3-3.


**Table 3-6 Summary of Hydrant and Model Data for Dual Hydrant Tests**

Hydrant Test	Residual Hydrant	Flow at Hydrant HA15H025 (L/s)	Flow at Hydrant HA15H027 (L/s)	Total Flow (L/s)	Field Test Residual Pressure (PSI)	Model Residual Pressure (PSI)
1	HA15H026	61.7	32.2	93.9	62.6	61.0
2	HA15H028	58.2	33.1	91.3	61.3	57.0

### 3.3 Development

Figure 3-4 illustrates the location of the proposed development. The development will be serviced by a connection on the existing 300 mm watermain on Forest Avenue.

The elevation of the development node (J-471) was estimated using Hamilton’s existing water model and the elevations of the surrounding nodes. The elevation of the demand node is 102.34 m.



**Figure 3-4. Model Layout for the Proposed Development Area**

## 4.0 ANALYSIS

### 4.1 Available Fire Flow

The model was used to determine the available fire flow at the development node (J-471) and the existing hydrant on Forest Avenue (HA15H025).



Table 4-1 summarizes the available fire flows at the development node (J-471) and the existing hydrant on Forest Avenue (HA15H025) under MDD 2021 and 2031 conditions, at a residual pressure of 140 kPa, and HDR02 and HDR2A tank levels set at 50% and 75%. The minimum available fire flow of 150 L/s can be achieved at the development node and existing hydrant on Forest Avenue (HA15H025) under all scenarios. The complete fire flow results are available in Appendix D.

The fire flow results in the model are lower than the field testing results due to pressure and flow being measured at different hydrants during the field test. The headlosses in the watermain between the two (2) hydrants is not accounted for in the field test since the pressure is not measured at the flow hydrant. In the model analysis, both the flow and pressure are measured at the same hydrant so the headlosses associated with the low C-factor in the existing 300 mm watermain on Forest Avenue are included in the calculation. Due to the low C-factor, there is a high headloss in this section of pipe which results in a lower available fire flow.

**Table 4-1. Available Fire Flow Results (L/s) for the Proposed Development**

Node	2021		2031		Meets FF Criteria?
	Tank Level				
	50%	75%	50%	75%	
HA15H025	178	185	168	175	TRUE
J-471	170	177	163	169	TRUE

#### 4.2 System Pressures

The pressure results for the development node (J-471) and the existing hydrant on Forest Avenue (HA15H025) are summarized in Table 4-2 and Table 4-3 with PD2 tank levels set to 50% and 75%, respectively, and the PD2 and WTP pumps off. Under each of the scenarios, the pressures ranged between 376 kPa – 424 kPa, which are within the City’s allowable operating pressure range of 275 – 690 kPa. The complete system pressure results are included in Appendix E.



**Table 4-2. Pressure Results (kPa) with Tanks Set at 50%**

Node	ADD		MDD		PHD	
	2021	2031	2021	2031	2021	2031
HA15H025	404	404	396	393	383	376
J-471	407	406	398	395	386	379

**Table 4-3. Pressure Results (kPa) with Tanks Set at 75%**

Node	ADD		MDD		PHD	
	2021	2031	2021	2031	2021	2031
HA15H025	422	421	413	410	401	394
J-471	424	423	416	412	403	396

### 4.3 Flushing

The hydraulic model was used to evaluate the flushing capacity in the existing 300 mm watermain on Forest Avenue, with PD2 tank levels set at 50% full and the PD2 and WTP pumps offline. The 2021 ADD scenario was used to represent existing conditions for construction flushing requirements. Flushing demands were modelled to replace domestic demands while the area is under development. Results were based on a minimum velocity of 0.8 m/s as required by the MECP Guidelines. Hydrant nodes were modelled with an emitter coefficient of 11.2 L/s/m<sup>0.5</sup> (150 gpm/psi). This value is recommended by the American Water Works Association (AWWA) to represent a single 60mm (2.5”) outlet and considers all lateral valve and bends within the hydrant.

Table 4-4 summarizes the flushing results for the existing 300 mm watermain on Forest Avenue. A flushing velocity of 0.8 m/s was achieved in the existing 300 mm watermain when the tank levels are set to 50%. The complete flushing report is available in Appendix F.

**Table 4-4. Flushing Results with Tanks set to 50% (ADD 2021)**

Pipe	Length (m)	Diameter (mm)	Flushing Velocity (m/s)	Meets Criteria
HA15W12654(1)(2)(1)	20	300	1.12	TRUE
HA15W12654(1)(2)(2)	123	300	1.09	TRUE



## 5.0 CONCLUSIONS

This analysis was based on the City's existing hydraulic water model. The model was verified using field test results and the City's historical SCADA data. The C-factors of the watermains near the development area were adjusted to provide a closer representation of the hydraulic capacity of the water system based on field testing data provided. Lower than expected C-factors were required on the CI watermains near the development area to better match the model results to the field testing.

The watermain hydraulic assessment of the proposed 117 Forest Avenue & 175 Catherine Street South development demonstrated that:

1. Under the proposed development conditions, the minimum available fire flow requirement of 150 L/s was achieved at the development node (J-471) and the existing hydrant on Forest Avenue (HA15H025) under MDD 2021 or MDD 2031 conditions.
2. The service pressures under existing conditions, and ultimate build-out (currently 2031\*) conditions are within the standards established by the MECP and City of Hamilton Guidelines. Under the proposed development conditions the pressures are expected to range between 376 kPa – 424 kPa.
3. The minimum flushing velocity of 0.8 m/s, as required by the MECP guidelines, can be achieved in the existing 300 mm watermain on Forest Avenue.

\* As amended from time to time as per Official Plan Report Content




## APPENDIX A – Site Plan

YOUNG STREET


SURVEY INFORMATION  
TAKEN FROM DRAWINGS  
PREPARED BY A.T.  
MCLAREN LIMITED ON  
AUGUST 10TH, 2021

KEY PLAN

175 CATHARINE ST S  
HAMILTON, ONTARIO



CATHARINE STREET SOUTH



**PARKING SUMMARY**

PARKING REQUIRED	RATIO	SPACES
RESIDENTIAL		
NEW BUILDING - 216 UNIT	0.62	130
EXISTING BUILDING - 92 UNIT	0.62	58
BARRIER-FREE		3
VISITOR		INCLUDED
TOTAL REQUIRED		191
PARKING PROVIDED		
RESIDENTIAL		
NEW BUILDING - 216 UNIT		161
EXISTING BUILDING - 92 UNIT		29
BARRIER-FREE		3
VISITOR		INCLUDED
TOTAL PROVIDED		193
SMALL PARKING		20
GRAND TOTAL PROVIDED		213

**UNDERGROUND GROSS FLOOR AREA**

Floors	Area
Not Placed	0.00 m <sup>2</sup>
UNDERGROUND LEVEL 3	861.66 m <sup>2</sup>
UNDERGROUND LEVEL 2	2,501.49 m <sup>2</sup>
UNDERGROUND LEVEL 1	2,892.48 m <sup>2</sup>
11th FLOOR	625.59 m <sup>2</sup>
12th FLOOR	625.59 m <sup>2</sup>
13th FLOOR	625.59 m <sup>2</sup>
14th FLOOR	625.59 m <sup>2</sup>
Total	8,758.00 m <sup>2</sup>

**SELLABLE/NON-SELLABLE AREAS**

Floors	Area
COMMON AREA	
1st FLOOR	76.12 m <sup>2</sup>
2nd FLOOR	76.12 m <sup>2</sup>
NON-SELLABLE	
1st FLOOR	333.33 m <sup>2</sup>
2nd FLOOR	157.88 m <sup>2</sup>
3rd FLOOR	157.88 m <sup>2</sup>
4th FLOOR	157.88 m <sup>2</sup>
5th FLOOR	165.84 m <sup>2</sup>
6th FLOOR	165.84 m <sup>2</sup>
7th FLOOR	92.05 m <sup>2</sup>
8th FLOOR	92.05 m <sup>2</sup>
9th FLOOR	92.05 m <sup>2</sup>
10th FLOOR	92.05 m <sup>2</sup>
SELLABLE	
1st FLOOR	776.40 m <sup>2</sup>
2nd FLOOR	1,175.06 m <sup>2</sup>
3rd FLOOR	1,175.06 m <sup>2</sup>
4th FLOOR	1,175.06 m <sup>2</sup>
5th FLOOR	1,056.14 m <sup>2</sup>
6th FLOOR	1,056.14 m <sup>2</sup>
7th FLOOR	699.59 m <sup>2</sup>
8th FLOOR	699.59 m <sup>2</sup>
9th FLOOR	699.59 m <sup>2</sup>
10th FLOOR	699.59 m <sup>2</sup>
11th FLOOR	74.00 m <sup>2</sup>
12th FLOOR	74.00 m <sup>2</sup>
13th FLOOR	74.00 m <sup>2</sup>
14th FLOOR	74.00 m <sup>2</sup>
UNDERGROUND	
11th FLOOR	625.59 m <sup>2</sup>
12th FLOOR	625.59 m <sup>2</sup>
13th FLOOR	625.59 m <sup>2</sup>
14th FLOOR	625.59 m <sup>2</sup>
GROSS FLOOR AREA	13,593.54 m <sup>2</sup>

**TOTAL CONSTRUCTABLE AREA**

Floors	Area
UNDERGROUND LEVEL 3	861.66 m <sup>2</sup>
UNDERGROUND LEVEL 2	2,501.49 m <sup>2</sup>
UNDERGROUND LEVEL 1	2,892.48 m <sup>2</sup>
1st FLOOR	1,185.85 m <sup>2</sup>
2nd FLOOR	1,332.94 m <sup>2</sup>
3rd FLOOR	1,332.94 m <sup>2</sup>
4th FLOOR	1,332.94 m <sup>2</sup>
5th FLOOR	1,221.98 m <sup>2</sup>
6th FLOOR	1,221.98 m <sup>2</sup>
7th FLOOR	791.64 m <sup>2</sup>
8th FLOOR	791.64 m <sup>2</sup>
9th FLOOR	791.64 m <sup>2</sup>
10th FLOOR	791.64 m <sup>2</sup>
11th FLOOR	699.59 m <sup>2</sup>
12th FLOOR	699.59 m <sup>2</sup>
13th FLOOR	699.59 m <sup>2</sup>
14th FLOOR	699.59 m <sup>2</sup>
Total	19,849.17 m <sup>2</sup>

**UNITS BREAKDOWN**

Level	1 BED UNITS	2 BED UNITS	TOTAL UNITS
1st FLOOR	11	3	14
2nd FLOOR	20	2	22
3rd FLOOR	20	2	22
4th FLOOR	20	2	22
5th FLOOR	19	1	20
6th FLOOR	19	1	20
7th FLOOR	11	1	12
8th FLOOR	11	1	12
9th FLOOR	11	1	12
10th FLOOR	11	1	12
11th FLOOR	0	1	1
12th FLOOR	0	1	1
13th FLOOR	0	1	1
14th FLOOR	0	1	1
TOTAL UNITS	153	19	172

CONTRACTOR MUST CHECK AND VERIFY ALL DIMENSIONS AND JOB CONDITIONS BEFORE PROCEEDING WITH WORK.  
ALL DRAWINGS MAY BE SUBJECT TO CHANGE DUE TO COMMENTS FROM MUNICIPAL DEPARTMENTS AND OTHER AGENCIES WITH AUTHORITY.  
ALL DRAWINGS AND SPECIFICATIONS ARE THE PROPERTY OF THE ARCHITECTS AND MUST BE RETURNED AT THE COMPLETION OF THE WORK.  
THE CONTRACTOR WORKING FROM DRAWINGS NOT SPECIALLY MARKED FOR CONSTRUCTION MUST ASSUME FULL RESPONSIBILITY AND BEAR COSTS FOR ANY CORRECTIONS OR DAMAGES RESULTING FROM HIS OR HER WORK.

**KEY TO DETAIL LOCATION**

No.	DETAIL NUMBER
No.	DRAWING SHEET NUMBER

DRAWING SETS ISSUED	No.	DATE (DD.MM.YY)	BY
ISSUED FOR SPA	1.	23.04.19	KNYMH
ISSUED FOR SPA	2.	10.05.21	KNYMH
SPA COMMENTS	3.	10.08.21	KNYMH
ISSUED FOR BP APPROVAL	4.	29.07.22	KNYMH


ALL PREVIOUS ISSUES OF THIS DRAWING ARE SUPERSEDED.

REVISIONS TO THIS DRAWING  
**NOT FOR CONSTRUCTION**

BUILDING PERMIT NUMBER:



KNYMH INC.  
1006 SKYVIEW DRIVE • SUITE 101  
BURLINGTON, ONTARIO • L7P 0V1  
T 905.639.6595  
F 905.639.0394  
www.knymh.com info@knymh.com



THIS DOCUMENT IS INCOMPLETE AND MAY NOT BE USED FOR REGULATORY APPROVAL PERMIT OR CONSTRUCTION AND ARE FOR USE BY CONSULTANTS, SUBCONSULTANTS, OWNER AND CONTRACTORS TO PROVIDE THEIR INPUT TO THE COORDINATION OF THIS DOCUMENT.

**BROCKTON APARTMENTS**  
175 Catharine St S  
Hamilton, Ontario

DRAWING SHEET TITLE:  
**SITE PLAN**

DRAWING SCALE:  
As indicated

PROJECT NUMBER:  
**21039**

DRAWN BY: MHT  
CHECKED BY: PM  
DRAWING SHEET NUMBER:  
**SP1.01**

PLOT DATE:  
2021-08-05



## APPENDIX B – Field Testing Report



**FLOWMETRIX**  
INDU-TECH  
PROCESS

## Fire Flow Testing Report

Residual Hydrant #  
NFWA Colour Code

**HA15H026**  
**BLUE**



DATE July 21, 2022  
TIME 12:00 PM

ADDRESS 146 Forest Avenue  
Hamilton, ON  
L8N 1X5

SIZE-inches/mm 8 300  
MATERIAL DI

CONTACT INFO Scott Beedie  
Urban Solutions  
(905) 546-1087  
[sbeedie@urbansolutions.info](mailto:sbeedie@urbansolutions.info)

### RESIDUAL HYDRANT INFO.


HYDRANT #	HA15H026
N.F.P.A. COLOUR CODE	BLUE
STATIC PRESSURE	63.1 psi
RESIDUAL PRESSURE - ONE PORT OPEN	60.2 psi
RESIDUAL PRESSURE - TWO PORTS OPEN	60.0 psi
PRESSURE DROP	3.1 psi
% PRESSURE DROP	4.9 % psi
Flow at Test Hydrant @ 20 psi	4025 USGPM

### FLOW HYDRANT(S) INFO.

HYDRANT ASSET ID	HYD. # PORTS	OUTLET DIAMETER (INCHES)	NOZZLE COEFFICIENT	DIFFUSER TYPE	DIFFUSER COEFFICIENT	PITOT READING (psi)	PITOT FLOW (USGPM)	FLOW METER (USGPM)
HA15H025	1	2.5	Round	LPD250	0.90	20.5	683	0
		2.5	Round	LPD250	0.90	10.4		0
HA15H025	2	2.5	Round	LPD250	0.90	10.4	972	0
		2.5	Round	LPD250	0.90	10.4		0

### FIRE FLOW CHART

Pressure - Flow Graph  
at Test Hydrant



### COMMENTS

OPERATOR FMX Jordan Whitlock  
OPERATOR Brendan Howatt  
OPERATOR City of Hamilton



**FLOWMETRIX**  
INDU-TECH  
PROCESS

# Fire Flow Testing Report

Residual Hydrant #  
N.F.P.A. Colour Code

**HA15H028**  
**BLUE**



DATE: July 21, 2022  
TIME: 11:30 AM

ADDRESS: 50 Young Street  
Hamilton, ON  
L8N 1V2

SIZE-inches/mm: 6 / 150  
MATERIAL: DI

CONTACT INFO: Laura Drennan  
Urban Solutions  
(905) 546-1087  
[ldrennan@urbansolutions.info](mailto:ldrennan@urbansolutions.info)

## RESIDUAL HYDRANT INFO.


HYDRANT #	HA15H028
N.F.P.A. COLOUR CODE	BLUE
STATIC PRESSURE	63.1 psi
RESIDUAL PRESSURE - ONE PORT OPEN	59.8 psi
RESIDUAL PRESSURE - TWO PORTS OPEN	59.5 psi
PRESSURE DROP	3.6 psi
% PRESSURE DROP	5.7 % psi
Flow at Test Hydrant @ 20 psi	2127 USGPM

## FLOW HYDRANT(S) INFO.

HYDRANT ASSET ID	HYD. # PORTS	OUTLET DIAMETER (INCHES)	NOZZLE COEFFICIENT	DIFFUSER TYPE	DIFFUSER COEFFICIENT	PITOT READING (psi)	PITOT FLOW (USGPM)	FLOW METER (USGPM)
HA15H027	1	2.5	Round	LPD250	0.90	9.7	471	0
HA15H027	2	2.5	Round	LPD250	0.90	3.4	554	0
HA15H027	2	2.5	Round	LPD250	0.90	3.4	554	0

## FIRE FLOW CHART

Pressure - Flow Graph  
at Test Hydrant



## COMMENTS

OPERATOR: FMX  
OPERATOR: Jordan Whitlock  
OPERATOR: Brendan Howatt  
City of Hamilton

# Fire Flow Testing Report



FLOWMETRIX  
INDU-TECH  
PROCESS

Residual Hydrant #  
NFPA Colour Code

**HA15H026**  
**BLUE**



## RESIDUAL HYDRANT INFO.

HYDRANT #	HA15H026
N.F.P.A. COLOUR CODE	BLUE
STATIC PRESSURE	66.5 psi
RESIDUAL PRESSURE	62.6 psi
PRESSURE DROP	3.9 psi
% PRESSURE DROP	5.9 % psi
Flow on Water Main at Test Hydrant @ 20 psi	3727 USGPM


DATE	September 13, 2022
TIME	12:00 PM
ADDRESS	146 Forest Avenue Hamilton, ON L8N 1X5
SIZE-inches/mm	8 300
MATERIAL	DI
CONTACT INFO	Scott Beedie Urban Solutions (905) 546-1087 <a href="mailto:sbeedie@urbansolutions.info">sbeedie@urbansolutions.info</a>

## FLOW HYDRANT(S) INFO.

FLOW HYDRANT ID	HYD. # PORTS	OUTLET DIAMETER (INCHES)	NOZZLE COEFFICIENT	DIFFUSER TYPE	DIFFUSER COEFFICIENT	PITOT READING (psi)	PITOT FLOW (USGPM)	FLOW METER (USGPM)
HA15H025	2	2.5	Round	LPD250	0.90	10.5	489	0
		2.5	Round	LPD250	0.90	10.5	489	0
HA15H027	2	2.5	Round	LPD250	0.90	3.1	266	0
		2.5	Round	Swivel	0.83	3.1	245	0
Total Flow (USGPM)							1490	0
Total Flow (USGPM)							1490	

## FIRE FLOW CHART

Pressure - Flow Graph  
at Test Hydrant



## COMMENTS

OPERATOR	FMX	Andrew Cheung
OPERATOR	FMX	Noushin Ahanrobay
OPERATOR		City of Hamilton



FLOWMETRIX  
INDU-TECH  
PROCESS  
WESTCAN

# Fire Flow Testing Report

Residual Hydrant #  
NFWA Colour Code

**HA15H028**  
**BLUE**



### RESIDUAL HYDRANT INFO.

HYDRANT #	HA15H028
N.F.P.A. COLOUR CODE	BLUE
STATIC PRESSURE	66.0 psi
RESIDUAL PRESSURE	61.3 psi
PRESSURE DROP	4.7 psi
% PRESSURE DROP	7.2 % psi

Flow on Water Main At Test Hydrant      20 psi      1792 USGPM

DATE      September 13, 2022  
TIME      12:30 PM

ADDRESS      50 Young Street  
Hamilton, ON  
L8N 1V2

SIZE-inches/mm      6      150  
MATERIAL      DI


CONTACT INFO      Scott Beedie  
Urban Solutions  
(905) 546-1087  
[sbeedie@urbansolutions.info](mailto:sbeedie@urbansolutions.info)

### FLOW HYDRANT(S) INFO.

HYDRANT ASSET ID	HYD. # PORTS	OUTLET DIAMETER (INCHES)	NOZZLE COEFFICIENT	DIFFUSER TYPE	DIFFUSER COEFFICIENT	PITOT READING (psi)	PITOT FLOW (USGPM)	FLOW METER (USGPM)
HA15H025	2	2.5	Round	LPD250	0.90	9.3	461	0
		2.5	Round	LPD250	0.90	9.3	461	0
HA15H027	2	2.5	Round	LPD250	0.90	3.0	262	0
		2.5	Round	LPD250	0.90	3.0	262	0
Total Flow (USGPM)							1445	0
Total Flow (USGPM)							1445	

### FIRE FLOW CHART

Pressure - Flow Graph  
at Test Hydrant



### COMMENTS

OPERATOR	FMX	Andrew Cheung
OPERATOR	FMX	Noushin Ahanrobay
OPERATOR		City of Hamilton



## APPENDIX C – Model Verification – C-factor Change Log

Model Verification - C-Factor Adjustment Log

ID	Label	Start Node	Stop Node	Street	Diameter (mm)	Material	Hazen-Williams C	Length (m)	Adusted c-factor
33453	HA15W12665(1)	HA15T024	HA15H037	Augusta	150	Cast Iron	80	5	22
33454	HA15W12665(2)	HA15H037	HA14C006	Augusta	150	Cast Iron	80	85	22
33460	HA15W12667(1)	HA15C011	HA15H036	Augusta	150	Cast Iron	80	120	22
33461	HA15W12667(2)	HA15H036	HA15T024	Young Street	150	Cast Iron	80	79	22
23632	HA15W12661	HA15C013	HA15C018	Catherine Street South	150	Cast Iron	80	100	25
33463	HA15W12662(1)	HA14C007	HA15H027	Young Street	150	Cast Iron	80	97	25
33464	HA15W12662(2)	HA15H027	HA15C013	Young Street	150	Cast Iron	80	89	25
33466	HA15W12670(1)	HA15R004	HA15H028	Young Street	150	Cast Iron	80	76	25
33467	HA15W12670(2)	HA15H028	HA15C013	Young Street	150	Cast Iron	80	9	25
23631	HA15W20308	HA15C013	HA15T041	Catherine Street South	150	Cast Iron	80	211	25
23667	HA14W12653	HA14V014	HA14C009	Forest Avenue	150	Cast Iron	80	1	20
23668	HA14W13250	HA14T011	HA14V014	Forest Avenue	150	Cast Iron	80	73	20
23666	HA14W13290	HA14C009	HA14C007	Walnut Street South	150	Cast Iron	80	101	20
23664	HA14W13291	HA14C006	HA14C007	Walnut Street South	150	Cast Iron	80	100	20
23663	HA14W13292	HA14C002	HA14C006	Walnut Street South	150	Cast Iron	80	167	20
28902	HA14W22892	HA14T045	HA14T039	Forest Avenue	300	Cast Iron	130	123	20
23721	HA14W23899	HA14C009	HA14T063	Forest Avenue	300	Cast Iron	130	105	20
33472	HA15W12654(1)(1)	HA15C018	HA15H025	Forest Avenue	300	Cast iron	80	25	20
33473	HA15W12654(1)(2)	HA15H025	HA15H026	Forest Avenue	300	Cast iron	80	143	20
33470	HA15W12654(2)	HA15H026	HA14C009	Forest Avenue	300	Cast iron	80	19	20
23574	HA15W12660	HA15R001(2)	HA15C018	Forest Avenue	300	Cast Iron	80	84	20





## **APPENDIX D – Fire Flow Results**

**Fire Flow Analysis - Proposed Development**

**MDD 2021 - Tank 50%**

Label	Zone	Fire Flow Iterations	Satisfies Fire Flow Constraints?	Fire Flow (Needed) (L/s)	Fire Flow (Available) (L/s)	Flow (Total Needed) (L/s)	Flow (Total Available) (L/s)	Pressure (Residual Lower Limit) (kPa)	Pressure (Calculated Residual) (kPa)	Is Fire Flow Run Balanced?
HA15H025	2	3	TRUE	150	178	150	178.02	138	138	TRUE
J-471	2	3	TRUE	150	170	155.39	175.83	138	138	TRUE

**MDD 2021 - Tank 75%**

Label	Zone	Fire Flow Iterations	Satisfies Fire Flow Constraints?	Fire Flow (Needed) (L/s)	Fire Flow (Available) (L/s)	Flow (Total Needed) (L/s)	Flow (Total Available) (L/s)	Pressure (Residual Lower Limit) (kPa)	Pressure (Calculated Residual) (kPa)	Is Fire Flow Run Balanced?
HA15H025	2	3	TRUE	150	185	150	184.72	138	138	TRUE
J-471	2	3	TRUE	150	177	155.39	182.19	138	138	TRUE

**MDD 2031 - Tank 50%**

Label	Zone	Fire Flow Iterations	Satisfies Fire Flow Constraints?	Fire Flow (Needed) (L/s)	Fire Flow (Available) (L/s)	Flow (Total Needed) (L/s)	Flow (Total Available) (L/s)	Pressure (Residual Lower Limit) (kPa)	Pressure (Calculated Residual) (kPa)	Is Fire Flow Run Balanced?
HA15H025	2	3	TRUE	150	168	150	168.06	138	138	TRUE
J-471	2	3	TRUE	150	163	155.39	168.65	138	138	TRUE

**MDD 2031 - Tank 75%**

Label	Zone	Fire Flow Iterations	Satisfies Fire Flow Constraints?	Fire Flow (Needed) (L/s)	Fire Flow (Available) (L/s)	Flow (Total Needed) (L/s)	Flow (Total Available) (L/s)	Pressure (Residual Lower Limit) (kPa)	Pressure (Calculated Residual) (kPa)	Is Fire Flow Run Balanced?
HA15H025	2	3	TRUE	150	175	150	174.5	138	138	TRUE
J-471	2	3	TRUE	150	169	155.39	174.85	138	138	TRUE



## APPENDIX E – System Pressures

## System Pressures - Proposed Development

### ADD 2021 - Tank 50%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 1 item>	143.89	404
33553	J-471	TRUE	102.34	2	1.96	<Collection: 1 item>	143.89	407

### ADD 2021 - Tank 75%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 1 item>	145.65	422
33553	J-471	TRUE	102.34	2	1.96	<Collection: 1 item>	145.65	424

### ADD 2031 - Tank 50%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	143.82	404
33553	J-471	TRUE	102.34	2	1.96	<Collection: 1 item>	143.82	406

### ADD 2031 - Tank 75%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	145.58	421
33553	J-471	TRUE	102.34	2	1.96	<Collection: 1 item>	145.58	423

### MDD 2021 - Tank 50%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	143.04	396
33553	J-471	TRUE	102.34	2	5.39	<Collection: 1 item>	143.05	398

### MDD 2021 - Tank 75%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	144.8	413
33553	J-471	TRUE	102.34	2	5.39	<Collection: 1 item>	144.81	416

### MDD 2031 - Tank 50%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	142.71	393
33553	J-471	TRUE	102.34	2	5.39	<Collection: 1 item>	142.72	395

### MDD 2031 - Tank 75%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	144.47	410
33553	J-471	TRUE	102.34	2	5.39	<Collection: 1 item>	144.48	412

### PHD 2021 - Tank 50%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	141.74	383
33553	J-471	TRUE	102.34	2	8.09	<Collection: 1 item>	141.75	386

### PHD 2021 - Tank 75%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	143.5	401
33553	J-471	TRUE	102.34	2	8.09	<Collection: 1 item>	143.51	403

### PHD 2031 - Tank 50%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	141.03	376
33553	J-471	TRUE	102.34	2	8.09	<Collection: 1 item>	141.04	379

### PHD 2031 - Tank 75%

ID	Label	Is Active?	Elevation (m)	Zone	Demand (L/s)	Demand Collection	Hydraulic Grade (m)	Pressure (kPa)
33471	HA15H025	TRUE	102.56	2	0	<Collection: 0 items>	142.79	394



## APPENDIX E – Flushing Results

Flushing Analysis - Proposed Development, ADD 2021, Tanks at 50%

ID	Label	Length (m)	Diameter (mm)	Flushing Event	Velocity (Maximum Flushing) (m/s)	Satisfies Flushing Target Velocity?	Shear Stress (Maximum Flushing) (kg/m <sup>2</sup> )	Satisfies Flushing Target Shear Stress?	Satisfies Flushing Target?
33554	HA15W12654(1)(2)(1)	20	300	Event - 1	1.12	TRUE	10.19	TRUE	TRUE
33555	HA15W12654(1)(2)(2)	123	300	Event - 1	1.09	TRUE	9.58	TRUE	TRUE



# Flushing Field Report


Study: Flushing Study

Legend	
	Valves to Open
	Valves to Close
	Flushing Hydrants
	Pipe Run
	Closed Pipes

# Flushing Field Report

Study: Flushing Study; Area: Forest; Event: Event - 1

Primary View



## Flushing Field Report

Study: Flushing Study; Area: Forest; Event: Event - 1

Fire Hydrant	Notes	Pressure (kPa) Static, Dynamic	Measured Flow (L/s)	Predicted Pressure (kPa)	Predicted Flow (L/s)
HA14C009				110	38.72
HA15H026				114	38.53

Valve	Operation	Notes	Flushing	Minimum	Recommended															
HA14W13290	Close <input type="checkbox"/>		Time (min)	2.2	2.2															
HA14W23899	Close <input type="checkbox"/>		Volume (ML)	0.0	0.0															
HA14W13250	Close <input type="checkbox"/>		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr><td>Start Time</td><td>_____</td></tr> <tr><td>End Time</td><td>_____</td></tr> <tr><td>Operator</td><td>_____</td></tr> <tr><td>Date</td><td>_____</td></tr> </table>			Start Time	_____	End Time	_____	Operator	_____	Date	_____							
Start Time	_____																			
End Time	_____																			
Operator	_____																			
Date	_____																			
	<input type="checkbox"/>																			
	<input type="checkbox"/>																			
	<input type="checkbox"/>																			
	<input type="checkbox"/>																			
	<input type="checkbox"/>																			
	<input type="checkbox"/>																			
	<input type="checkbox"/>		<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Water Quality</th> <th style="width: 20%;">Initial</th> <th style="width: 20%;">Final</th> </tr> </thead> <tbody> <tr> <td>Clear</td> <td style="text-align: center;"><input type="checkbox"/></td> <td style="text-align: center;"><input type="checkbox"/></td> </tr> <tr> <td>Colored</td> <td style="text-align: center;"><input type="checkbox"/></td> <td style="text-align: center;"><input type="checkbox"/></td> </tr> <tr> <td>Chlorine Residual</td> <td></td> <td></td> </tr> <tr> <td>Turbidity</td> <td></td> <td></td> </tr> </tbody> </table>			Water Quality	Initial	Final	Clear	<input type="checkbox"/>	<input type="checkbox"/>	Colored	<input type="checkbox"/>	<input type="checkbox"/>	Chlorine Residual			Turbidity		
Water Quality	Initial	Final																		
Clear	<input type="checkbox"/>	<input type="checkbox"/>																		
Colored	<input type="checkbox"/>	<input type="checkbox"/>																		
Chlorine Residual																				
Turbidity																				
<b>Pipe Run to be Cleaned</b>																				
HA15W12654(1)(2)(1), HA15W12654(1)(2)(2)																				

Notes \_\_\_\_\_

## Flushing Field Report

Study: Flushing Study; Area: Forest; Event: Event - 1

### Final Actions

Valve	Operation	Notes
HA14W13290	Reopen <input type="checkbox"/>	
HA14W23899	Reopen <input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	
	<input type="checkbox"/>	