

Operated Plant Hire

MAN 3.5 HIAB

Agile and efficient, the MAN 3.5 HIAB is a compact truck-mounted crane suited to light-to-medium duty lifting.

Overview



Built on a 3.5-tonne MAN TGE chassis, this vehicle offers excellent manoeuvrability combined with reliable lifting capability. Its compact size allows it to operate in tight urban environments while maintaining efficiency and safety.

Ideal for: Urban work, deliveries, and small-scale lifting operations



At a Glance

Specifications

- **Chassis:** MAN TGE 180 dropside 3.5 tonne
- **Crane:** Copma 35.3 remote control
- **Crane Capacity:** 355kg at 7.1m
- Rear mounted crane allows for loading of van or trailer
- **Train Weight:** 7t
- **Towing Capacity:** 3.5t

Key Features

- Loading of van body or trailer
- Remote control crane allows for exact positioning of critical infrastructure
- Suitable for restricted access
- Durable construction
- Flexible lifting applications

Contact Us



remoteaccess@auroraenergy.co



auroraenergy.co

Duty Chart – MAN 3.5 HIAB

